

Attachment to item number 5.1 -

Onsite - Wastewater Assessment

ONSITE-WASTEWATER ASSESSMENT

223 Carlton River Road Carlton February 2025





Development Application: 7.2023.17.2 -Response to Request For Information -223-227 Carlton River Road, Carlton - P2.pdf Plans Reference: P2 Date received: 17/03/2025

Disclaimer: The author does not warrant the information contained in this document is free from errors or omissions. The author shall not in any way be liable for any loss, damage or injury suffered by the User consequent upon, or incidental to, the existence of errors in the information.



Investigation Details

Client: Stargar PTY LTD

Site Address: 223 Carlton River Road, Carlton

Date of Inspection: 18/12/2024

Proposed Works: Wastewater system

Investigation Method: Hand Auger

Inspected by: JP Cumming

Site Details

Certificate of Title (CT): 126930/1

Title Area: Approx. 3.311 ha

Applicable Planning Overlays: Flood-prone Areas, Airport obstacle limitation area

Slope & Aspect: 2° SW facing slope

Vegetation: Mixed Flora

Ground Surface: Disturbed

Background Information

Geology Map: MRT 1:250000

Geological Unit: Quaternary Sediments

Climate: Annual rainfall 500mm

Water Connection: Tank

Sewer Connection: Unserviced-On-site required

Testing and Classification: AS2870:2011, AS1726:2017 & AS1547:2012



Investigation

A number of bore holes were completed to identify the distribution and variation of the soil materials at the site, bore hole locations are indicated on the site plan. See soil profile conditions presented below. Tests were conducted across the site to obtain bearing capacities of the material at the time of this investigation.

Wastewater Soil Profile Summary

Hole 1 Depth (m)	Horizon	Description
0.00 - 0.20	A1	Grey SAND (SP), single grain structure, slightly moist loose consistency, variable boundary to
0.20 - 1.30+	A2	Pale Grey SAND (SP), single grain structure, slightly moist, loose, no refusal.

Site Notes

Soils on these aeolian deposits are characterised by moderately deep sandy profiles. The anticipated subsoil permeability under saturated conditions from samples across the site is expected to be in the order of >3m/day.

Wastewater Classification & Recommendations

According to AS1547-2012 (on-site waste-water management) the natural soil is classified as **Sand** (category 1). It is proposed to install a dual-purpose septic tank with on-site absorption. A Design Loading Rate (DLR) of 20L/m²/day has been assigned for primary treated effluent.

The existing three-bedroom dwelling has a calculated maximum wastewater output of 600L/day. This is based on a tank water supply and a maximum occupancy of 5 people (120L/day/person). The existing septic system does not appear to be functioning therefore it is proposed that it be disconnected and decommissioned.

Using the DLR of $20L/m^2/day$, an absorption area of at least $30m^2$ will be required to accommodate the expected flows. This can be accommodated by one $15m \times 2m \times 0.6m$ terraced absorption trench connected to a dual-purpose septic tank (min 3000L). For all calculations please refer to the Trench summary reports. A cut-off drain will be required upslope of the absorption area and the area excluded from traffic or any future building works. A 100% reserve area should be set aside for future wastewater requirements.



To comply with the Southern Beaches On-site Waste Water and Stormwater Management Specific Area Plan of the Sorell Local Provisions Schedule:

SOR-S2.7.1 On-site waste water

Ac	ceptable Solutions	Comment
A1	Development must:	Non-compliance with
(a)	not cover more than 20% of the site;	A1 (e) See P1
(b)	not be located on land shown on an overlay map, as within:	
	(i) a flood-prone hazard area;	
	(ii) a landslip hazard area;	
	(iii) a coastal erosion hazard area;	
	(iv) a waterway and coastal protection area; or	
	(v) a coastal inundation hazard area;	
(c)	be located on a site with a soil depth of at least 1.5m;	
(d)	be located on a site where the average gradient of the land does not exceed 10%; and	
(e)	in the case of a dwelling, provide 65m^2 of land for wastewater land application area per bedroom which is located at least 1.5m from an upslope or side slope boundary and 5m from a downslope boundary.	

Performance Criteria	Comment
P1 The site must provide sufficient area for management of on-site waste water, having regard to:	Complies
(a)the topography of the site;	
(b) the capacity of the site to absorb wastewater;	
(c) the size and shape of the site;	
(d) the existing buildings and any constraints imposed by existing development;	
(e) the area of the site to be covered by the proposed development;	
(f) the provision for landscaping, vehicle parking,	
driveways and private open space;	
(g) any adverse impacts on the quality of ground, surface and coastal waters;	
(h) any adverse environmental impact on surrounding properties and the locality; and	
(i) any written advice from a suitably qualified person (onsite waste water management) about the adequacy of the on-site waste water management system.	



Design provisions have been made to address site constraints and manage risk including the use of subsurface application, assigning a conservative DLR and the designation of a 100% reserve area. It is therefore concluded that there is a low and acceptable risk of environmental impact and impact on human health from wastewater management on the site for the current proposal.

The following setback distances are required to comply with the Building Act 2016:

Upslope or level buildings: 3m

Downslope buildings: 6m

Upslope or level boundaries: 1.5m

Downslope boundaries: 4m

Downslope surface water: 100m

Compliance with Building Act 2016 Guidelines for On-site Wastewater Management Systems is outlined in the attached table.

During construction GES will need to be notified of any variation to the soil conditions or wastewater loading as outlined in this report.

Dr John Paul Cumming B.Agr.Sc (hons) PhD CPSS GAICD

Director







GES P/L

Land suitability and system sizing for on-site wastewater management

Trench 3.0 (Australian Institute of Environmental Health)

Assessment Report

Site assessment for on-site waste water disposal

Assessment for Stargar PTY LTD

Assess. Date

20-Feb-25

Ref. No.

Assessed site(s) 223 Carlton River Road, Carlton

Site(s) inspected

30-Jun-23

Local authority Sorell

Assessed by John Paul Cumming

This report summarises wastewater volumes, climatic inputs for the site, soil characteristics and sustem sizing and design issues. Capability and Environmental sensitivity issues are reported separately, where 'Alert' columns flag factors with high (A) or very high (AA) limitations which probably require special consideration for system design(s). Blank spaces on this page indicate data have not been entered into TRENCH.

Wastewater Characteristics

Wastewater volume (L/day) used for this assessment = 600

(using the 'No. of bedrooms in a dwelling' method)

Septic tank wastewater volume (L/day) = 200

Sullage volume (L/day) = 400

Total nitrogen (kg/year) generated by wastewater = 5.4

Total phosphorus (kg/year) generated by wastewater = 2.3

Climatic assumptions for site

(Evapotranspiration calculated using the crop factor method)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Mean rainfall (mm) "	39	32	45	35	42	53	33	49	46	44	43	43
Adopted rainfall (R, mm)	39	32	45	35	42	53	33	49	46	44	43	43
Retained rain (Rr, mm)	35	29	41	31	38	48	30	44	42	39	39	39
Max. daily temp. (deg. C)												
Evapotrans (ET, mm)	130	110	91	63	42	29	32	42	63	84	105	126
Evapotr. less rain (mm)	95	81	50	32	4	-18	2	-2	21	45	66	87

Annual evapotranspiration less retained rain (mm) = 463

Soil characterisitics

Texture = Sand

Category = 1

Thick. (m) = 2

Adopted permeability (m/day) = 3

Adopted LTAR (L/sq m/day) = 20

Min depth (m) to water = 3

Proposed disposal and treatment methods

Proportion of wastewater to be retained on site:

All wastewater will be disposed of on the site

The preferred method of on-site primary treatment: The preferred method of on-site secondary treatment:

In dual purpose septic tank(s)

The preferred type of in-ground secondary treatment:

In-ground

Trench(es)

The preferred type of above-ground secondary treatment: Site modifications or specific designs:

None Not needed

Suggested dimensions for on-site secondary treatment system

Total length (m) = 15

Width (m) =2

Depth (m) = 0.6

Total disposal area (sq m) required = 30

comprising a Primary Area (sq m) of: 30

and a Secondary (backup) Area (sq m) of:

Sufficient area is available on site

Comments

The assigned LTAR for the Category 1 soil present is 40L/m²/day with an absorption area of 30m² required for a typical threebedroom dwelling with a mains water supply.







GES P/L

Land suitability and system sizing for on-site wastewater management Trench 3.0 (Australian Institute of Environmental Health)

Site Capability Report Site assessment for on-site waste water disposal

Assessment for Stargar PTY LTD Assess. Date

Ref. No.

Assessed site(s) 223 Carlton River Road, Carlton

Site(s) inspected 30-Jun-23

Local authority Sorell

Assessed by John Paul Cumming

20-Feb-25

This report summarises data relating to the physical capability of the assessed site(s) to accept wastewater. Environmental sensitivity and system design issues are reported separately. The 'Alert' column flags factors with high (A) or very high (AA) site limitations which probably require special consideration in site acceptability or for system design(s). Blank spaces indicate data have not been entered into TRENCH.

				Confid	Limi	tation	
Alert	Factor	Units	Value	level	Trench	Amended	Remarks
Α	Expected design area	sq m	400	V. high	High		
	Density of disposal systems	/sq km	20	Mod.	Moderate		
	Slope angle	degrees	2	High	Very low		
	Slope form Co	onvex sprea	ading	High	Very low		
	Surface drainage		Good	High	Very low		
	Flood potential Site floods	s 1 in 75-10	00 yrs	High	Low		
	Heavy rain events	Infred	quent	High	Moderate		
	Aspect (Southern hemi.)	aces NE o	r NW	V. high	Low		
	Frequency of strong winds	Com	ımon	High	Low		
	Wastewater volume	L/day	600	High	Moderate		
	SAR of septic tank effluent		1.4	High	Low		
	SAR of sullage		2.5	High	Moderate		
	Soil thickness	m	2.0	V. high	Very low		
	Depth to bedrock	m	3.0	V. high	Very low		
	Surface rock outcrop	%	0	V. high	Very low		
	Cobbles in soil	%	0	V. high	Very low		
	Soil pH		6.5	High	Very low		
	Soil bulk density gm	/cub. cm	1.5	High	Low		
	Soil dispersion Eme	rson No.	8	V. high	Very low		
AA	Adopted permeability	m/day	3	Mod.	Very high		
	Long Term Accept. Rate L/c	day/sq m	20	High	Low		

Comments

The soils on site have good capacity to accept wastewater provided that secondary treatment of effluent is applied.







GES P/L

Land suitability and system sizing for on-site wastewater management Trench 3.0 (Australian Institute of Environmental Health)

Environmental Sensitivity ReportSite assessment for on-site waste water disposal

Assessment for Stargar PTY LTD

Assess, Date

20-Feb-25

Ref. No.

Rei

30-Jun-23

Assessed site(s) 223 Carlton River Road, Carlton Local authority Sorell

Site(s) inspected

Assessed by John Paul Cumming

This report summarises data relating to the environmental sensitivity of the assessed site(s) in relation to applied wastewater. Physical capability and system design issues are reported separately. The 'Alert' column flags factors with high (A) or very high (AA) limitations which probably require special consideration in site acceptability or for system design(s). Blank spaces indicate data have not been entered into TRENCH.

				Confid	Limi	tation	
Alert	Factor Un	its	Value	level	Trench	Amended	Remarks
Α	Cation exchange capacity mmol/10	00g	30	High	High		
Α	Phos. adsorp. capacity kg/cub	m	0.3	High	High		
	Annual rainfall excess n	nm	-463	High	Very low		
	Min. depth to water table	m	3	High	Very low		
	Annual nutrient load	kg	7.7	High	Low		
	G'water environ. value Agric sensi	t/dom	irrig	V. high	Moderate		
000000000000000000000000000000000000000	Min. separation dist. required	m	3	High	Very low		
	Risk to adjacent bores						Factor not assessed
	Surf. water env. value Agric sensit/	dom c	drink	V. high	Moderate		
	Dist. to nearest surface water	m	300	V. high	Low		
AA	Dist. to nearest other feature	m	4	V. high	Very high		
200000000000000000000000000000000000000	Risk of slope instability	Ver	ylow	V. high	Very low		
	Distance to landslip	m	1000	V. high	Very low		

Comments

There is low risk of environmental degredation associated with the disposal of wastewater on this site.

Demonstration of wastewater system compliance to Building Act 2016 Guidelines for On-site Wastewater

Acceptable Solutions	Performance Criteria	Compliance
A1 Horizontal separation distance from a building to a land application area must comply with one of the following: a) be no less than 6m; or b) be no less than: (i) 3m from an upslope building or level building; (ii) If primary treated effluent to be no less than 4m plus 1m for every degree of average gradient from a downslope building; (iii) If secondary treated effluent and subsurface application, no less than 2m plus 0.25m for every degree of average gradient from a downslope building.	a) The land application area is located so that (i) the risk of wastewater reducing the bearing capacity of a building's foundations is acceptably low.; and (ii) is setback a sufficient distance from a downslope excavation around or under a building to prevent inadequately treated wastewater seeping out of that excavation	Complies with A1 (b) (i) Land application area will be located with a minimum separation distance of 3m from an upslope or level building. Complies with A1 (b) (ii) Land application area will be located with a minimum separation distance of 6m from a downslope building.
Horizontal separation distance from downslope surface water to a land application area must comply with (a) or (b) (a) be no less than 100m; or (b) be no less than the following: (i) if primary treated effluent 15m plus 7m for every degree of average gradient to downslope surface water; or (ii) if secondary treated effluent and subsurface application, 15m plus 2m for every degree of average gradient to down slope surface water.	 Horizontal separation distance from downslope surface water to a land application area must comply with all of the following: a) Setbacks must be consistent with AS/NZS 1547 Appendix R; b) A risk assessment in accordance with Appendix A of AS/NZS 1547 has been completed that demonstrates that the risk is acceptable. 	Complies with A2 (a) Land application area located > 100m from downslope surface water

A3	P3	
Horizontal separation distance from a property boundary to a land application area must comply with either of the following: (a) be no less than 40m from a property boundary; or (b) be no less than: (i) 1.5m from an upslope or level property boundary; and (ii) If primary treated effluent 2m for every degree of average gradient from a downslope property boundary; or (iii) If secondary treated effluent and subsurface application, 1.5m plus 1m for every degree	Horizontal separation distance from a property boundary to a land application area must comply with all of the following: (a) Setback must be consistent with AS/NZS 1547 Appendix R; and (b) A risk assessment in accordance with Appendix A of AS/NZS 1547 has been completed that demonstrates that the risk is acceptable.	Complies with A3 (b) (i) Land application area will be located with a minimum separation distance of 1.5m from an upslope or level property boundary Complies with A3 (b) (ii) Land application area will be located with a minimum separation distance of 4m from a downslope property boundary.
of average gradient from a downslope property boundary.		
A4	P4	
Horizontal separation distance from a downslope bore, well or similar water supply to a land application area must be no less than 50m and not be within the zone of influence of the bore whether up or	Horizontal separation distance from a downslope bore, well or similar water supply to a land application area must comply with all of the following:	Complies with A4 No bore or well identified within 50m
down gradient.	(a) Setback must be consistent with AS/NZS 1547 Appendix R; and	
	(b) A risk assessment completed in accordance with Appendix A of AS/NZS 1547 demonstrates that the risk is acceptable	

Vertical separation distance between groundwater and a land application area must be no less than: (a) 1.5m if primary treated effluent; or (b) 0.6m if secondary treated effluent	P5 Vertical separation distance between groundwater and a land application area must comply with the following: (a) Setback must be consistent with AS/NZS 1547 Appendix R; and (b) A risk assessment completed in accordance with Appendix A of AS/NZS 1547 that demonstrates that the risk is acceptable	Complies with A5 (a) No groundwater encountered
A6 Vertical separation distance between a limiting layer and a land application area must be no less than: (a) 1.5m if primary treated effluent; or (b) 0.5m if secondary treated effluent	P6 Vertical setback must be consistent with AS/NZS1547 Appendix R.	Complies with A6 (a)
A7 nil	P7 A wastewater treatment unit must be located a sufficient distance from buildings or neighbouring properties so that emissions (odour, noise or aerosols) from the unit do not create an environmental nuisance to the residents of those properties	Complies



AS1547:2012 – Loading Certificate – Septic System Design

This loading certificate sets out the design criteria and the limitations associated with use of the system.

Site Address: 223 Carlton River Road, Carlton

System Capacity: 5 people @ 120L/person/day

Summary of Design Criteria

DLR: $20L/m^2/day$.

Absorption area: 30m²

Reserve area location /use: Assigned

Water saving features fitted: Standard fixtures

Allowable variation from design flows: 1 event @ 200% daily loading per quarter

Typical loading change consequences: Expected to be minimal due to capacity of system and site area (provided loading changes within 25% of design)

Overloading consequences: Continued overloading may cause hydraulic failure of the absorption area and require upgrading/extension of the area. Risk considered acceptable due to visible signs of overloading and owner monitoring.

Underloading consequences: Lower than expected flows will have minimal consequences on system operation unless the house has long periods of non occupation. Under such circumstances additional maintenance of the system may be required. Risk considered acceptable.

Lack of maintenance / monitoring consequences: Issues of underloading/overloading and condition of the absorption area require monitoring and maintenance, if not completed system failure may result in unacceptable health and environmental risks. Septic tank de-sludging must also be monitored to prevent excessive sludge and scum accumulation. Monitoring and regulation by the property owner required to ensure compliance.

Other operational considerations: Owners/occupiers must be aware of the operational requirements and limitations of the system, including the following; the absorption area must not be subject to traffic by vehicles or heavy stock and should be fenced if required. The absorption area must be kept with adequate grass cover to assist in evapotranspiration of treated effluent in the absorption trenches. The septic tank must be desludged at least every 3 years, and any other infrastructure such as septic tank outlet filters must also be cleaned regularly (approx. every 6 months depending upon usage). Foreign materials such as rubbish and solid waste must be kept out of the system.

CERTIFICATE OF THE RESPONSIBLE DESIGNER

Section 94 Section 106 Section 129 Section 155

To:	Stargar PTY LTD	Owner name	25			
	223 Carlton River Road			Address	Form 35	
	Carlton		7173	Suburb/postcode		
Designer detail	e.					
	5.			1		
Name:	John-Paul Cumming			Category:	Bld. Srvcs. Dsgnr Hydraulic	
Business name:	Geo-Environmental Solutions	3		Phone No:	03 6223 1839	
Business address:	29 Kirksway Place					
	Battery Point		7004	Fax No:	N/A	
Licence No:	CC774A Email ac	ddress: of	ffice@geos	olutions.net.au		
Details of the p	roposed work:					
Owner/Applicant	Stargar PTY LTD			Designer's project	[‡] J8849	
Address:	223 Carlton River Road			Lot No:	126930/1	
	Carlton		7173	_]	.2000.	
Type of work:	Building wo	rk 🗍		」 Plumbing work	X (X all applicable)	
Description of wor	rk:			_	[(A all applicable)	
	management system - design Design Work (Scope, limitat	ions or e	xclusions	re-t wa sto. on- ma bac	dition / repair / removal / erection ater / sewerage / rmwater / site wastewater nagement system / ckflow prevention / other) certificates)	
Certificate Type:	Certificate		Re	sponsible Prac	titioner	
	☐ Building design			chitect or Buildin		
	☐ Structural design		En	gineer or Civil D	esigner	
	☐ Fire Safety design		Fire Engineer			
	☐ Civil design		Civ	il Engineer or C	ivil Designer	
			Bu	ilding Services [Designer	
	☐ Fire service design		Bu	ilding Services [Designer	
	☐ Electrical design			ilding Services [
	☐ Mechanical design		Bu	ilding Service D	esigner	
	☐ Plumbing design			ımber-Certifier; / esigner or Engin	Architect, Building eer	
	☐ Other (specify)					
Deemed-to-Satisfy:	×	Perform	ance Solut	ion: 🔲 (X the a	appropriate box)	
Other details:		1				
Septic tank and abs	sorption trench					
Design docume	Design documents provided:					

The following documents are provided with this Certificate – Document description: Date: Feb-25 Drawing numbers: Prepared by: Geo-Environmental Solutions Schedules: Prepared by: Date: Prepared by: Geo-Environmental Solutions Date: Feb-25 Specifications: Computations: Prepared by: Date: Performance solution proposals: Prepared by: Date: Prepared by: Geo-Environmental Solutions Test reports: Date: Feb-25 Standards, codes or guidelines relied on in design process: AS1547:2012 On-site domestic wastewater management. AS3500 (Parts 0-5)-2013 Plumbing and drainage set. Any other relevant documentation: Onsite Wastewater Assessment - 223 Carlton River Road, Carlton - Feb-25

Onsite Wastewater Assessment - 223 Carlton River Road, Carlton - Feb-25

Attribution as designer:

I John-Paul Cumming, am responsible for the design of that part of the work as described in this certificate;

The documentation relating to the design includes sufficient information for the assessment of the work in accordance with the *Building Act 2016* and sufficient detail for the builder or plumber to carry out the work in accordance with the documents and the Act;

This certificate confirms compliance and is evidence of suitability of this design with the requirements of the National Construction Code.

	Name: (print)	Signed	Date
Designer:	John-Paul Cumming		20/02/2025
Licence No:	CC774A		

Assessment of Certifiable Works: (TasWater)

Note: single residential dwellings and outbuildings on a lot with an existing sewer connection are not considered to increase demand and are not certifiable.

If you cannot check ALL of these boxes, LEAVE THIS SECTION BLANK.

TasWater must then be contacted to determine if the proposed works are Certifiable Works.

I confirm that the proposed works are not Certifiable Works, in accordance with the Guidelines for TasWater CCW Assessments, by virtue that all of the following are satisfied:

	, ,
Х	The works will not increase the demand for water supplied by TasWater
Х	The works will not increase or decrease the amount of sewage or toxins that is to be removed by or discharged into, TasWater's sewerage infrastructure
Х	The works will not require a new connection, or a modification to an existing connection, to be made to TasWater's infrastructure
Х	The works will not damage or interfere with TasWater's works
Х	The works will not adversely affect TasWater's operations
Х	The work are not within 2m of TasWater's infrastructure and are outside any TasWater easement
Х	I have checked the LISTMap to confirm the location of TasWater infrastructure
	If the property is connected to TasWater's water system, a water meter is in place, or has been

Certification:

applied for to TasWater.

I John-Paul Cumming...... being responsible for the proposed work, am satisfied that the works described above are not Certifiable Works, as defined within the Water and Sewerage Industry Act 2008, that I have answered the above questions with all due diligence and have read and understood the Guidelines for TasWater CCW Assessments.

Note: the Guidelines for TasWater Certification of Certifiable Works Assessments are available at: www.taswater.com.au

Name: (print)

Signed

Date

Designer:

John-Paul Cumming

20/02/2025





Do not scale from these drawings. Dimensions to take precedence over scale.

Stargar PTY LTD Lot 1 223 Carlton River Road C.T.: 126929/1 PID: 5914397

Date: 20/02/2025

Drawing Number:

Sheet 1 of 1 Drawn by: LR

Design notes:

Do not scale from these drawings. Dimensions to take precedence

over scale.

- 1. Absorption trench dimensions of up to 20m long by 0.45m deep by 2m wide total storage volume calculated at average 35% porosity.
- 2.Base of trenches to be excavated level and smearing and compaction avoided.
- 3.350-410mm Arch should be placed in the centre of trench
- 4.Geotextile or filter cloth to be placed over the distribution arch to prevent clogging


Geo-Environmental Solutions

- 5.Construction on slopes up to 20% to allow trench depth range 720mm upslope edge to 450mm on down slope edge
- 6.Dispersive soils gypsum to be incorporated into the base of the trench at a rate of 1kg/m²
- 7.All works on site to comply with AS3500 and Tasmanian Plumbing code.



29 Kirksway Place, Battery Point T| 62231839 E| office@geosolutions.net.au


Sheet 1 of 1



Terraced Absorption Trench Detail



29 Kirksway Place, Battery Point T| 62231839 E| office@geosolutions.net.au



Tas Figure C2D6 Alternative Venting Arrangements

Vents must terminate in accordance with AS/NZS 3500.2

Alternative venting to be used by extending a vent to terminate as if an upstream vent, with the vent connection between the last sanitary fixture or sanitary appliance and the on-site wastewater management system. Use of a ground vent in not recommended

Inspection openings must be located at the inlet to an on-site wastewater management system treatment unit and the point of connection to the land application system and must terminate as close as practicable to the underside of an approved inspection opening cover installed at the finished surface level

Access openings providing access for desludging or maintenance of on-site wastewater management system treatment unites must terminate at or above finished surface level

Do not scale from these drawings.
Dimensions to take precedence
over scale