

NOTICE OF PROPOSED DEVELOPMENT

Notice is hereby given that an application has been made for planning approval for the following development:

SITE: 12 Oakmont Road, Midway Point

**PROPOSED DEVELOPMENT:
DWELLING AND GARAGE**

The relevant plans and documents can be inspected at the Council Offices at 47 Cole Street, Sorell during normal office hours, or the plans may be viewed on Council's website at www.sorell.tas.gov.au until **Friday 9th May 2025**.

Any person may make representation in relation to the proposal by letter or electronic mail (sorell.council@sorell.tas.gov.au) addressed to the General Manager. Representations must be received no later than **Friday 9th May 2025**.

APPLICANT: Play Co Pty Ltd

APPLICATION NO: DA 2024 / 307 1

DATE: 17 April 2025

Part B: Please note that Part B of this form is publicly exhibited.

Full description of Proposal:	Use: single dwelling
	Development: 2 storey dwelling with double garage
	<i>Large or complex proposals should be described in a letter or planning report.</i>
Design and construction cost of proposal:	\$ \$850,000+gst

Is all, or some the work already constructed:	No: <input checked="" type="checkbox"/> Yes: <input type="checkbox"/>
---	---

Location of proposed works:	Street address: 12 Oakmont Road
	Suburb: Midway Point Postcode: TAS 7171
	Certificate of Title(s) Volume: Folio:


Current Use of Site	residential
---------------------	--------------------

Current Owner/s:	Name(s) Rowville Warehouse Pty Ltd
------------------	---

Is the Property on the Tasmanian Heritage Register?	No: <input checked="" type="checkbox"/> Yes: <input type="checkbox"/>	<i>If yes, please provide written advice from Heritage Tasmania</i>
Is the proposal to be carried out in more than one stage?	No: <input checked="" type="checkbox"/> Yes: <input type="checkbox"/>	<i>If yes, please clearly describe in plans</i>
Have any potentially contaminating uses been undertaken on the site?	No: <input checked="" type="checkbox"/> Yes: <input type="checkbox"/>	<i>If yes, please complete the Additional Information for Non-Residential Use</i>
Is any vegetation proposed to be removed?	No: <input checked="" type="checkbox"/> Yes: <input type="checkbox"/>	<i>If yes, please ensure plans clearly show area to be impacted</i>
Does the proposal involve land administered or owned by either the Crown or Council?	No: <input checked="" type="checkbox"/> Yes: <input type="checkbox"/>	<i>If yes, please complete the Council or Crown land section on page 3</i>
If a new or upgraded vehicular crossing is required from Council to the front boundary please complete the Vehicular Crossing (and Associated Works) application form https://www.sorell.tas.gov.au/services/engineering/		

 Sorell Council Development Application: Development application 12 Oakmont Road, Midway Point.pdf Plans Reference: P1 Date Received: 22/11/2024

Part B continued: Please note that Part B of this form is publicly exhibited

Declarations and acknowledgements	
<ul style="list-style-type: none">I/we confirm that the application does not contradict any easement, covenant or restriction specified in the Certificate of Title, Schedule of Easements or Part 5 Agreement for the land.I/we consent to Council employees or consultants entering the site and have arranged permission and/or access for Council's representatives to enter the land at any time during normal business hours.I/we authorise the provision of a copy of any documents relating to this application to any person for the purposes of assessment or public consultation and have permission of the copyright owner for such copies.I/we declare that, in accordance with s52(1) of the <i>Land Use Planning and Approvals Act 1993</i>, that I have notified the owner(s) of the intention to make this application.I/we declare that the information in this application is true and correct. <p><i>Details of how the Council manages personal information and how you can request access or corrections to it is outlined in Council's Privacy Policy available on the Council website.</i></p> <ul style="list-style-type: none">I/we acknowledge that the documentation submitted in support of my application will become a public record held by Council and may be reproduced by Council in both electronic and hard copy format in order to facilitate the assessment process, for display purposes during public exhibition, and to fulfil its statutory obligations. I further acknowledge that following determination of my application, Council will store documentation relating to my application in electronic format only. <ul style="list-style-type: none">Where the General Manager's consent is also required under s.14 of the <i>Urban Drainage Act 2013</i>, by making this application I/we also apply for that consent.	
Applicant Signature:	Signature:  Date: 20.11.2024

Crown or General Manager Land Owner Consent	
<p>If the land that is the subject of this application is owned or administered by either the Crown or Sorell Council, the consent of the relevant Minister or the Council General Manager whichever is applicable, must be included here. This consent should be completed and signed by either the General Manager, the Minister, or a delegate (as specified in s52 (1D-1G) of the <i>Land Use Planning and Approvals Act 1993</i>).</p> <p>Please note:</p> <ul style="list-style-type: none">If General Manager consent is required, please first complete the General Manager consent application form available on our website www.sorell.tas.gov.auIf the application involves Crown land you will also need a letter of consent.Any consent is for the purposes of making this application only and is not consent to undertaken work or take any other action with respect to the proposed use or development.	
<p>I _____ being responsible for the administration of land at _____ declare that I have given permission for the making of this application for _____</p>	
Signature of General Manager, Minister or Delegate:	Signature: _____ Date: _____





Statewide Geotechnics

ABN 93 844 683 471

55 Leonard Avenue
Moonah TAS 7009

Telephone: 0499 498 337
Email: statewidegeo@gmail.com

SITE CLASSIFICATION & DISPERSIVE SOIL ASSESSMENT REPORT

Proposed Residential Development
12 Oakmont Road, Midway Point

Prepared for: Stronghold Engineers Pty Ltd

Date of investigation: 5th January 2025

Date of report: 27th January 2025

Prepared by: Drew Bedelph, Engineering Geologist

Table of Contents

1.	Introduction	1
2.	Site Conditions	2
3.	Field Investigation	2
4.	Dispersive Soil Assessment	3
5.	Site Classification	3
6.	Discussion and Recommendations	3
6.1	Dispersive Soil Management	3
6.2	Foundation Design	4
7.	Wind Classification	5

Figures

1. Figure 1 – Site Layout and Test Location Plan

Appendices

1. Appendix A – Borehole Logs and Descriptive Terms
2. Appendix B – Form 55 Certificate of Qualified Person
3. Appendix C – DPIPWE Technical Reference Manual '*Dispersive Soils and their Management*'

© 2025 Statewide Geotechnics

*This document and its attachments is the property of **Statewide Geotechnics**. This document and its attachments may only be used for the purpose for which it was requested and in accordance with any agreement between **Statewide Geotechnics** and the client. Any unauthorised use of this document is prohibited.*

1. Introduction

At the request of Jeremy Lin of Stronghold Engineers Pty Ltd, Statewide Geotechnics have undertaken a geotechnical investigation at the site of a proposed residential development at 12 Oakmont Road, Midway Point (Title Reference 185905/38, Property ID 9375744).

The investigation has been conducted for the purposes of assessing general subsurface conditions at the site and consequently assigning a Site Classification in accordance with AS2870-2011: '*Residential Slabs and Footings*', assigning a Wind Classification in accordance with AS4055-2012: '*Wind Loads for Housing*', and providing an assessment and management plan for dispersive soils to satisfy the *Tasmanian Planning Scheme – Sorell Local Provisions Schedule*, specifically Clause SOR-S1.8 'Development Standards for Subdivision', the objective of which is to ensure that subdivision within an area of potentially dispersive soils minimises the potential for development to cause:

- (a) erosion; and
- (b) risk to property and the environment.

There is no acceptable solution. Performance Criteria P1 prescribes that "Each lot, or a lot proposed in a plan of subdivision, must minimise the risks associated with dispersive soil to property and the environment, having regard to:

- (a) the dispersive potential of soils in the vicinity of proposed building areas, driveways, services and the development area generally;
- (b) the potential of the subdivision to affect or be affected by erosion, including gully and tunnel erosion;
- (c) the dispersive potential of soils in the vicinity of water drainage lines, infiltration areas and trenches, water storages, ponds, dams and disposal areas;
- (d) the level of risk and potential consequences for property and the environment from potential erosion, including gully and tunnel erosion;
- (e) management measures that would reduce risk to an acceptable level; and
- (f) the advice contained in a dispersive soil management plan".

2. Site Conditions

The subject property comprises an approximately 573m² vacant allotment within a newly-developed subdivision and is situated on the corner of Oakmont Road and Inverness Street at Midway Point. The site slopes at a gentle angle towards the west and, at the time the investigation was undertaken, was noted to be devoid of vegetation.

The 1:250,000 scale regional geology map of SE Tasmania, published by Mineral Resources Tasmania ('MRT'), shows the geology of the site and surrounds to be underlain by a surface covering of Quaternary age sand overlying insitu Triassic age quartz sandstone rock.

The Tasmanian State Government's interactive planning scheme map viewer, 'iPlan', indicates that the site and surrounds is underlain by "*potentially dispersive soil*" as a consequence of the prevailing Triassic age sandstone and derived soils.

Examination of the 1:25,000 scale MRT Landslide Hazard Band map of the Midway Point area indicates that the site is situated within an 'Unclassified' area which is deemed acceptable for building without further investigation.

3. Field Investigation

The field investigation was conducted on the 5th January 2025 and involved a detailed site inspection followed by the drilling of two boreholes to refusal depths of between 1.20m and 1.40m in using a Proline drilling rig. The strength of subsurface materials encountered within the investigation boreholes were assessed down-hole, where possible, using a hand shear vane.

The locations of the boreholes are shown on attached Figure 1, whilst copies of the borehole logs and descriptive terms used are provided in Appendix A.

The boreholes encountered uniform subsurface conditions at the site, comprising a surface layer of loose to moderately dense sandy topsoil to 0.30m underlain by stiff to very stiff medium plasticity residual clay, coloured brown. Weathered sandstone rock, presenting as dense to very dense clayey sand was encountered in the lowermost 0.30m of both holes, with refusal being met on hard material interpreted to be MW or better insitu sandstone at a depth of 1.40m in BH1 and 1.20m in BH2. The boreholes were both found to be dry on completion.

These findings are in general agreement with both the 1:25,000 scale geological map of the area and the findings of investigations conducted on nearby allotments.

4. Dispersive Soil Assessment

Two samples of residual clay encountered in the field investigation were subjected to Emerson Class Number dispersion testing to determine the dispersiveness of the on-site materials.

Both samples yielded an Emerson Class 2 (2), indicating slightly dispersive material. The results are consistent with the visual analysis of the materials made at the time the field investigation was undertaken.

The findings of the field and laboratory tests indicate that there is a low risk associated with dispersive soils and potential erosion on the site. On this basis it is assessed that the development will not negatively impact the site and surrounds and is therefore deemed to satisfy conditions (a) – (d) of section E21.7.1 P1 of the *Sorell Interim Planning Scheme* (2015), provided the recommendations provided in Section 6 below are adhered to.

5. Site Classification

After considering the site geology, drainage, soil conditions and plasticity characteristics of the subsurface materials encountered, the site has been classified as follows:

CLASS M (AS2870-2011)

Notwithstanding this, and in the instance that deeper footings are designed to found on or in the insitu sandstone rock layer encountered at 1.20m-1.40m depth below existing ground level, footings may be proportioned for a **CLASS A** site.

Foundation designs in accordance with this classification are to be subject to the overriding conditions of Section 6 below.

This classification is applicable only for ground conditions as encountered at the time of this investigation. If cut or fill earthworks are undertaken, or other works that alter the conditions of the site, then the Site Classification may need to be reassessed.

6. Discussion and Recommendations

6.1 Dispersive Soil Management

The following management measures are recommended for development on the site:

- As far as possible, minimise soil disturbance and avoid leaving areas of bare soil exposed during and after construction;
- As far as possible, use alternatives to 'cut and fill' construction, such as pier and post foundations;
- Where possible, avoid the use of trenches for the supply of services i.e. water & power. If trenches must be used, ensure that repacked spoil is properly compacted, treated with gypsum at rate of 1Kg/m² and topsoiled. Where possible, trenches to be placed shallow in the surface soil layer and mounded over to achieve the required cover depth. If buried, the trench must be backfilled in layers of no more than 200mm with clay with 5% by weight gypsum added. The trench must be finished with at least 150mm depth of non-dispersive suitable topsoil and finished to a level at least 75mm above natural ground to allow for possible settlement;
- All stormwater runoff from the dwelling to be directed to Council mains;
- Ensure runoff from hard areas is adequately captured and not allowed to flow across the ground surface or pond in low areas of the site;
- Drainage of any site cut must not employ conventional rock drain construction; it must adhere to recommendations for dispersive soils, unless founded entirely in rock;
- Establish and maintain vegetation cover on exposed areas of ground, and if any bare area of soil develops then it must be top-dressed with suitable topsoil and additional vegetation planted; and
- Ensure that excavated spoils are not reused on site in landscaping unless the material is appropriately treated with gypsum, compacted, and capped with natural soil and gypsum.

The client's attention is drawn to the Tasmanian Department of Primary Industries, Water and Environment technical reference manual '*Dispersive Soils and their Management*' (2009) as a guide to undertaking works on the site, a copy of which is attached herein in Appendix C.

6.2 Foundation Design

Specific attention and consideration should be given to the design of footings as required by AS2870-2011.

In addition to the normal founding requirements arising from the above classification, particular conditions at the site determine that the founding medium for all footings should be as follows:

**Silty CLAY, medium plasticity, trace gravel, brown,
encountered between 0.30m below existing ground level.**

An allowable bearing pressure of 100kPa is available for edge beams, strips and pads founded as above, provided the site is prepared as follows:

1. Earthworks should be carried out in accordance with AS3798-2007 '*Earthworks for Residential and Commercial Developments*';
2. Any organics or other deleterious materials should be removed from the building footprint;
3. Any floating boulders encroaching on the building footprint and preventing a uniform founding medium from being established should be removed and replaced with lean-mix concrete; and
4. Any sands or granular materials disturbed in bases of footing excavations should be compacted.

The Site Classification in Section 5 assumes that the natural drainage and infiltration conditions at the site will not be significantly affected for the proposed development work on the site. The client must take care to ensure that surface water is not permitted to collect adjacent to the structure and that significant changes to seasonal soil moisture equilibria do not develop as a result of service trench construction or tree root action.

The client's attention is drawn to Appendix B of AS2870 and CSIRO Building Technical File BTF18-2011 '*Foundation Maintenance and Footing Performance: A Homeowner's Guide*' as a guide to maintenance requirements for the proposed structure on the Site.

Although the auger hole data indicates that the site conditions are relatively uniform, variations in soil conditions may occur in areas of the site not specifically covered by the field investigation. The base of all footings should therefore be inspected to ensure that the founding medium meets the requirements referenced herein with respect to type and strength of founding material.

7. Wind Classification

After considering the terrain, shielding and topography of the site, the site has been classified as follows:

N2 (AS4055-2012)

FIGURE 1

Site Layout and Test Location Plan



BH1
 ● Approximate borehole location

Drawn	DB
Approved	
Date	27/01/2025
Scale	Not to scale
Original size	A4



Client:	Stronghold Engineers Pty Ltd	
Project:	Dispersive soil assessment and Site Classification, 12 Oakmont Road Midway Point	
Title:	Site Layout and Test Location Plan	
Project no:	SC855	Figure no: Figure 1

APPENDIX A

Borehole Logs and Descriptive Terms



Engineering Log - Borehole

Borehole no:	BH1
Sheet	1 of 1

Client: Stronghold Engineers Pty Ltd	Hole commenced: 5/01/2025
Project Name: Site Classification - 12 Oakmont Road, Midway Point	Hole completed: 5/01/2025
Project No: SC855	Hole logged by: DGB
Hole Location: Refer site layout and test location plan	Log checked by: DGB

Drill Model and Mounting:	Proline rig	Slope: deg.	R.L. Surface	Operator: DGB
Hole Diameter: 100	mm	Bearing: deg.	Datum	

Drilling Information								Rock Substance							Observations			
Method	Penetration			Support	Water	Sample Tests	Depth meters	Graphic Log	Classification symbol	Material plasticity or particle characteristics, colour, secondary and minor component	Soil type:	Moisture condition	Consistency, density index	Pocket Penetrometer		Structure and additional observations		
	1	2	3											100	200		300	400
AS									SM	Silty SAND, fine to medium grained, grey		D/M	L/MD					Topsoil
									CH	Silty CLAY, medium plasticity, some fine to medium sand, brown		M	St					Residual soil
						D	0.50											
													VSt					
						D	1.00											
									SC	Clayey SAND, fine to medium, trace gravel, yellow-brown		M	D					XW/HW Triassic sandstone
						D							VD					
							1.50			Auger refusal - borehole terminated at 1.40m depth								Dry on completion
							2.00											
							2.50											
							3.00											
							3.50											
							4.00											

Method C - Casing M - Mud Penetration  Graphic Log 	Support C - Casing M - Mud Penetration No Resistance Ranginf to Refusal Graphic Log Inflow Outflow Water Level	Samples and Tests U60 Undisturbed Sample U50 50mm Diameter D Disturbed Sample N Standard Penetration N* SPT + Sample NC Cone Penetrometer Classification Symbols and Soil Description - Based on Unified Soil Classification System	Moisture Condition D Dry M Moist W Wet Plastic Limit < PL = PL > PL	Consistency/ relative rock density VS - Very Soft S - Soft F - Firm St - Stiff VSt - Very Stiff H - Hard Fb - Friable VL - Very Loose L - Loose MD - Moderately Dense VD - Very Dense
--	--	--	--	---



Engineering Log - Borehole

Borehole no:	BH2
Sheet	1 of 1

Client:	Stronghold Engineers Pty Ltd	Hole commenced:	5/01/2025
Project Name:	Site Classification - 12 Oakmont Road, Midway Point	Hole completed:	5/01/2025
Project No:	SC855	Hole logged by:	DGB
Hole Location:	Refer site layout and test location plan	Log checked by:	DGB

Drill Model and Mounting:	Proline rig	Slope:	deg.	R.L. Surface
Hole Diameter:	100 mm	Bearing:	deg.	Datum
				Operator:
				DGB

Drilling Information								Rock Substance							Observations
Method	Penetration			Support	Water	Sample Tests	Depth meters	Graphic Log	Classification symbol	Material plasticity or particle characteristics, colour, secondary and minor component	Soil type:	Moisture condition	Consistency, density index	Pocket Penetrometer	Structure and additional observations
	1	2	3											100 200 300 400 500	
AS									SM	Silty SAND, fine to medium grained, grey		D/M	L/MD		Topsoil
									CH	Silty CLAY, medium plasticity, some fine to medium sand, brown		M	St		Residual soil
						D	0.50								
													VSt		
						D	1.00		SC	Clayey SAND, fine to medium, trace gravel, yellow-brown		M	D		XW/HW Triassic sandstone
						D							VD		
										Auger refusal - borehole terminated at 1.20m depth					Dry on completion
							1.50								
							2.00								
							2.50								
							3.00								
							3.50								
							4.00								

Method C - Casing M - Mud Penetration No Resistance Ranginf to Refusal  Graphic Log Inflow Outflow Water Level	Support C - Casing M - Mud Penetration No Resistance Ranginf to Refusal  Graphic Log Inflow Outflow Water Level	Samples and Tests U60 Undisturbed Sample U50 50mm Diameter D Disturbed Sample N Standard Penetration N* SPT + Sample NC Cone Penetrometer Classification Symbols and Soil Description - Based on Unified Soil Classification System	Moisture Condition D Dry M Moist W Wet Plastic Limit < PL = PL > PL	Consistency/ relative rock density VS - Very Soft S - Soft F - Firm St - Stiff VSt - Very Stiff H - Hard Fb - Friable VL - Very Loose L - Loose MD - Moderately Dense VD - Very Dense
--	---	--	--	---

DESCRIPTIVE TERMS - BOREHOLE/EXCAVATION LOG

Method

S auger screwing	W washbore	B blade bucket
D auger drilling	N natural exposure	C cable tool
R roller/tricone	E existing excavation	H hammer drill

Water

*	not observed
▼	observed water level
◀	observed water inflow
▶	observed water outflow
R	refer report for details

Notes, samples, tests, etc

U45	undisturbed sample, 45mm diameter
D	disturbed sample
N*	Standard Penetration Test
	N indicates SPT value
	* indicates sample retrieved

Structure, additional observations

PP	pocket penetrometer test, figure indicates soil strength (kPa)
V	vane shear test, figure indicates soil strength (kPa)
DCP	dynamic cone penetrometer test, figure indicates blows/depth increment.

Soil profile

known boundary	probable boundary	possible boundary
	-----	? _ ? _ ? _ ? _

Moisture condition

(based on appearance and feel)

dry (D)	Looks and feels dry, cohesive soils usually hard powdery or friable, granular soils run freely through the fingers.
moist (M)	Soils feel cool, darker in colour. Cohesive soils usually weakened by moisture, granular soils tend to cohere, no free water on hands.
wet (W)	Soils feel cool, darker in colour. Cohesive soils usually weakened, granular soils tend to cohere, free water collects on hands when remoulding.

Consistency

(based on undrained shear strength (C_u), estimated, or measured by vane shear test)

very soft	soft	firm	stiff	very stiff	hard
VS	S	F	St	VSt	H

C_u (kPa) 12.5 25 50 100 200

Density Index

(generally estimated or based on penetrometer results)

very loose	loose	medium dense	dense	very dense
VL	L	MD	D	VD

Density Index I_d (%) 15 35 65 85

APPENDIX B

Form 55 Certificate of Qualified Person

CERTIFICATE OF QUALIFIED PERSON – ASSESSABLE ITEM

Section 321

To: **Jeremy Lin** Owner /Agent
Stronghold Engineers Pty Ltd Address
Suburb/postcode

Form **55**

Qualified person details:

Qualified person: **Drew Bedelph T/A Statewide Geotechnics**

Address: **55 Leonard Avenue** Phone No: **0499498337**
MOONAH TAS **7009** Fax No: **-**

Licence No: **n/a** Email address: **statewidegeo@gmail.com**

Qualifications and Insurance details: **BSc (Hons) with major in Geology, Professional Indemnity Insurance (AIG Australia Ltd, policy number 1023401768, \$1,000,000 cover)** (description from Column 3 of the Director of Building Control's Determination)

Speciality area of expertise: **Engineering Geology** (description from Column 4 of the Director of Building Control's Determination)

Details of work:

Address: **12 Oakmont Road** Lot No: **38**
MIDWAY POINT TAS **7171** Certificate of title No: **185905**

The assessable item related to this certificate: **Dispersive soil assessment and foundation classification for proposed buildings in accordance with AS2870-2011** (description of the assessable item being certified)
Assessable item includes –

- a material;
- a design
- a form of construction
- a document
- testing of a component, building system or plumbing system
- an inspection, or assessment, performed

Certificate details:

Certificate type: **Foundation classification** (description from Column 1 of Schedule 1 of the Director of Building Control's Determination)

This certificate is in relation to the above assessable item, at any stage, as part of - (tick one)

building work, plumbing work or plumbing installation or demolition work: ☒

or

a building, temporary structure or plumbing installation: ☐

In issuing this certificate the following matters are relevant –

Documents:

Dispersive soil assessment and site classification report dated 27th January 2025 by Drew Bedelph, Statewide Geotechnics

Relevant
calculations:

Not applicable

References:

As per the assessment and site classification report dated 27th January 2025
Appendix B of AS2870-2011
CSIRO Building Technical File BTF-18-2011 'Foundation Maintenance and Footing Performance: A Homeowner's Guide'

Substance of Certificate: (what it is that is being certified)

An investigation was conducted for the purposes of assessing dispersive soils and general geological conditions at the site and consequently assigning a Site Classification in accordance with AS2870-2011: 'Residential Slabs and Footings'.

Scope and/or Limitations

The classification is applicable only for ground conditions encountered at the time of the investigation. If cut/fill earthworks are undertaken, or the structure/s moved from the site/s assessed, then further investigation and reclassification will be required.

I certify the matters described in this certificate.

Qualified person:

Signed:



Certificate No:

Date:

27/01/2025

APPENDIX C

DPIPWE Technical Reference Manual -

‘Dispersive Soils and their Management’

DISPERSIVE SOILS *and* *their* MANAGEMENT



Technical Reference Manual

Marcus Hardie
Land Management Officer
DPIW

With contributions from:

Richard Doyle - TIAR, UTAS, Hobart
Bill Cotching - TIAR, UTAS, Burnie
Tim Duckett - LMRS, Hobart
Peter Zund - NRM South, Hobart

TABLE OF CONTENTS

1.0	Introduction: Why dispersive soils and tunnel erosion are an issue.....	7
1.1	Environments in which dispersive soils and tunnel erosion occur.....	7
1.2	Tunnel erosion hazard mapping.....	8
2.0	Understanding dispersion and the erosion process.....	11
2.1	Sodicity and dispersion.....	11
2.2	Tunnel erosion.....	12
3.0	Identifying dispersive soils.....	13
3.1	Field techniques.....	15
3.2	Simple field test for identifying dispersive soils.....	15
3.3	Laboratory techniques for identifying dispersive soils.....	15
4.0	Approaches for minimising erosion risk in dispersive soils.....	16
4.1	Management options for tunnel erosion.....	17
4.2	Identification and avoidance of dispersive soils.....	17
4.3	Compaction.....	17
4.4	Chemical amelioration.....	18
4.5	Sand blocks and sand barriers.....	19
4.6	Use of topsoil / burial and revegetation.....	20
5.0	Activities that increase the risk of erosion on dispersive soils.....	21
5.1	Activities that promote tunnel erosion.....	22
5.2	Removal of topsoil.....	22
5.3	Cut and fill.....	22
5.4	Trenches and supply of services.....	23
5.5	Storm water and runoff.....	25
5.6	Roads and culverts.....	25
5.7	Sewage and grey water.....	27
5.8	Dam construction.....	28
6.0	Repair and rehabilitation of tunnel erosion.....	30
7.0	References.....	32
8.0	Appendix I: Analysis and classification of dispersive soils.....	35
9.0	Appendix II: Amendment to existing codes of practice & guidelines.....	37
9.1	Soil and Water Management Code of Practice for Hobart Regional Councils (1999b).....	38
9.2	Guidelines for Soil and Water Management (Anon 1999c).....	38

LIST OF FIGURES

Figure 1.	Exceptions always exist. (a). Tunnel erosion in shallow stony ground located on a side slope away from drainage lines. (b). Tunnel erosion in mature forest, Middleton. Tunnel erosion existed prior to felling of trees in the foreground.....	8
Figure 2.	Location of tunnel erosion prone dispersive soils (sodosols) in Southern Tasmania.....	9
Figure 3.	Map of land systems containing areas of tunnel erosion on private freehold land in Southern Tasmania (based on Grice 1995).....	10
Figure 4.	1:10000 Brighton Land Use Suitability Mapping (Cumming 2003).....	8
Figure 5.	Behaviour of non sodic and sodic soils in water: (Anon 1999a).....	12
Figure 6.	Sidewall collapse due to mechanical scouring and undercutting sidewalls.....	12
Figure 7.	Surface water entering an existing tunnel system, increasing the mechanical erosion and scoring.....	13
Figure 8.	Collapse of tunnel roof, following loss of dispersive soil horizon leading to formation of a stable depression.....	13
Figure 9	(a) Example of dribble pattern on an exposed subsoil, the photograph was taken from within an actively eroding tunnel system. (b) Dribble patterns on sodic soil ped.....	13
Figure 10.	'Pitting or pocketing', resulting from topsoil removal, surface water has dissolved through the soil surface.....	14
Figure 11.	Sediment fans or 'spew holes' are often the first obvious sign of tunnel erosion (a) Honeywood, (b). Woodbridge (c) Campania (d) Dunalley.....	14
Figure 12.	Field test for aggregate dispersion (Sorensen 1995).....	15
Figure 13.	The severity and depth of dispersive subsoils (or sodium content) can vary considerably over short distances. (a). Highly dispersive subsoils (orange) meters away from (b) non-dispersive soils (brown).....	17
Figure 14.	Modified sand block design. (a) plan view, (b) cross section view. The depth of the sand block is determined by the depth of dispersive clays or tunnel erosion. The span length of the structure is determined by the width of the tunnelling.....	19
Figure 15.	(a) Installation of sandblock perpendicular to a service trench. Note securing of geotextile to the optical fibre cable to prevent water flowing past the sand block. (b) Sandblock before final topsoiling.....	19
Figure 16.	Initiation of tunnel erosion caused by scalping or removing topsoil. Note that even a very thin layer of topsoil was able to prevent widespread tunnel erosion.....	22
Figure 17.	Extensive tunnel and rill erosion initiated by excavating a cut & fill pad for a large building on sodic soils.....	22
Figure 18.	Tunnel erosion in footings intended for a winery. Erosion resulted from ponding of rainwater on highly dispersive fill. (a). The fill contains a number of narrow slots (up to 1.2 meters deep) caused by surface water dissolving through the footing.....	22
Figure 19.	Pier or post style construction has considerably lower risk of initiating tunnel erosion than cut and fill techniques.....	23
Figure 20.	Hydrological barrier to isolate foundations from surface and groundwater (Duckett pers. comm.).....	23
Figure 21.	(a) Tunnel erosion initiated by installation of an optical fibre cable into a dispersive soil. (b) Subsidence and early stages of tunnelling resulting from inappropriate installation of power pole in a backfilled trench.....	24

Figure 22. Cable and pipe installation techniques. (a). Good technique, surface burial of pipe or cable ensuring that ponding cannot collect on or behind the mound. (b) Average technique, simple surface burial, however ponding can occur behind the mound. (c) Good technique, where topsoil depth allows partial burial.....	24
Figure 23. Improved trench design. (a). Traditional Trench. Note surface sinks allowing water to pond above trench. (b) Improved trench with individually compacted clay layers. The surface is finished above the ground surface to prevent ponding on top of the trench.....	25
Figure 24. Tunnel erosion resulting from construction of a stormwater culvert in dispersive clay, Brighton.....	25
Figure 25. Road surface breaking up due to construction on dispersive clays. This section of road is repaired 2-3 times a year.....	25
Figure 26. Undercutting and collapse of roadside batter due to construction of a table drain in dispersive clay. Note the failure of the rock rap (blue) to prevent further erosion.....	26
Figure 27. Table drain constructed in dispersive subsoil. The concentration of runoff in the culvert is greatly adding to the erosion problem, resulting in slumping and undercutting of the road and the adjacent batter slope. This photo was taken 18 months after the driveway was constructed.....	26
Figure 28. Rill and tunnel erosion caused by excavation of sodic soils for road construction. Dunalley.....	26
Figure 29. Alternative road design using road bars and diversion mounds to shed water into stable areas.....	26
Figure 30. Ozzi Kleen single tank (Aerated Wastewater Treatment System) for treatment and disposal of sewage and grey water; Raised – mulched area in foreground is being used for effluent disposal from the house in background.	27
Figure 31. Example of a composting toilet system. (source: www.nature-loo.com.au).....	28
Figure 32. The dam in the foreground has been constructed from dispersive clays. Note the cloudy brown colour of water in foreground, compared to the blue colour of the dam constructed from non-dispersive soils in the background...	28
Figure 33. Typical small dam failure. Note piping through earth bank.....	28
Figure 34. Piping failure of a dam constructed from soils derived from Permian mudstone. This dam is known to have failed on first filling. The image was taken from the dam floor; note the dam wall (background) has been completely breached.....	28
Figure 35. Failure of Blackman Creek dam (source: Davies Brothers). In October 2005 the Blackman creek dam failed, resulting in the evacuation of Tunbridge and loss of 3000 ML irrigation water. Doyle and Cumming (unpublished 2005) indicate the cause of the failure to be associated with a variably compacted - moderately dispersive soil layer.....	29
Figure 36. Examples of tunnel erosion control (a). Poor technique. Rock rap is usually an inappropriate erosion control technique for dispersive soils. Normally rock barriers work well to trap sediment and reduce erosion. However in dispersive soils, hard surfaces such as rock are quickly bypassed. Note (upper area) of the rock structure (b). Excellent technique. Note the entire repaired area is fenced, and the whole length of the repaired tunnel is covered with topsoil and jute cloth. Sand barrier have been construct every 20 meters down the slope.....	31
Figure 37. Good technique. Topsoil mounding, reclaimed tunnel erosion, Brighton. Note the width of earthworks required to fix a 50cm wide tunnel, and the raised profile to shed surface water: Jute Cloth would prevent surface erosion until vegetation has established.....	32
Figure 38. Emerson dispersion test procedure (AS 1289.3.8.1-1997) (Raine and Loch 2003). Soils with an Emerson ration of 1 or 2 are highly susceptible to tunnel erosion (Vacher <i>et al.</i> 2004).....	36
Figure 39. Pinhole test for compacted soils & fill. (Photo, Raine & Loch 2003).....	36

PURPOSE OF THIS DOCUMENT

Currently, there is little locally relevant or available information on the management of dispersive soils in urban and peri-urban environments. Issues associated with dispersive soils and their management are not adequately addressed in planning schemes, building codes or the development approval process. This document seeks to provide a summary of the available science and experience gained with the management of dispersive soils and tunnel erosion in Tasmania. It is expected this document will have relevance for a range of stakeholders including, professionals in the building and construction industry, local government, affected landholders and natural resource managers. It is important to acknowledge that advice provided in this document results from a process of expert opinion and field observation, rather than rigorous scientific study or an established body of locally relevant literature. This document will require updating as new information becomes available.

The purpose of this document is to,

- » Raise awareness of the risks associated with development and construction on dispersive soils.
- » Reduce the incidence of tunnel erosion and environmental harm resulting from disturbance of dispersive soils in Tasmania.
- » Indicate the types of environments in which tunnel erosion and dispersive soils occur.
- » Review chemical and physical analytical techniques used for identifying dispersive soils.
- » Identify risks associated with traditional construction techniques on dispersive soils.
- » Outline low-risk options for construction and development on dispersive soils.
- » Review methods for repairing tunnel erosion in peri-urban environments.

This document aims to reduce rather than eliminate risk associated with construction and development on dispersive soils. The advice presented in this document needs to be carefully considered together with other expert opinion in relation to specific sites on a case by case basis. Erosion processes in dispersive soils are complex and difficult to predict. No responsibility is taken for advice provided in this document.

The Crown in the right of the State of Tasmania does not accept responsibility for any loss or damage which may result to any person arising from reliance on all or any part of this information, whether or not that loss or damage has resulted from negligence or any other cause.

1.0 INTRODUCTION: WHY DISPERSIVE SOILS AND TUNNEL EROSION ARE AN ISSUE

- » Dispersive soils and tunnel erosion have been found in all municipalities in southern Tasmania, and several locations in northern Tasmania.
- » In recent years, urban expansion has occurred in areas known to contain dispersive soils.
- » Tunnel erosion in dispersive or sodic soils mostly occurs in areas with
 - Soils derived from Triassic sandstone or Permian mudstone.
 - Deep sedimentary soils.
 - North facing slopes.
 - Slopes over 10 degrees.
 - Drainage lines.
 - Areas in which vegetation, soils or local hydrology have been disturbed.
- » Tunnel erosion has the potential to result in considerable damage to infrastructure (including dwellings) and the environment.
- » The location or extent of dispersive soils has not been specifically mapped in Tasmania.
- » Existing soil maps and tunnel erosion hazard maps are unsuitable for land use planning and infrastructure development.

Dispersive soils and tunnel erosion occur in all municipalities in southern Tasmania, as well as parts of the Northern Midlands, Tamar Valley and Break O'Day municipalities. In recent years, urban expansion on dispersive soils has increased the incidence of infrastructure damage and environmental harm resulting from tunnel erosion. Unlike other forms of erosion, tunnel erosion results from a combination of both chemical and physical processes, which makes its control and repair difficult. Management of tunnel erosion is focused on both the prevention of further tunnel erosion and improved repair and management of existing tunnel affected land.

1.1 ENVIRONMENTS IN WHICH DISPERSIVE SOILS AND TUNNEL EROSION OCCUR

Crouch (1976) identified that landscapes which were predisposed to tunnel erosion had;

- » A seasonal or highly variable rainfall combined with high summer temperature.
- » Cracking of surface soils due to desiccation.
- » A reduction or detrimental change in vegetative cover.
- » A relatively impermeable layer in the soil profile.
- » Sufficient slope to create sub-surface flow.
- » A dispersible soil layer.

In Tasmania, tunnel erosion is commonly associated with dispersive subsoils derived from Triassic sandstone, or Permian mudstone (Colclough 1978, Doyle and Habraken 1993). However tunnel erosion is also known to occur on dispersive soils derived from Jurassic Dolerite (Bruny Island, Dunalley and Orielson) and Lower Carboniferous – Upper Devonian granites (Elephant Pass). Tunnel erosion mostly occurs on moderately steep (>10°) north or north-east facing slopes in areas with less than 650 mm annual rainfall. Tunnel erosion is less common in shallow soils or soils containing a high proportion of stones (exceptions exist, Figure 1a) and areas with greater than 800mm rainfall.



Figure 1a & b. Exceptions always exist. (a) Tunnel erosion in shallow stony ground located on a side slope away from drainage lines, Brighton. (b) Tunnel erosion in a mature forest, on dispersive soils derived from Triassic Sandstone, Middleton. Tunnel erosion existed prior to felling of trees in the foreground.

The nature and extent of tunnel erosion appears to differ between soil types. In soils derived from Permian sediments, tunnel erosion is usually confined to a single narrow 'slot' often within a drainage line. In soils derived from Triassic sediments, tunnels often have multiple branches and frequently occur on hillslopes as well as drainage lines. While tunnel erosion usually results from some form of disturbance, in a few instances tunnel erosion has occurred in otherwise undisturbed environments (Figure 1b).

1.2 TUNNEL EROSION HAZARD MAPPING

The location and extent of tunnel erosion in Tasmania has not been specifically mapped or investigated, however land system mapping indicates that approximately 103,000 ha of private freehold land has a tunnel erosion hazard (Grice 1995). Figure 2, the 'Location of tunnel erosion prone dispersive soils (sodic soils or sodosols) in Southern Tasmania (DPIWE 2004)' map has been created by modifying the Soil Orders Map of Tasmania 1: 500,000, (DPIWE 2004) to reveal the location of sodosols (soils with more than 6% sodium in the subsoil) as a predictor of dispersive soils. Figure 3 the 'Map of land systems containing areas of tunnel erosion on private freehold land in Southern Tasmania' has been generated from state-wide land systems mapping in which combinations of soil, geology and climate have been inferred to reveal areas which have an elevated likelihood that tunnel erosion may occur (Grice 1995). Note: neither of these maps indicate the actual location or extent of dispersive soils or tunnel erosion.

Tunnel erosion hazard maps in Figures 2 and 3 (pages 9-10) cannot be used for land use planning or making decisions on soil suitability for sub-division. Note that some areas indicated to have a dispersive soil or tunnel erosion hazard differ between the two maps. These discrepancies are expected, and result from differences in how the two maps were produced. Landuse planning, sub-division works and site development require field inspections and large scale soil mapping at 1:5,000 – 1:10,000 scale.

A local example of larger scale land suitability mapping for residential development was conducted in the Brighton municipality to identify soils which were unsuitable for urban development (Figure 4) (Cumming 2003). Similar landuse and erosion surveys have been used to quantify risk associated with urban development on erosion prone loess soils in the Port Hills, Christchurch, New Zealand (Trangmar 2003).




Figure 4. 1:10,000 Brighton Land Use Suitability Map (Cumming 2003).

Cumming (2003) notes 'The map is reliable only at the scale published, and must not be enlarged....'




Figure 2. Location of tunnel erosion prone dispersive soils (sodic soils or sodosols) in Southern Tasmania (DPIWE 2004).




Figure 3. Map of land systems containing areas of tunnel erosion on private freehold land in Southern Tasmania (based on Grice 1995).

2.0 UNDERSTANDING DISPERSION AND THE EROSION PROCESS

SODIC SOILS AND DISPERSION

- » Dispersion results from the presence exchangeable sodium between clay platelets.
- » Dispersion results in the swelling of clay platelets and collapse of clay aggregates.
- » Dispersion is often seen as 'muddy' or 'milky' water in dams and surface water.
- » Dispersion only occurs in non-saline water or rainwater.

TUNNEL EROSION RESULTS FROM

- » Both chemical and physical processes.
- » Dispersion of clay subsoils.
- » Sodic or dispersive subsoils coming into contact with fresh water (rain, runoff etc).
- » Soil cracks and pores which enable runoff and dispersed clays to flow through the soil.
- » Intense rainfall events on dry cracked soil, usually at the end of summer.
- » Loss of topsoil through erosion or excavation which exposes dispersive soils to rainfall.
- » Hydraulic disturbance such as vegetation removal or creation of runoff.


2.1 SODICITY AND DISPERSION

Tunnel erosion mostly occurs in dispersive soils (Vacher *et al.* 2004) which typically contain greater than 6.0 % exchangeable sodium (ESP). These soils are known as sodic soils or Sodosols (Isbell 2002), or in the past may have been referred to as Solodic, Solonetz or Solodized – solonetz (Doyle and Habraken 1993). Other soils such as Vertosols, Kurosols and Kandosols may also contain sodic or dispersive soil layers.

When a sodic soil comes into contact with non-saline water, water molecules are drawn in-between the clay platelets causing the clay to swell to such an extent that individual clay platelets are separated from the aggregate, this process is known as dispersion (Figure 5, van de Graaff & Patterson 2001, Nelson 2000). When small aggregates are placed in a dish of distilled water they appear to 'dissolve' into a milky ring or halo. This milky ring is the ejected clay platelets floating away from the clay aggregate. Dispersed platelets are often so small that they remain forever in suspension, which explains why dams constructed from dispersive clays never settle and always appear 'muddy' or 'milky'.

While sodic soils are generally dispersive, it is important to acknowledge that not all sodic soils disperse, and that not all dispersive soils are sodic (Sumner 1993). Factors such as silt and high magnesium content may induce non-sodic soils (ESP <6%) to disperse, while organic matter, clay mineralogy, acidity, and high iron content may prevent sodic soils (ESP >6%) from dispersing (Raine and Loch 2003, Rengasamy 2002). In southern Tasmania degraded Kurosols are known to be dispersive despite having less than 6.0 % ESP (Doyle pers. comm.). In addition, soils which are both saline and sodic do not disperse or behave like sodic soils until the salt is leached from the soil profile, usually following subsurface drainage (Rengasamy and Olsson 1991).

In slightly saline water, or water with a moderate electrolyte (salt) concentration, sodic soils swell, but generally don't disperse. The clay platelets remain intact. The presence of salts within the soil water reduces the osmotic gradient between the outside and inside of the clay platelets preventing the ultimate stage of swelling leading to dispersion (Nelson 2000). Maintenance of salts within the soil water is one of the most important mechanisms by which sodic soils are protected from dispersion and development of tunnel erosion.



2.2 TUNNEL EROSION

Tunnel erosion results from a complex interaction of chemical and physical processes associated with clay dispersion, mechanical scouring, entrainment and mass wasting. Observation indicates that in Tasmania, tunnel erosion usually starts as a result of rainfall coming into contact with dispersive subsoil following,

- » Loss of topsoil ie excavation or erosion.
- » Surface soil cracking due to desiccation (drying).
- » A change in hydrology or generation of runoff.
- » And occasionally formation of rabbit burrows or old root holes.

Once subsoil clays have dispersed the development of tunnel erosion depends on whether the soil matrix has sufficient permeability to enable dispersed soil material to move downslope through soil cracks and pores. This movement of dispersed clays leaves behind a small cavity. Further rainfall events, entrain more dispersed soil material, resulting in both the headward and tailward expansion of the cavity (Zhu 2003, Vacher *et al.* 2004, Laffan and Cutler 1977). Eventually

cavities link-up to form a continuous tunnel system in which water flowing at the tunnel base, further scours the sidewalls resulting in slumping and tunnel enlargement (Figure 6) (Laffan and Cutler 1977, Zhu 2003). Eventually undermining reaches an extent where complete roof collapse occurs and either gully erosion forms (Figure 24) (Laffan and Cutler 1977), or the topsoil collapses back over the tunnel to form a stable depression (Figure 8).



Figure 6. Sidewall collapse due to mechanical scouring and undercutting sidewalls. Dolerite derived soils, Dunalley.

Tunnel erosion tends to be a sporadic phenomenon (Pickard 1999). Tunnel eroded areas may appear to be stable for periods up to a decade or more before a single runoff event re-initiates the erosion process (Zhu 2003). There may also be a significant time-lag between disturbance and the first observation of tunnelling. At one site in Kingborough, tunnel development only became apparent 10-15 years after the site was disturbed presumably as a result of dwelling construction. At a property on Bruny Island, a single summer storm in 2003 increased the section of a hillslope affected by tunnel erosion by around 30%. Observation indicates that tunnel initiation tends to occur late in summer when vegetation has died off and soils are desiccated and cracked (Floyd 1974, Vacher *et al.* 2004). Sudden downpours generate large amounts of surface runoff which enter the subsoil directly through soil cracks (Figure 7), dispersing sodic soil horizons and initiating the tunnel erosion process. Although greater rainfall generally falls over winter, tunnel initiation is uncommon during the winter months as clays tend to have swelled, sealing surface cracks and reducing the presence of void spaces within the soil (Floyd 1974).



Figure 7. Surface water entering an existing tunnel system, increasing the mechanical erosion and scoring.



Figure 8. Collapse of tunnel roof, following loss of dispersive soil horizon leading to formation of a stable depression, Cygnet.

3.0 IDENTIFYING DISPERSIVE SOILS

IDENTIFICATION OF DISPERSIVE SOILS

- » Dispersive soils can be identified by dribble patterns and pitting.
- » Early stages of tunnel erosion can be identified by the development of spew holes.
- » Simple field tests can be used to identify the presence of dispersive soils.
- » For engineering works or infrastructure development, a combination of analytical and physical tests should be used. Consult an appropriately qualified and experienced soil specialist or civil engineer.

3.1 FIELD TECHNIQUES

Dispersive soils may be readily identified by distinctive dribble patterns that form following exposure to rain or low electrolyte runoff. The presence of the distinctive 'dribble' patterns or 'worm channels' is considered to be a reliable indicator of moderately to highly dispersive soils (Figure 9) and is nearly always observed on the sidewalls of tunnel erosion cavities. Where topsoil has been removed by erosion or excavation, pitting and pocketing can occur in subsoils exposed to rainfall (Figure 10).



Figure 9. (a) Example of dribble pattern on an exposed subsoil, the photograph was taken from within an actively eroding tunnel system. (b) Dribble patterns on sodic soil ped.



Figure 10. 'Pitting & pocketing', resulting from topsoil removal, surface water has dissolved through the soil surface. Soils derived from Triassic Sandstone.




Figure 11. 'Sediment fans or 'spew holes' are often the first sign of tunnel erosion (a) Honeywood, (b). Woodbridge (c) Campania (d) Dunalley.

Early signs of tunnel erosion include the presence of sediment fans or 'spew holes' which result from the ejection of fine sediments and dispersed clays from the downslope end of a tunnel erosion system (Figure 11). It is however important to note that by the time a spew hole has developed, considerable sub-surface erosion may have already occurred.

3.2 SIMPLE FIELD TEST FOR IDENTIFYING DISPERSIVE SOILS

Field testing for dispersive soils can be conducted by observing the behaviour of air dried aggregates in distilled water or rainwater. This analysis is a simplification of the Emerson crumb test (Emerson 2002).

- 1) Collect soil aggregates (1-2 cm diameter) from each layer in the soil profile.
- 2) If moist, dry the aggregates in the sun for a few hours until air-dried.
- 3) Place the aggregates in a shallow glass jar or dish of distilled water or rain water. It may help to place the jar on black card or a dark surface (distilled water can be purchased at most supermarkets).
- 4) Leave the aggregates in water without shaking or disturbing them for 2 hours.
- 5) Observe and record if you can see a milky ring around the aggregates. Don't worry if the soil collapses or bubbles (Figure 12).



Caution: Aggregates may not disperse when they should if they haven't been sufficiently dried. While the presence of a milky halo indicates the presence of dispersion, the absence of a milky halo does not necessarily mean that soil will not disperse. Some soils only disperse after they have been disturbed or remoulded. Further testing using an approved Australian Standard technique may be required.

3.3 LABORATORY TECHNIQUES FOR IDENTIFYING DISPERSIVE SOILS

Although a number of tests have been used to identify dispersive soils, no single test has been developed that can reliably identify all dispersive soils under all conditions (Bell and Maud 1994, Bell and Walker 2000). For civil engineering works or infrastructure development, it's suggested that a range of chemical and physical tests be employed rather than relying on interpretation of a single analysis (McDonald *et al.* 1981, Bell and Maud 1994, Bell and Walker 2000). McDonald *et al.* (1981) note that "there is urgent need for an agreed standard test or tests to identify dispersive soil. In the meanwhile, engineers should use a large number of inexpensive tests for screening, and confirm these as needed by more elaborate tests, adopting the most conservative evaluation." A review of analytical procedures for identifying dispersive behaviour in soils is presented by Bell and Maud (1994) and Bell and Walker (2000). It should also be noted that identification of soil dispersion does not necessarily imply that tunnel erosion will occur; as other factors such as water chemistry, site hydrology and soil porosity also influence the development of tunnel erosion.

CHEMICAL TESTS.

Chemical analyses such as ESP and SAR attempt to relate the relative abundance of exchangeable cations to aggregate stability and dispersion. Relationships between soil dispersion and chemical properties such as Exchangeable Sodium Percent (ESP), Cation Exchange Capacity (CEC), Sodium Absorption Ratio (SAR), and Electrical Conductivity (EC) have been developed for a limited range of soils (Elgers, 1985, Sherard *et al.* 1976, Gerber and Harmse 1987, Rengasamy *et al.* 1984). Use of chemical techniques for the prediction of soil dispersion have not been established for most Tasmanian soils. It should be noted that threshold levels for dispersion are arbitrarily defined (Sumner 1993) and that dispersion can occur in soils with ESP below 6 or SAR below 3 (further details and discussion of test procedures are provided in Appendix I).

PHYSICAL TESTS

The physical tests of soil dispersion such as the pinhole test and the Emerson crumb test rely on observation and ranking of soil dispersion in distilled water and / or dispersant.

The performance of a range of analytical procedures for the prediction of soil dispersion has been conducted by a number of authors including: Bell and Maud (1994), Bell and Walker (2000), Sherard *et al.* (1976), Moore *et al.* (1985) and Elges (1985). Review of these studies generally indicate that the Emerson crumb test (Emerson 2002) and the pinhole test to be the most reliable tests for predicting dispersive behaviour of soils, while the pinhole test (AS 1289.3.8.3 – 1997) was rated the most reliable single test for identification of soil dispersion associated with earth works such as dams or embankments, (further details and discussion of test procedures is provided in Appendix I).

4.0 APPROACHES FOR MINIMISING EROSION RISK IN DISPERSIVE SOILS

MINIMISE RISK OF TUNNEL EROSION BY;

- » Identifying and avoiding disturbance to areas with dispersive subsoils.
- » Minimising excavation of dispersive soils.
- » Not allowing water to pond on the soil surface, or exposed subsoils.
- » Keeping sodic sub-soils buried under topsoil.
- » Maintaining vegetation cover.

UNDERSTAND THAT;

- » The presence and severity of dispersive soils may vary enormously over short distances.
- » Past efforts to control field tunnel erosion have often failed.

STRATEGIES FOR REDUCING THE RISK OF TUNNEL DEVELOPMENT IN PERI-URBAN AREAS INCLUDE;

- » Soil testing and avoidance.
- » Precise compaction.
- » Chemical amelioration.
- » Sand filters and sand blocks.
- » Topsoiling and revegetation.

4.1 MANAGEMENT OPTIONS FOR TUNNEL EROSION

Past efforts to repair tunnel erosion in agricultural landscapes have relied on mechanical destruction of the tunnel system by deep ripping, contour furrowing, and contour ripping. Unfortunately many of these techniques either failed or resulted in tunnel re-emergence in an adjacent areas (Floyd 1974, Boucher 1995). The use of these 'agricultural' techniques is inappropriate in peri-urban areas where tunnel repair requires a low incidence of re-failure due to the potential for damage to infrastructure. Experience with the construction of earth dams using dispersive clays, demonstrates that repair and prevention of tunnel erosion in urban and peri-urban environments is best achieved using a combination of,

- » Identification and avoidance of dispersive soils.
- » Precise re-compaction.
- » Chemical amelioration.
- » Sand blocks and barriers.
- » Topsoil, burial and revegetation.

4.2 IDENTIFICATION AND AVOIDANCE OF DISPERSIVE SOILS

The risk of tunnel erosion resulting from construction activities on dispersive soils can often be reduced or eliminated by identifying and avoiding areas containing dispersive soils. The presence and severity of dispersive soils can vary enormously over short distances (Figure 13). In many instances, large scale (ie 10 x 10 or 20 x 20 meter grid) soil survey and screening of soils for dispersion, (using the Emerson crumb test - section 3, Appendix I) can be used to site dwellings and infrastructure away from dispersive soils. Advice should be sought from a suitably qualified and experienced engineer or soil professional.



4.3 COMPACTION

Ritchie (1965) demonstrated that the degree of compaction within the dam wall was the single most important factor in reducing dam failure from piping (tunnel erosion). A high degree of compaction reduces soil permeability, restricting the movement of water and dispersed clay through the soil matrix, which decreases the severity of dispersion and restricts tunnel development (Vacher *et al.* 2004). However, dispersive soils can be difficult to compact as they lose strength rapidly at or above optimum moisture content, and thus may require greater compactive force than other soils (McDonald *et al.* 1981). Bell & Bryun (1997) and Bell and Maud (1994) suggest that dispersive clays must be compacted at a moisture content 1.5 -2% above the optimum moisture content in order to achieve sufficient density to prevent piping (Elges 1985).

Construction of structures such as earth dams and footings for buildings with dispersive soils require geotechnical assessment and advice from a qualified and experienced engineer; in order to determine compaction measures such as the optimal moisture content, number of passes, and maximum thickness of compacted layers.

Normal earth moving machinery including bull-dozer, excavators and graders do not provide sufficient compactive force to reduce void spaces or achieve adequate compaction in dispersive soils. A sheepsfoot roller of appropriate weight is usually required to compact dispersive soils. By comparison a D6 dozer applies only 0.6 kg/cm² pressure compared to 9.3 kg/cm² for a sheepsfoot roller (Sorensen 1995).

Figure 13. The severity (or sodium content) and depth of dispersive subsoils can vary considerably over short distances. (a). At this site highly dispersive subsoils exist meters away from (b) non-dispersive soils.

4.4 CHEMICAL AMELIORATION

Initiation of tunnel erosion is predominantly a chemical process, so it makes sense to use chemical amelioration strategies when attempting to prevent or repair tunnel erosion in dispersive soils. Despite the widespread use of gypsum and lime to treat sodic soils in agriculture, the use of gypsum and lime to treat tunnel affected areas has been relatively rare (Boucher 1990).

Hydrated lime (calcium hydroxide) has been widely used to prevent piping in earth dams. Rates of application have varied depending on soils and degree of compaction used in construction. Laboratory testing usually indicates that only around 0.5 – 1.0% hydrated lime is required to prevent dispersion, however difficulties with application and mixing necessitate higher rates of application (Moore *et al.* 1985). Moore *et al.* (1985) cite examples of the use of hydrated lime to control piping in earth dams at rates between 0.35% (N.S.W. Australia) and 4% (New Mexico). Elgers (1985), and McElroy (1987) recommend no less than 2% hydrated lime (by weight of the total soil material) to prevent dispersion within dam embankments, while Bell and Maud (1994) suggest that 3% - 4% by mass of hydrated lime should be added to a depth of 0.3m on the upper face of embankments. In alkaline (pH >7.0) soils (most sodic subsoils in Tasmania are neutral or alkaline) the effectiveness of hydrated lime is reduced by the formation of insoluble calcium carbonate (Moore *et al.* 1985), such that gypsum is preferred to hydrated lime. It is important to note that agricultural lime (calcium carbonate) is not a suitable substitute for hydrated lime due to its low solubility (McElroy 1987). Also note that excessive applications of lime may raise soil pH above levels required to sustain vigorous plant growth.

Gypsum (calcium sulphate) is more effective than lime for the treatment of dispersive soils as it increases the electrolyte concentration in the soil solution as well as displacing sodium with calcium within the clay structure (Raine and Loch 2003). Gypsum is less commonly used than hydrated lime in dam construction and other works due to its lower solubility, and higher cost. Elgers (1985) recommends that in construction, a minimum of 2% by mass of gypsum be used. Bell and Maud (1994) present a means of calculating the amount of gypsum required to displace excess sodium and bring ESP values within desired limits (normally < 5). Be aware that application of excessive amounts of gypsum may cause soil salinity to temporarily rise beyond the desired level for plant growth.

NOTE:

- » Use of gypsum in Tasmania is covered under the Fertiliser Act 1993, which has established the allowable limit for cadmium and lead at 10 mg/kg and 5 mg/kg for mercury.
- » Gypsum is usually imported into Tasmania from Victoria or South Australia, which have different standards for allowable heavy metal content.
- » Purchasers of gypsum should check with suppliers to ensure that gypsum imported into Tasmania is compliant with current regulations.

Alum (aluminium sulphate) has been effectively used to prevent dam failure and protect embankments from erosion. Application rates are not well established. Limited data suggests mixtures of 0.6 – 1.0% (25% solution of aluminium sulphate) (Bell and Bruyn 1997, McElroy 1987) to 1.5% (Ouhadi, and Goodarzi 2006) of the total dry weight of soil may be appropriate. Alum is however highly acidic (pH 4-5), and thus alum treated soils will need to be capped with topsoil in order to establish vegetation (Ryker 1987). Soil testing is required to establish appropriate application rates for Tasmanian soils.

Long chain polyacrylamides have been shown to increase aggregate stability, reduce dispersion and maintain infiltration rates in dispersive soils (Levy *et al.* 1992, Raine and Loch 2003). However the effect is highly variable between various polyacrylamide products and the chemical and physical properties of the soil. The benefit of polyacrylamides is generally short due to their rapid degradation (Raine and Loch 2003). Further advice and laboratory testing should be conducted before using polyacrylamides to protect earth dams from piping failure.

Note that appropriate application rates for gypsum, hydrated lime, alum and polyacrylamides have not been established for dispersive soils in Tasmania. Extensive laboratory assessment of materials used for the construction of dams or embankments is required before locally relevant 'rules of thumb' can be established for the use of these products.

4.5 SAND BLOCKS AND SAND BARRIERS

Sand filters were first developed to prevent piping in earth dams. Sand filters prevent dam failure by trapping entrained sand and silt, blocking the exit of the tunnel and preventing further tunnel development (Sherard *et al.* 1977). Following the work of Sherard *et al.* (1977), Richley (1992 and 2000) developed the use of sand blocks to prevent tunnel erosion during installation of an optical fibre cable in highly dispersive soils near Campania, Tasmania. The sand blocks work slightly differently to the sand filters in that they allow the free water to rise to the surface through the sand. The use of sand blocks has recently been modified by Hardie *et al.*, (2007) to prevent re-initiation of tunnel erosion along an optical fibre cable near Dunalley. Modifications to the original technique developed by Richley (1992 and 2000) include (Figure 14 & 15);

- » Upslope curved extremities to prevent the structure from being by-passed.
- » Geotextile on the downslope wall to prevent collapse or removal of sand following settlement or erosion.
- » Application of gypsum (around 5% by weight) to ensure infiltrating water contains sufficiently electrolyte to prevent further dispersion.
- » Earth mound upslope of the structure to prevent run-on entering the sand blocks.



Figure 15. (a) Installation of sandblock perpendicular to a service trench. Note securing of geotextile to the optical fibre cable to prevent water flowing past the sand block. (b) Sandblock before final topsoiling.




Figure 14. Modified sand block design. (a) plan view, (b) cross section view. The depth of the sand block is determined by the depth of dispersive soils or tunnel erosion. The span length of the structure is determined by the width of the tunnelling.

4.6 USE OF TOPSOIL / BURIAL AND REVEGETATION

Topsoil or burial of exposed dispersive soils reduces the likelihood of subsoil dispersion and initiation of tunnel erosion by;

- » Providing a source of salt to increase the electrolyte content of infiltration water.
- » Preventing desiccation and subsoil cracking.
- » Promoting even infiltration.
- » Providing a protective cover from raindrop impact.
- » Providing a suitable medium for revegetation.

Topsoil minimises the interaction between water and dispersive clays by providing both a physical and chemical barrier. Topsoil also reduces soil desiccation and development of surface cracks (Sorensen 1995). It is suggested that exposed dispersive subsoils be covered with at least 150mm of non dispersive topsoil and sown with an appropriate mix of grass species. In some cases it will be necessary to protect the topsoil from erosion with 'jute' cloth or similar product.

The suitability of planting trees in tunnel affected areas is influenced by the amount of annual rainfall and frequency of soil cracking resulting from desiccation. Boucher (1995) recommends the preferred option for revegetation of reclaimed tunnel erosion is a widely spaced tree cover in association with a combination of perennial and annual pastures, rather than a dense stand of trees or pasture alone. Experience in Tasmania suggests that in low rainfall areas, or areas in which existing trees or shrubs cause soil drying and cracking, the preferred option for revegetating tunnel affected land is a dense healthy pasture. In high rainfall areas, dense plantings of trees have been successfully used to repair or stabilise tunnel erosion for example Colclough (1973) successfully used *Pinus radiata* to stabilise tunnel-gully affected land in a moderate rainfall area near Tea Tree, Tasmania.

5.0 ACTIVITIES THAT INCREASE THE RISK OF EROSION ON DISPERSIVE SOILS

ACTIVITIES THAT INCREASE RISK OF INITIATING TUNNEL EROSION, INCLUDE;

- » Removal of topsoil.
- » Soil excavation or expose of subsoils to rainfall.
- » Supply of services via trenches.
- » Construction of roads and culverts in dispersive subsoils.
- » Installation of sewage and grey water disposal systems in dispersive subsoils.
- » Dam construction from dispersive soils.

OPTIONS FOR REDUCING THE RISK OF TUNNEL EROSION DURING CONSTRUCTION AND DEVELOPMENT WORKS ON DISPERSIVE SOILS INCLUDE,

- » Where possible do not remove or disturb topsoil or vegetation.
- » Ensure that dispersive subsoils are covered with an adequate layer of topsoil.
- » Avoid construction techniques that result in exposure of dispersive subsoils.
- » Use alternatives to 'cut and fill' construction such as pier and post foundations.
- » Where possible avoid the use of trenches for the supply of services ie water & power.
- » If trenches must be used, ensure that repacked spoil is properly compacted, treated with gypsum and topsoiled.
- » Consider alternative trenching techniques that do not expose dispersive subsoils.
- » Ensure runoff from hard areas is not discharged into areas with dispersive soils.
- » If necessary create safe areas for discharge of runoff.
- » If possible do not excavate culverts and drains in dispersive soils.
- » Consider carting non-sodic soil to create appropriate road surfaces and drains without the need for excavation.
- » Ensure that culverts and drains excavated into dispersive subsoils are capped with non-dispersive clays mixed with gypsum, topsoiled and vegetated.
- » Avoid use of septic trench waste disposal systems; consult your local council about the use of alternative above ground treatment systems.
- » Where possible do not construct dams with dispersive soils, or in areas containing dispersive soils.
- » If dams are to be constructed from dispersive clays, ensure you consult an experienced, qualified civil engineer to conduct soil tests before commencing construction.
- » Construction of dams from dispersive soils is usually possible, using one or a combination of: precise compaction, chemical amelioration, capping with non-dispersive clays, sand filters and adequate topsoiling.

With all forms of construction on dispersive soils, ensure you obtain advice and support from a suitably experienced and qualified engineer or soil professional before commencing work.

5.1 ACTIVITIES THAT PROMOTE TUNNEL EROSION

In almost all cases tunnel erosion results from some form of disturbance resulting in rainwater or water with very low salt content coming into contact with dispersible subsoil. Changes to hydrology, such as concentration of flow in culverts, runoff from hardened areas and ponding of rainfall all increase risks of tunnel erosion. Typical activities that increase the risk of exposing dispersible subsoils to rainfall include;

- » Removal of topsoil.
- » Soil excavations.
- » Trenches and supply of services.
- » Roads and culverts.
- » Sewage and grey water disposal.
- » Dam construction.

5.2 REMOVAL OF TOPSOIL.

Topsoil provides both a physical and chemical barrier to infiltrating water (see section 4.6). Removal or stockpiling of topsoil for even relatively short periods can result in the initiation of tunnel erosion (Figure 16). If dispersible subsoils are exposed during construction, ensure they are covered with topsoil or dusted with gypsum and that rainfall does not have the opportunity to collect and pond.



Figure 16. Initiation of tunnel erosion caused by scalping or removing topsoil. Note that even a very thin layer of topsoil was able to prevent widespread tunnel erosion

5.3 CUT AND FILL

The use of 'cut and fill' excavation techniques (road cuttings, housing pads etc.) should be avoided in areas containing dispersive soils. Excavation can lead to the development of 'outlet initiated' tunnel erosion resulting from the removal of overburden (Figures 17 and 28) (Crouch *et al.* 1986, Vacher *et al.* 2004). While this form of tunnel erosion is rarely as extensive or deep as other forms of tunnelling, outlet initiated tunnelling can be difficult to repair and results in the deposition of sand and 'spewey' clays around the back of dwellings or in culverts.



Figure 17. Extensive 'outlet initiated' tunnel and rill erosion caused by excavating a cut and fill pad for a large building in a dispersive soil. Triassic sandstone parent material.

Although less commonly observed than the outlet initiated tunnelling, development of tunnel erosion in footings constructed from dispersive soils can occur as a result of rainfall ponding on dispersive fill. Note that in Figure 18 tunnelling has developed on a flat area without the need for a slope to generate water movement.



Figure 18. (Same site as Figure 17) Tunnel erosion in footings intended for a large building. Erosion resulted from ponding of rainwater on highly dispersive fill. The fill contains a number of narrow slots (up to 1.2 meters deep) caused by surface water 'dissolving' through the footing.

Seek experienced and qualified geotechnical advice from a suitably qualified civil engineer or appropriate soil specialist if a structural fill or footing is to be constructed from or into dispersive soils.

In areas with dispersive soils, pier or post style construction (Figure 19) is a low risk option for the construction of footings. Footings will need be excavated beneath any sodic layers and / or pinned to the basement rock. Post holes should be completely filled and capped with concrete above the soil surface, rather than backfilled with spoil. Runoff and surface water must be safely directed away from the building, or prevented from flowing near the foundations.



Figure 19. Pier or post style construction has considerably lower risk of initiating tunnel erosion than cut and fill techniques.

5.4 TRENCHES AND SUPPLY OF SERVICES

Services such as electricity, telecommunications and water are usually supplied to dwellings via trenches from mains outside the property. In areas with dispersive subsoils, supply of services by trenches increases the risk of initiating tunnel erosion (Figure 21b) (Richley 1995 & 2000, Hardie *et al.* 2007). Unfortunately most service providers are unfamiliar with the issues associated with dispersive soils, and may need assistance to understand why alternative supply options may need to be considered. Electricity and telecommunications can be supplied by private power poles resulting in minimal soil disturbance, provided that the poles are installed using augurs rather than excavated trenches (Figure 21a) and that the hole is completely filled with concrete above the soil surface or repacked with a mixture of gypsum and soil, with a high level of compaction. Spoil should be removed from the site.

EMERGING TECHNIQUE: HYDROLOGICAL BARRIER

This technique for diverting surface and subsurface water away from footings has been proposed as an alternative, or an addition to pier or post foundations. The hydrological barrier technique involves construction of a sand and gypsum filled trench to the depth of the foundations around the upslope area of the dwelling (Figure 20). The sand – gypsum mixture acts to trap the dispersed silts pugging up the developing tunnel while allowing the water to come into contact with the gypsum and rise through the sand and away from the footings. An earth mound immediately above the sand filled trench acts to prevent surface runoff entering the trench. The hydrological barrier can be installed either during construction or fitted to existing dwellings after construction. While the hydrological barrier technique has only been trialled once in Tasmania (Duckett pers. comm.) the design principles result from successful use of sand blocks (Figures 14 & 15) for the prevention of tunnel erosion resulting from the installation of optical fibre cables in dispersive soils (Richley 1995 & 2000, Hardie *et al.*, 2007).

Figure 20. Hydrological barrier to isolate foundations from surface and groundwater (Duckett pers. comm.), (a) cross section view, (b) plan view.







Figure 21 (a) Tunnel erosion initiated by installation of an optical fibre cable into a dispersive soil. (b) Subsidence and early stages of tunnelling resulting from inappropriate installation of power pole in a backfilled trench.

Alternatives to the use of trenches for the supply of potable water and other services will need to be approved by your local council. Examples include laying cable or pipe in the thin topsoil then carting more topsoil to the site to ensure adequate burial depth (Figure 22c). Alternatively the cable may need to be laid in hard conduit on the soil surface and buried with non-dispersive soil (Figure 22a). Any earthworks on the site must ensure that rainwater is not able to collect and pond on the soil surface, such that additional soil may be required to ensure that any buried cable or pipe is level with the land surface (Figure 22b). The remaining mound can be landscaped into the surrounding garden provided that trees and large shrubs are not planted in such a way as to prevent future access to the pipe.



Trenches may be used to supply services such as water and electricity, however in dispersive soils, the increased porosity of repacked spoil within the trench can lead to tunnel erosion and damage to pipes and cables (Figures 6 & 21b). If a trench must be used, then use of chemical amelioration, sand blocks and precise compaction can lower the risk of tunnel formation. Richley (1992) used sand blocks to prevent development of tunnel erosion along an optical fibre cable installed in highly dispersive soil near Campania, and Hardie *et al.* (2007) used a combination of chemical amelioration, compaction and sand blocks to prevent re-initiation of tunnel erosion following repair of a 380m long tunnel erosion system near Dunalley.




Figure 23. Improved trench design. (a). Traditional Trench. Note surface sinks allowing water to pond above trench. (b) Improved trench with individually compacted clay layers. The surface is finished above the ground surface to prevent ponding on top of the trench.

5.5 STORM WATER AND RUNOFF

Storm water and runoff from hard surfaces such as driveways and courtyards, need to be managed to prevent initiation of tunnel erosion (Trangmar 2003, Vacher *et al.* 2004). Stormwater and runoff should not be allowed to collect or pond on dispersive soils. Runoff should be directed away from susceptible areas (exposed dispersive soils) through the use of pipes or diversion mounds created from imported non-dispersive clays rather than trenches or culverts which risk excavation and exposure of dispersive subsoils (Figure 24). Captured runoff should be dissipated and spread over as wide an area as possible, not concentrated in drainage lines. Where possible dispose of captured water in 'safe' areas such as;

- » Garden beds mixed with gypsum.
- » Existing well vegetated areas with ample topsoil.
- » Stony elevated areas (Trangmar 2003).

If no other options exist, then a garden bed with ample topsoil and gypsum (around 2 -5 % of total soil volume) may need to be created away from dwellings or infrastructure. Wherever possible use rainwater tanks to capture runoff from roofs and buildings, but note that overflows will also need to be piped to 'safe' areas.



Figure 24. Tunnel erosion resulting from construction of a stormwater culvert in dispersive clay derived from Triassic sandstone, Brighton.

5.6 ROADS AND CULVERTS

Construction of roads or driveways on dispersive soils is difficult due to their low bearing capacity when wet (Figure 25). Concentrating water in roadside culverts and drains which have been excavated into dispersive soils often leads to erosion and collapse of the road batter adjacent embankments (Figures 26-28). Soil surveys may assist landholders / councils to locate roads in areas containing non-dispersive soils, however in most cases managing runoff without excavating culverts is the best means of reducing the erosion risk.



Figure 25. Road surface breaking up due to construction on dispersive clays. This section of road is repaired 2-3 times a year.



Figure 26. Undercutting and collapse of roadside batter due to construction of a table drain in dispersive clay. Note the failure of the blue rock rap to prevent further erosion.



Figure 27. Table drain constructed in dispersive subsoil. The concentration of runoff in the culvert is greatly adding to the erosion problem, resulting in slumping and undercutting of the road and the adjacent batter slope. This photo was taken 18 months after the driveway was constructed.




Figure 28. Rill and tunnel erosion caused by excavation of sodic soils for road construction. Dunalley.

Table drains should not be constructed in dispersive soils (Figure 26 & 27). If topsoil depth is insufficient to allow table drains to be constructed without exposing dispersive soils, then alternative forms of road construction and drainage need to be considered. Road design needs to ensure runoff is spread out and dissipated over wide, well vegetated areas. On steep slopes, minor roads are best constructed straight up and down the slope with speed hump like barriers across the road surface to shed water to the sides (Figure 29 - Duckett *pers. comm.*). Consideration should be given to spreading topsoil, applying gypsum and re-vegetating either side of the roadway to ensure runoff doesn't initiate further tunnelling.




Figure 29. Alternative road design using road bars and diversion mounds to shed water into stable areas.

Where it is necessary to excavate drains and culverts in dispersive soils, it is suggested that the exposed subsoil is treated with gypsum or hydrated lime then capped with a thick layer (i.e. 200-300mm) of non-dispersive clay (test for dispersion using procedure in section 3) preferably also mixed with either gypsum or hydrated lime. The clay capping should be covered with topsoil and revegetated if appropriate. Alternatives to the use of clay capping include the use of bitumen spraying and hydro-mulching, however few details of these techniques are available.

5.7 SEWAGE AND GREY WATER

Experience from the Brighton municipality has demonstrated that septic tank systems do not perform adequately in dispersive soils. Installation of septic systems in dispersive soils have resulted in the initiation of tunnel erosion resulting in health risks associated with uncontrolled discharge of effluent (Parkinson pers. comm.).

Brighton council have tested five different domestic wastewater treatment and disposal systems for use in dispersive or shallow soils (Parkinson & Palmer unpublished). Three systems were found to be viable: Recirculating Sand Filter (RSF), Pulse Dosed Aerobic Sand Filter (PDASF) and Effluent Landscape Mound (ELM), table 1).

Of the three systems, the Pulse Dosed Aerobic Sand Filter (PDASF) produced the highest level of treatment however at the time of the study the Effluent Landscape Mound (ELM) was the only system to be accredited by Australian Standards (AS1547, 2000). Other systems with similar or better performance have been developed since the original study. Check with your local council or a suitably qualified and experienced consultant to determine which operating systems meet current standards and would be best suited to your soils and level of occupancy.



Figure 30. Ozzi Kleen single tank (Aerated Wastewater Treatment System) for treatment and disposal of sewage and grey water. Raised – mulched area in foreground is being used for effluent disposal from the house in background.

Table 1: Alternative sewage and grey water treatment systems for dispersive or shallow soils.
(Parkinson & Palmer unpublished).

	Sand Bed Size (meters)	Tank Requirement	Suitability for Above Ground Spray	Final Quality (cfu / 100mL)	Australian Standard
Recirculating Sand Filter	2 x 6 x 1	2.4 meter diameter, and filter & effluent pump wells.	Yes	0-10	No
Pulse Dosed Aerobic Sand Filter	10 x 4 x 1 and rock filter 12 x 1.5 m x 0.4	2 x 3000L and filter & effluent pump wells	Yes	0-10	No
Effluent Landscape Mound	18 x 6.5 x 1	4500L, Dosing And effluent pump wells.	Required additional disinfection or subsoil application.	<50	Yes AS 1547, 2000

Alternatively composting toilets provide a no-water, zero tunnelling risk option for the treatment of sewage in areas with dispersive soils (Figure 31). Composting toilets offer a practical low risk and environmentally sustainable alternative to standard flushing toilets.



Figure 31. Example of a composting toilet system. (Source www.nature-loo.com.au)

5.8 DAM CONSTRUCTION

Dispersive soils are inherently unsuited to dam construction. A survey by Foster *et al.* (2000) found that 48% of dam failures resulted from piping (internal tunnelling) and that 42% of these failures occurred on first filling. Dams constructed from dispersive clays are always 'muddy' and are rarely suitable for swimming. Small farm and amenity dams are particularly prone to tunnel failure as they are frequently built without regulation, soil testing, or engineering advice. Serious consideration should be given to whether constructing a dam is necessary, and the potential consequences of dam failure before building a dam in an area containing dispersive soils.

Tunnel erosion or piping in dam walls results from fresh water dispersing sodic clays within the embankment. The dispersed clays flow into void spaces created by insufficient compaction during construction. Movement of dispersed clays creates increasingly larger cavities until a continuous tunnel or pipe is formed between the inner and outer wall, at which point dam failure occurs (Figures 33-35). The likelihood of failure of dams built with dispersive soils depends on a number of factors (Vacher *et al.* 2004) including,

- » The rate of first filling.
- » The degree of compaction during construction.
- » The dispersibility of materials used to construct the dam.
- » The electrolyte content of the soil solution.
- » The electrolyte concentration of the stored water.



Figure 32. The dam in the foreground has been constructed from dispersive clays. Note the rill erosion and cloudy brown colour of water in foreground, compared to the blue colour of the dam constructed from non-dispersive soils in the background.



Figure 33. Typical small dam failure. Note piping through the side wall of the dam. This dam was constructed using dispersive clays derived from Triassic sandstone.



Figure 34. Piping failure of a dam constructed from soils derived from Permian mudstone, Penna area. This dam is known to have failed on first filling. The image was taken from the dam floor, looking at the inside of the dam wall.



Figure 35. Failure of Blackman Creek dam (source: Davies Brothers). In 2005 the Blackman creek dam failed, resulting in the evacuation of Tunbridge. Doyle and Cumming (unpublished 2005) indicate the cause of the failure to be variability in the compaction of a slightly to a moderately dispersive soil layer, combined with rapid filling of the dam with low electrolyte water.

The risk of tunnel or piping failure in small earth dams can be minimised by a combination of control measures including:

- i) Adequate compaction
- ii) Chemical ameliorants e.g. gypsum, hydrated lime etc.
- iii) Sand filters.
- iv) Construction with non-dispersive clay.
- v) Topsoiling.

Construction of earth dams with dispersive soils is usually possible if adequate compaction can be achieved (Bell and Maud 1994). Ritchie (1965) demonstrated that the degree of compaction within the dam wall is the single most important factor in reducing dam failure. The importance of other factors such as batter angle, rate of filling or moisture content during construction were all secondary to that of compaction. Dispersive soils can be difficult to compact as they lose strength rapidly at or above optimum moisture content, and thus may require greater compactive force if moisture contents are just dry of optimum (McDonald *et al.* 1981). A sheep's foot roller is required to adequately compact dispersive soils as normal earth moving machinery cannot provide enough compactive force. (Refer section 4.3).

Chemical ameliorants such as hydrated lime (calcium hydroxide), gypsum (calcium sulphate), alum (aluminium sulphate) and long chain polyacrylamides have been used to prevent dispersion and piping in earth dams. Hydrated lime is the most commonly applied product with the rate varying between 0.5 to 4.0 % by weight, depending on

soil chemistry and level of dispersion (Moore *et al.* 1985, McElroy 1987, Elgers 1985, Bell and Maud (1994). Gypsum may also be used but its lower solubility and higher cost may limit its use. Gypsum is more effective than lime due to its higher electrolyte content which prevents dispersion as well as improves clay structure. Gypsum may also be added to the dam water to artificially increase the electrolyte (salt) concentration of the dam water, to minimise the risk of failure upon first filling (McDonald *et al.* 1981). (Refer section 4.4).

CASE STUDY: BEN BOYD DAM, NSW.

The Ben Boyd dam in New South Wales was protected from tunnel erosion or piping failure through a combination of chemical amelioration, precise compaction and increasing the electrolyte content of the inflowing waters.

The earth dam was successfully constructed with dispersive clays with ESP values as high as 20.7, (average 7.5) in an area known to contain very low electrolyte stream flow. Gypsum was applied to the dam structure at a rate of 1% by weight or 27 tonnes per hectare over the storage area. The gypsum was cultivated into the inner wall of the dam to a depth of 150cm and then compacted with a vibrating sheep's foot roller. The infilling water was dosed with gypsum and alum to raise the electrolyte concentration from around 70 mg/l to 300-600 mg/l (McDonald *et al.* 1981).

Sand filters can effectively seal and safely control leaks in dispersive clays. While sand filters are unable to 'trap' dispersed clays, the sands and silts are effectively 'trapped' sealing the exit of the tunnel and preventing further tunnel development (Sherard *et al.* 1977). (Refer section 4.5).

Dams constructed with low to moderately dispersive clays can often be protected from piping by capping the upper dam wall with a thick layer of compacted non dispersive clay, usually mixed with either hydrated lime or gypsum. Topsoiling and re-establishment of vegetation minimises the interaction between water and dispersive clays by providing both physical and chemical barrier to infiltrating water. Topsoil also reduces soil desiccation and development of surface cracks. (Refer section 4.6).

6.0 REPAIR AND REHABILITATION OF TUNNEL EROSION

While the techniques outlined in this document represent the best available knowledge at the time of writing, it should be recognised that repair and rehabilitation works are prone to re-failure and that the techniques outlined below (and in the wider literature) have not been validated by replicated field trials or adequate long term monitoring. Differences between field sites, erosion processes and long term landuse of the reclaimed area may affect the success of repair works.

- » Repair of tunnel erosion is expensive, difficult and prone to re-failure.
- » Existing literature is focused on repair of field tunnel erosion in agricultural landscapes rather than urban or peri-urban areas.
- » A combination of chemical, physical and vegetative measures are required to repair tunnel erosion.
- » Repair of tunnel erosion in peri-urban areas should consider use of controlled compaction, chemical amelioration, sandblocks, and topsoiling.
- » Revegetate repaired areas with fast growing locally appropriate pasture species and trees in higher rainfall areas.
- » Seek professional assistance.

Repairing tunnel erosion is expensive, difficult and prone to re-failure. Every effort must be made to prevent the formation of tunnel erosion before intervention is required. Literature on the repair and rehabilitation of tunnel erosion is scarce and focused on agricultural landscapes rather than protection of infrastructure in urban environments. The history of tunnel erosion control and repair has been reviewed by Boucher (1990), and Ford *et al.* (1993). Boucher (1990) identified the need for a combination of mechanical, vegetative and chemical measures to control and repair tunnel erosion, however Boucher (1990) and Boucher (1995) also note that many past attempts to repair tunnel erosion have failed or been responsible for initiating further tunnelling.

In Tasmania, Colclough (1965, 1967, 1971, 1973 and 1978) pioneered early techniques for controlling tunnel erosion and Richley (1992 and 2000) demonstrated the use of sand blocks to prevent the development of tunnel erosion following installation of an optical fibre cable. Hardie *et al.*, (2007) detailed advances in repair and rehabilitation techniques resulting from experience gained with the rehabilitation of a 380 meter long tunnel erosion system in Dunalley, Tasmania.

It is strongly recommended that a suitably qualified soil professional, with first hand experience in dispersive soil management be consulted before embarking on any repair or rehabilitation works. The approach outlined below has been developed following extensive review of literature, expert opinion from erosion consultants and first hand experience of repairing tunnel erosion.

GENERAL RECOMMENDATIONS FOR REPAIR OF TUNNEL EROSION IN PERI-URBAN AREAS.

- 1) Where possible cut off or divert surface water away from the tunnel system using diversion mounds rather than drains. Earthworks must be conducted without exposing dispersive subsoils. Experience has shown that identification of 'safe' areas is rare and usually dependant on there being a change in soil type or geology. If there is any doubt that a disposal area is 'safe' then works to divert flow from the head of the tunnel system should be abandoned.
- 2) Identify the true head of the tunnel system to determine the scale of intervention work required. This usually requires chasing tunnels with an excavator and use of coloured dye to trace water movement.
- 3) If tunnels are shallow and reappearance of tunnel erosion is not likely to impact on critical infrastructure, then deep ripping and cultivation techniques may be used to destroy the tunnel system (see Floyd 1974, Colclough 1965 & 1971).
- 4) If tunnels extend below the maximum depth of deep ripping, or if critical infrastructure is at risk from tunnel reappearance, then control and repair options will require a higher level of intervention to lower the risk of re-failure.

- 5) Tunnel systems will need to be dug out along their entire path using an excavator.
- 6) If soils have a low to moderate risk of dispersion (ESP 6 - 15), or if the consequences of tunnel reappearance is low, then the dispersive soils excavated from the trench can be treated with gypsum and repacked back into the excavated area.
- 7) If soils are highly dispersive (ESP > 15) or the risk of tunnel reappearance may cause damage to infrastructure, then non-dispersive clays will need to be carted to the site and repacked in the trench. Repacked soils should also be mixed with gypsum as an additional measure against future dispersion.
- 8) All material repacked into the trench needs to be compacted to at least 95% of proctor maximum. Compaction is best achieved using a sheep's foot roller. Track rolling with an excavator or back hoe is not adequate. Alternative compaction techniques may be available.
- 9) The surface of the repacked material should be finished with a convex shape to ensure runoff is not able to pond on top of the reclaimed area. The upper surface of the repaired work should be treated with gypsum to act as an electrolyte source for water infiltrating into the repacked spoil.
- 10) Treated areas and exposed subsoils should be covered with topsoil and revegetated with fast growing, locally appropriate species such as cocksfoot, ryegrass, and clovers. Fertiliser may also need to be applied to ensure adequate establishment.
- 11) Bare areas above the tunnel head may need to be treated to minimise runoff through use of scarifying, topsoil, fertiliser and sowing locally appropriate pasture species.
- 12) Consideration should be given to applying gypsum over the whole area at a rate of approximately 1.0 - 2.5 t/ha every 3 to 5 years.
- 13) Fence off all reclaimed areas, and allow only minimal grazing over time.
- 14) Control rabbits and maintain vegetative ground cover.



Figure 36. Examples of tunnel erosion control (a) Poor technique. Rock rap is usually an inappropriate erosion control technique for dispersive soils. Normally rock barriers work well to trap sediment and reduce erosion. However in dispersive soils, hard surfaces such as rock are quickly bypassed i.e. upper corner of the rock structure (b) Excellent technique. Note the entire repaired area is fenced, and the whole length of the repaired tunnel is covered with topsoil and jute cloth. Sand barriers have been constructed every 20 meters down the slope.



Figure 37. Good technique. Topsoil mounding, reclaimed tunnel erosion, Brighton. Note the width of earthworks required to fix a 50cm wide tunnel, and the raised profile to shed surface water. Jute cloth would prevent surface erosion until vegetation has established.

7.0 REFERENCES

- Anon (1999a) SOILpak for dryland farmers on the red soil of Central Western NSW. Chapter E4, NSW Dept. Primary Industry.
- Anon (1999b) Soil and Water Management Code of Practice for Hobart Regional Councils. Hobart City Council.
- Anon (1999c) Guidelines for Soil and Water Management, Reproduced, Department Primary Water and Environment.
- Australian Standards,
Pinhole test (AS 1289.3.8.3 – 1997)
Emerson soil crumb test (AS 1289.3.8.1-1997)
Onsite domestic wastewater management (AS1547:2000).
- Bell FG, Bryun IA (1997) Sensitive, expansive, dispersive and collapsive soils. *Bulletin of the International Association of Engineering Geology* **56**, 19-38.
- Bell FG, Maud RR (1994) Dispersive soils: a review from a South African perspective. *Quarterly Journal of Engineering Geology* **27**, 195-210.
- Bell FG, Walker DJH (2000) A further examination of the nature of dispersive soils in natal, South Africa. *Quarterly Journal of Engineering Geology and Hydrology* **33**, 187-199.
- Boucher SC (1990) 'Field tunnel erosion, its characteristics and amelioration'. Dept. of Conservation and Environment, Land Protection Division, Victoria, East Melbourne.
- Boucher SC (1995) Management options for acidic sodic soil affected by tunnel erosion. In 'Australian Sodic Soils: Distribution, Properties and Management'. (Eds R Naidu, ME Sumner; and P Regansamy) pp. 239-246. (CSIRO Publications).
- Colcough JD (1965) Soil conservation and soil erosion control in Tasmania - tunnel erosion. *Tasmanian Journal of Agriculture* **36**, 7-12.
- Colcough JD (1967) Soil conservation and soil erosion control in Tasmania - tunnel erosion control. *Tasmanian Journal of Agriculture* **38**, 25-31.
- Colcough JD (1971) Contour ripping. *Tasmanian Journal of Agriculture* **42** (2), 114-125.
- Colcough JD (1973) Vegetation to control tunnel erosion. *Tasmanian Journal of Agriculture* **44** (1), 65-70.
- Colcough JD (1978) Soil Conservation in Tasmania, *Journal Soil Conservation Service of New South Wales* **34** (2), 63-72.
- Craze B, Holman G, Chapman GA, Stone MJ (2003) Soil Survey Standard Test Method – Emerson Aggregate Test, EAT – P9B/2. In 'Soil Survey Standard Test Methods' (Eds Craze B, Holman G, Chapman GA, Stone MJ). Department of Land & Water Conservation, Sydney.
- Crouch RJ (1976) Field Tunnel erosion – A Review. *Journal Soil Conservation Service New South Wales*. **32** (2), 98-111.
- Crouch RJ, McGarity JW, Storrier RR (1986) Tunnel formation processes in the Riverina Area N.S.W, Australia. *Earth Surface Processes and Landforms* **11** (2), 157-166
- Cumming JP (2003) East Baskerville Urban Capability Report. Consultants report to Brighton council, July 2003. Sloane Weldon Pty Ltd Tasmania, Australia.
- Doyle R (pers. comm.) Lecturer in soil science, School of Agricultural Science, University of Tasmania.
- Doyle R, Cumming JP (unpublished 2005) Soil Materials Report on the Blackman River Earth Dam. University of Tasmania and SFM.
- Doyle R, Habraken FM (1993) The distribution of Sodic Soils in Tasmania. *Australian Journal of Soil Research* **31** (6), 931-947.
- DPIWE (2004) Soil Orders Map of Tasmania 1:500000. Department Primary Industries Water and Environment, Hobart.
- Duckett T (pers. comm.) Director, Land Management and Rehabilitation Services, Hobart Tasmania.

- Elgers HFWK (1985) Dispersive soils. *The Civil Engineer in South Africa* **27 (7)**, 347-353.
- Emerson WW (2002) Emerson Dispersion Test, In 'Soil Physical Measurement and Interpretation for Land Evaluation, Australian Soil and Land Survey Handbook Series, Vol. 5'. (Eds N McKenzie, K Coughlan, and H Creswell) pp 190-199 (CSIRO Publishing, Collingwood, Victoria).
- Floyd EJ (1974) Tunnel erosion a field study in the Riverina. *Journal of the Soil Conservation Service of N.S.W.* **30 (3)**, 145-156.
- Ford GW, Martin JJ, Rengasamy P, Boucher SC, Ellington A (1993) Soil Sodicity in Victoria. *Australian Journal Soil Research* **31**, 869-909.
- Foster M, Fell R, and Spannagle M (2000) A method for assessing the relative likelihood of failure of embankment dams by piping. *Canadian Geotechnical Journal* **37(5)**, 1025-1061.
- Gerber FA, and Harmse HJ von M (1987) Proposed procedure for identification of dispersive soils by chemical testing. *Civil Engineer in South Africa* **29 (10)**, 397-399.
- Grice MS (1995) 'Assessment of Soil and land degradation on private freehold land in Tasmania'. (Department of Primary Industry and Fisheries Tasmania, National Landcare Program).
- Hardie, M, Cotching WE, Zund P (2007) Rehabilitation of field tunnel erosion using techniques developed for construction with dispersive soils. *Australian Journal of Soil Research* **45(4)** 280-287.
- Isbell RF (2002) 'The Australian Soil Classification'. Australian Soil and Land Survey Handbooks Series Volume 4, (CSIRO Publishing: Collingwood, Vic.).
- Laffan MD, Cutler EJB (1977) Landscapes, soils, and erosion of a catchment in the Wither Hills, Marlborough. *New Zealand Journal of Science* **20 (3)**, 279-289.
- Levy GJ, Levin J, Gal M, Ben-Hur M, and Shainberg I (1992) Polymers' effect on infiltration and soil erosion during consecutive simulated sprinkler irrigations. *Soil Science Society of America Journal* **56**, 902 -907.
- McDonald LA, Stone PC, Ingles OG (1981) Practical treatments for dams in dispersive soils. In 'Proceedings of the 10th International Conference on Soil Mechanics and Foundation Engineering' **2**, pp. 355-366.
- McElroy GH (1987) The use of chemical additives to control the erosive behaviour of dispersed clays. In 'Engineering Aspects of Soil Erosion, Dispersive Clays and Loess', Proceedings Symposium, American Society of Civil Engineers, Geotechnical Special Publication **10**, 17-29.
- Moore PJ, Wrigley RJ, and Styles JR (1985) Identification and amelioration of some dispersive soils. *Transactions of the Institution of Engineers, Australia: Civil Engineering CE27 (4)*, Paper C1598. pp 371-383.
- Nelson PN (2000) Diagnosis and Management of Sodic Soils Under Sugarcane, BSES Publications.
- Ouhadi VR, Goodarzi AR (2006) Assessment of the stability of a dispersive soil treated by alum. *Engineering Geology* **85 (1-2)**, 91-101.
- Parkinson J (pers. comm.) Environmental health consultant, On-site Wastewater Solutions. Previously Environmental health Officer Brighton Council.
- Parkinson J, Palmer C (Unpublished) Trialling innovative and sustainable domestic wastewater treatment and disposal systems, Unpublished final report, Natural Heritage Trust & Brighton Council.
- Pickard J (1999) Tunnel erosion initiated by feral rabbits in gypsum, semi-arid New South Wales, Australia. *Zeitschrift fuer Geomorphologie* **43 (2)**, 155-166.
- Raine SR, Loch RJ (2003) What is a sodic soil? Identification and management options for construction sites and disturbed lands. In 'Road, Structures and Soils in South East Queensland 29-30th' (Department of Main Roads, Queensland).

- Rayment GE, Higginson FR (1992) 'Australian Laboratory Handbook of Soil and Water Chemical Methods'. Australian Soil and Land Survey Handbook Series, (Inkarta Press).
- Rengasamy P (2002) Clay dispersion, In ***Soil Physical Measurement and Interpretation for Land Evaluation, Australian Soil and Land Survey Handbook*** Series, Vol. 5, Eds McKenzie N, Coughlan K, and Creswell H. pp 200-210. CSIRO publishing, Collingwood, Victoria.
- Rengasamy P, Churchman GJ (1999) Cation exchange capacity, exchangeable cations and sodicity. In ***Soil Analysis and Interpretation Manual***. Ed Peverill KI, Sparrow LA, Reuter DJ. CSIRO publishing Collingwood, Victoria. pp 129-146.
- Rengasamy P, Greene RSB, Ford GW, and Mehanni AH (1984) Identification of dispersive behaviour and the management of red brown earths. ***Australian Journal of Soil Research* 22**, 413-431.
- Rengasamy P, Olsson KA (1991) Sodicty and soil structure. ***Australian Journal of Soil Research* 29**, 935-952.
- Richley LR (1992) Minimising Erosion Hazard due to Installation of an Optical Fibre Cable through Dispersible Clay Soils, ***Australian Journal of Soil and Water Conservation* 5 (4)**, 35-38.
- Richley LR (2000) Treatment of tunnel erosion in Tasmania, ***Natural Resource Management* 3 (2)**, 31-34.
- Ritchie JA (1965) Investigations into earthwork tunnelling and mechanical control measures using small scale dams. ***Journal Soil Conservation New South Wales* 21**, 81-89.
- Ryker NL (1987) Alum Treatment of Dispersive Clays. In ***Engineering Aspects of Soil Erosion, Dispersive Clays and Loess***, In 'Proceedings Symposium, American Society of Civil Engineers, Geotechnical Special Publication no 10'. pp 17-29.
- Sherard JL, Dunnigan LP, Decker RS (1976) Identification and nature of dispersive soils. ***Journal Geotechnical Division, proceedings ASCE* 102**, 287-301.
- Sherard JL, Dunnigan LP, Decker RS (1977) Some engineering problems with dispersive clays. In 'Some Engineering Problems with Dispersive Clays ASTM STP 623', American Society for Testing Materials, 3-12.
- Sorensen S (1995) Dispersive Soils: Guide for use in farm dam construction. DNRQ96017, Rural Water Advisory Services. Department of Natural Resources Queensland, Brisbane.
- Sumner ME (1993) Sodic Soils: New perspectives. ***Australian Journal Soil Research* 31**, 683 – 750.
- Trangmar B (2003) Soil Conservation Guidelines for the Port Hills. Landcare Research Contract Report: LC0203/111. Prepared for Christchurch City Council.
- Vacher CA, Loch RJ, Raine SR (2004) Identification and Management of Dispersive Mine Spoils. Final Report for Australian Centre for Mining Environmental Research, Kenmore Queensland.
- van de Graaff R, Patterson RA (2001) Explaining the mysteries of salinity sodicity, SAR and ESP in on-site practice. In ***Proceedings of On-site '01 Conference: Advancing on-site wastewater Systems*** (Eds. Patterson RA, Jones MJ). Lanfax Laboratories, Armidale.
- Zhu TX (2003) Tunnel development over a 12 year period in a semi-arid catchment of the Loess Plateau, China. ***Earth Surface Processes and Landforms* 28**, 507-525.

8.0 APPENDIX I: ANALYSIS AND CLASSIFICATION OF DISPERSIVE SOILS

(I). EXCHANGEABLE SODIUM PERCENT (ESP)

The Exchangeable Sodium Percent (ESP) is the most common analytical technique used to identify sodic or potentially dispersive soils. The ESP is determined from the ratio of exchangeable cations and is measured as method 15N1 (Rayment and Higginson 1992),

$$ESP = \frac{Na^+}{Na^+ + Mg^{2+} + K^+ + Ca^{2+}} \times 100$$

In Australia, soils with an ESP greater than 6 are classed sodic (Isbell 2002) due to their likelihood to undergo dispersion in fresh water. Highly sodic soils are classed as having an ESP greater than 15. Most North American literature however classifies soils as being sodic when the ESP exceeds 15 (Rengasamy & Churchman 1999).

(II). SODIUM ABSORPTION RATIO (SAR)

Sodium absorption ratio (SAR) is commonly used as a measure of soil sodicity in North America. In Australia it is more commonly used as a measure of sodicity in water; however its use for soil on either a saturated paste or 1:5 basis is considered useful, especially in acid soils, in which the presence of exchangeable Al^{3+} effects measurement of CEC (Rengasamy & Churchman 1999). Rengasamy and Olsson (1991) found that SAR of a 1:5 extract is better at predicting soil dispersion than ESP. Dispersion thresholds based on SAR 1:5 are not as well established as those for ESP however if SAR 1:5 is greater than 3, soils are considered sodic (Rengasamy and Olsson 1991).


$$SAR = \frac{Na^+}{((Mg^{2+} + Ca^{2+})/2)^{1/2}}$$

(III). EMERSON SOIL CRUMB TEST (AS 1289.3.8.1-1997)

The Emerson soil crumb test (AS 1289.3.8.1-1997) is an Australian Standard for the prediction of dispersive behaviour of clay soils. The Emerson test is quick and simple and can be used to assist in the rapid identification of dispersive soils. The test has three levels,

- (i) Spontaneous dispersion of an air dried aggregate in deionised water;
- (ii) Remoulding at near maximum field capacity and re-immersion in deionised water;
- (iii) Remoulded soil is shaken in deionised water.

A number of modifications and variations to the Emerson test have sought to add subclasses to either Class 2 and Class 3 aggregates (Craze *et al.* 2003). The history and interpretation of the Emerson crumb test is discussed in Emerson (2002).



pinhole is measured and the shape of the pinhole inspected for erosion.

(V). DISPERSION INDEX OR DOUBLE HYDROMETER TEST

The Dispersion Index has been widely used in Australia to identify soils at risk of tunnelling. Soil is shaken end over end in two separate operations, firstly in distilled water and secondly in dispersant to ensure complete dispersion. The difference between the amount of dispersion (measured as the % particles <2 microns) between the two tests is used to infer dispersion risk (Raine & Loch 2003). The dispersion index is very similar to the Double Hydrometer test (ASTM D 4211-83, 1986) routinely used in America for predicting dispersive behaviour of soils.



Figure 39. Pinhole test for compacted soils & fill. (Photo, Raine & Loch 2003).

POTENTIAL (514.03) (RENGASAMY 2002).

The mechanical dispersive potential is calculated as the difference in osmotic pressure between the threshold electrolyte concentration required to flocculate clays and the ambient solution concentration. The electrolyte concentration required to flocculate the clays is determined by sequentially lowering the SAR of the solution until no clay dispersion occurs.

(VI) MEASUREMENT OF CLAY DISPERSION (514.01) (RENGASAMY 2002).

The clay dispersion technique is based on the threshold electrolyte concept which takes into account the electro – osmotic pressures between clay platelets and at the soil solution. The percent of dispersed clay is determined by pipette extraction and weighing following 16 hours spontaneous dispersion and after 16 hours mechanical dispersion. The soil solution is also measured for SAR, EC and pH and the results reported as the percentage dispersed clay and the predicted dispersion class based on EC and SAR.

(VII) MEASUREMENT OF DISPERSIVE

$$\text{Dispersive if } \frac{\% \text{ Particles } < 2 \mu\text{m in dispersant \& water}}{\% \text{ Particles } < 2 \mu\text{m in distilled water}} = \leq 3.0$$

9.0 APPENDIX II: AMENDMENT TO EXISTING CODES OF PRACTICE & GUIDELINES

9.1 SOIL AND WATER MANAGEMENT CODE OF PRACTICE FOR HOBART REGIONAL COUNCILS (1999B).

The Soil and Water Management Code of Practice for Hobart Regional Councils (Anon 1999b) and Guidelines for Soil and Water Management (Anon 1999c) were written without an awareness of the specific issues associated with dispersive soils. Amendments (in italics) are proposed to the Water Management Code of Practice for Hobart Regional Councils (Anon 1999b) and Guidelines for Soil and Water Management (Anon 1999c).

Soil and Water Management Code of Practice for Hobart Regional Councils (Anon 1999b).

1.0 BUILDING SITES AND SMALL SUBDIVISIONS.

1.1.1 Soil and water management plans (SWMPs) are required for all developments where 250 square meters or more of ground will be disturbed. Council may vary this requirement where there is:

(iii) High likelihood that dispersive soils will be exposed or disturbed, in which case it may require a SWMP even though less than 250 square meters of ground will be disturbed.

1.1.4 Where development consent is not required, earthworks should only be undertaken without an SWMP if:

(ii) The land on which this work is undertaken is not:

» Geotechnically unstable; if soils are dispersive; and

(iv) Work will not disturb or expose dispersive soils.

1.2.1 On all sites, identify;

» Location of areas with dispersive soils or subsoils.

1.3.8 Table drains and culverts should not be constructed in locations or ways which expose dispersive soils

1.5.6 Exposed or disturbed dispersive soils will immediately be capped with 150mm topsoil.

1.5.7 Alternatives to the use of trenches for the supply of services should be considered in areas containing dispersive soils.

1.6.2 Stormwater should not be conveyed in trenches which expose dispersive soils.

1.6.3 Stormwater should not be disposed in areas which contain dispersive soils.

2.0 SUB-DIVISION CONSTRUCTION ACTIVITIES.

2.1.1 Soil and water management plans (SWMPs) are required for all developments where 250 square meters or more of ground will be disturbed. Council may vary this requirement where there is:

(iii) High likelihood that dispersive soils will be exposed or disturbed, in which case it may require a SWMP even though less than 250 square meters of ground will be disturbed.

2.1.4 Where development consent is not required, earthworks should only be undertaken without an SWMP if:

(ii) The land on which this work is undertaken is not:

» Geotechnically unstable; if soils are dispersive; and

(iv) Work will not disturb or expose dispersive soils.

2.2.3 On the map/plan identify;

» Location of areas with dispersive soils or subsoils.

2.3.4 Table drains and culverts should not be constructed in locations or ways which expose dispersive soils

2.5.6 Exposed or disturbed dispersive soils will immediately be capped with 150mm topsoil.

2.6.4 Stormwater should not be conveyed in trenches which expose dispersive soils.

2.6.5 Stormwater should not be disposed in areas which contain dispersive soils.

2.8.5 Table drains and culverts should not be constructed in locations or ways which expose dispersive soils.

3.0 CIVIL INFRASTRUCTURE WORKS.

3.1.1 Soil and water management plans (SWMPs) are required for all developments where 250 square meters or more of ground will be disturbed. Council may vary this requirement where there is:

(iii) High likelihood that dispersive soils will be exposed or disturbed, in which case it may require a SWMP even though less than 250 square meters of ground will be disturbed.

3.1.6 Where development consent is not required, earthworks should only be undertaken without an SWMP if:

(iv) Work will not disturb or expose dispersive soils.

3.2.3 On the map/plan identify;

» Location of areas with dispersive soils or subsoils.

3.3.4 Table drains and culverts should not be constructed in locations or ways which expose dispersive soils

3.5.11 Exposed or disturbed dispersive soils will immediately be capped with 150mm topsoil.

3.5.12 Alternatives to the use of trenches for the supply of services should be considered in areas containing dispersive soils.

3.6.4 Stormwater should not be conveyed in trenches which expose dispersive soils.

3.6.5 Stormwater should not be disposed in areas which contain dispersive soils.

3.8.4 Table drains and culverts should not be constructed in locations or ways which expose dispersive soils.

9.2 GUIDELINES FOR SOIL AND WATER MANAGEMENT (ANON 1999C)

The following section on dispersive soils should be appended to the guidelines.

What are Dispersive Soils.

- » Dispersive soils disperse or appear to 'dissolve' in water, forming a cloudy ring or halo of detached soil particles.
- » Dispersive soils are usually sodic, containing greater than 6% sodium within the clay structure.
- » Dispersive soils are usually derived from sedimentary rocks.
- » Dispersive soils occur in all municipalities in southern Tasmania.

Issues with Dispersive Soils

- » Result in tunnel erosion.
- » Result in damage to infrastructure including foundations, roads and septic systems.
- » Often responsible for dam collapse.
- » Impact on environment including considerable turbidity in waterways.
- » Usually considerable damage has occurred before tunnel erosion is detected.
- » Potential liability risk.

Management of Dispersive Soils

Should Do

- » Apply gypsum to potentially dispersive soils.
- » Cover exposed dispersive soils with topsoil.
- » Vegetate all bare areas with vigorous pasture.
- » Seek professional geotechnical advice before commencing construction works including dam construction, roads and building foundations.

Should Not Do.

- » Expose dispersive subsoils to rain.
- » Allow water to pond on dispersive soils.
- » Concentrate stormwater in drainage lines containing dispersive soils.
- » Use table drains, trenches or cut and fill construction techniques in areas containing dispersive soils.
- » Scalp or extract topsoil from areas with dispersive subsoils.



Tasmania
Explore the possibilities

CONTACT DETAILS

Sustainable Land Use
Department of Primary Industries
and Water

GPO Box 44
HOBART TAS 7001
Ph. 03 6233 6212
Fax. 03 6223 8603
www.dpiw.tas.gov.au

ISBN 978-0-7246-6774-1

© State of Tasmania
Published April 2009

CERTIFICATE OF THE RESPONSIBLE DESIGNER

Section 94
Section 106
Section 129
Section 155

To: Play Co Architect

Owner name

12 Oakmont Rd

Address

Midway Point TAS

7171

Suburb/postcode

Form **35**

Designer details:

Name:

Terry (Jiuwei) Wu

Category:

Civil Engineer

Business name:

Stronghold Engineers Pty Ltd

Phone No:

0422657288

Business address:

Suite 65/ 89-97 Jones St

Ultimo, NSW

2007

Fax No:

Licence No:

DEP0000252

Email address:

terry.w@shens.com.au

Details of the proposed work:

Owner/Applicant

Play Co Architect

Designer's project reference No.

P537

Address:

12 Oakmont Rd

Lot No:

Midway Point TAS

7171

Type of work:

Building work ☒

Plumbing work ☐ (X all applicable)

Description of work:

Stormwater design of new single dwelling.

(new building / alteration / addition / repair / removal / re-erection
water / sewerage / stormwater / on-site wastewater management system / backflow prevention / other)

Description of the Design Work (Scope, limitations or exclusions): (X all applicable certificates)

Certificate Type:	Certificate	Responsible Practitioner
	<input type="checkbox"/> Building design	Architect or Building Designer
	<input type="checkbox"/> Structural design	Engineer or Civil Designer
	<input type="checkbox"/> Fire Safety design	Fire Engineer
	<input checked="" type="checkbox"/> Civil design	Civil Engineer or Civil Designer
	<input type="checkbox"/> Hydraulic design	Building Services Designer
	<input type="checkbox"/> Fire service design	Building Services Designer
	<input type="checkbox"/> Electrical design	Building Services Designer
	<input type="checkbox"/> Mechanical design	Building Service Designer
	<input type="checkbox"/> Plumbing design	Plumber-Certifier; Architect, Building Designer or Engineer
	<input type="checkbox"/> Other (specify)	

Deemed-to-Satisfy: ☒ Performance Solution: ☐ (X the appropriate box)

Other details: Stormwater design of new single dwelling.

Design documents provided:

The following documents are provided with this Certificate –

Document description:

Drawing numbers: ST01-ST03	Prepared by: Terry (Jiuwei) Wu	Date: 28/02/2025
Schedules:	Prepared by:	Date:
Specifications:	Prepared by:	Date:
Computations:	Prepared by:	Date:
Performance solution proposals:	Prepared by:	Date:
Test reports:	Prepared by:	Date:

Standards, codes or guidelines relied on in design process:


AS/NZS 3500.3:2021 Plumbing and drainage - Part 3: Stormwater drainage
Sorell Council Stormwater in New Development Policy

Any other relevant documentation:**Attribution as designer:**

I Terry (Jiuwei) Wu am responsible for the design of that part of the work as described in this certificate;

The documentation relating to the design includes sufficient information for the assessment of the work in accordance with the *Building Act 2016* and sufficient detail for the builder or plumber to carry out the work in accordance with the documents and the Act;

This certificate confirms compliance and is evidence of suitability of this design with the requirements of the National Construction Code.

	<i>Name: (print)</i>	<i>Signed</i>	<i>Date</i>
Designer:	Terry (Jiuwei) Wu		28/02/2025
Licence No:	DEP0000252		

Assessment of Certifiable Works: (TasWater)

Note: single residential dwellings and outbuildings on a lot with an existing sewer connection are not considered to increase demand and are not certifiable.

If you cannot check ALL of these boxes, LEAVE THIS SECTION BLANK.

TasWater must then be contacted to determine if the proposed works are Certifiable Works.


I confirm that the proposed works are not Certifiable Works, in accordance with the Guidelines for TasWater CCW Assessments, by virtue that all of the following are satisfied:

- ☒ The works will not increase the demand for water supplied by TasWater
- ☒ The works will not increase or decrease the amount of sewage or toxins that is to be removed by, or discharged into, TasWater's sewerage infrastructure
- ☒ The works will not require a new connection, or a modification to an existing connection, to be made to TasWater's infrastructure
- ☒ The works will not damage or interfere with TasWater's works
- ☒ The works will not adversely affect TasWater's operations
- ☒ The work are not within 2m of TasWater's infrastructure and are outside any TasWater easement
- ☒ I have checked the LISTMap to confirm the location of TasWater infrastructure
- ☒ If the property is connected to TasWater's water system, a water meter is in place, or has been applied for to TasWater.

Certification:

ITerry (Jiuwei) Wu..... being responsible for the proposed work, am satisfied that the works described above are not Certifiable Works, as defined within the *Water and Sewerage Industry Act 2008*, that I have answered the above questions with all due diligence and have read and understood the Guidelines for TasWater CCW Assessments.

Note: the Guidelines for TasWater Certification of Certifiable Works Assessments are available at: www.taswater.com.au

	Name: (print)	Signed	Date
Designer:	Jiuwei Wu		28/02/25

DRAWING SCHEDULE			
Sheet Number	Sheet Name	Current Revision	Current Revision Date
A0000	Cover Sheet	E	2025.04.02
A0100	Site Plan	E	2025.04.02
A0120	Wall Type Details	E	2025.04.02
A1101	Ground Floor Plan	E	2025.04.02
A1102	First Floor Plan	E	2025.04.02
A1103	Roof Plan	E	2025.04.02
A2001	North and South Elevations	E	2025.04.02
A2002	East and West Elevation	E	2025.04.02
A2003	Fence Elevations	C	2025.04.02
A3001	Section A	E	2025.04.02
A3002	Section B	E	2025.04.02
A4001	Door Schedule	E	2025.04.02
A4002	Window Schedule	E	2025.04.02
A4003	Material and Finish Schedule	E	2025.04.02
A9002	Perspective	E	2025.04.02



Sorell Council

Development Application:5.2024.307.1 -
Response to Request For Information - 12
Oakmont Road, Midway Point P3.pdf
Plan Reference:P3
Date received:07/04/2025

NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT

12 Oakmont Road

12 Oakmont Road, Midway
Point, TAS

ARCHITECT



PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

CLIENT


PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS		
DRAWING NUMBER	A0000	DRAWING TITLE	Cover Sheet		
SCALE		PAPER SIZE	A3	REVISION	E
DRAWN BY	SH	REVIEWED BY	RN	STATUS	Preliminary



Sorell Council
Development Application:5.2024.307.1 -
Response to Request For Information - 12
Oakmont Road, Midway Point P3.pdf
Plan Reference:P3
Date received:07/04/2025

INVERNESS STREET

OAKMONT ROAD



SITE AREA:

584.6 m²

GFA CALCULATION:

GROUND FLOOR = 196.8 m²

LEVEL 1 = 191.6 m²

TOTAL = 488.4 m²

LANDSCAPED AREA CALCULATION:

TOTAL PROPOSED LANDSCAPED AREA:

126.2 m²

MAX. SITE COVERAGE (50%):

292.3 m²

TOTAL PROPOSED SITE COVERAGE AREA:

258.6 m²

NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway Point, TAS

ARCHITECT

 P L A Y


PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

CLIENT


PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS
DRAWING NUMBER	A0100	DRAWING TITLE	Site Plan
SCALE	1 : 200	PAPER SIZE	A3
DRAWN BY	SH	REVIEWED BY	RN
REVISION	E	STATUS	Preliminary




BR1 - EXTERNAL WALL - HEBEL CAVITY WALL




BR2 - EXTERNAL WALL - HEBEL CAVITY WALL




BR3 - GARAGE WALL - HEBEL WALL W/ STONE CLADDING



MS1 - INTERNAL CORRIDOR WALLS



MS2 - INTERNAL WALLS





Sorell Council

Development Application:5.2024.307.1 -
Response to Request For Information - 12
Oakmont Road, Midway Point P3.pdf
Plan Reference:P3
Date received:07/04/2025

NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway
Point, TAS


ARCHITECT

CLIENT

**PLAY**

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS		
DRAWING NUMBER	A0120	DRAWING TITLE	Wall Type Details		
SCALE	1 : 10	PAPER SIZE	A3	REVISION	E
DRAWN BY	SH	REVIEWED BY	RN	STATUS	Preliminary



NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway Point, TAS

ARCHITECT
PLAY

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

CLIENT


PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS
DRAWING NUMBER	A1101	DRAWING TITLE	Ground Floor Plan
SCALE	1 : 100	PAPER SIZE	A3
DRAWN BY	SH	REVIEWED BY	RN
REVISION	E	STATUS	Preliminary





Sorell Council

Development Application:5.2024.307.1 -
Response to Request For Information - 12
Oakmont Road, Midway Point P3.pdf
Plan Reference:P3
Date received:07/04/2025



NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway Point, TAS

ARCHITECT



P L A Y

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

CLIENT


PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS
DRAWING NUMBER	A1102	DRAWING TITLE	First Floor Plan
SCALE	1 : 100	PAPER SIZE	A3
DRAWN BY	SH	REVIEWED BY	RN
REVISION	E	STATUS	Preliminary





Sorell Council

Development Application:5.2024.307.1 -
Response to Request For Information - 12
Oakmont Road, Midway Point P3.pdf
Plan Reference:P3
Date received:07/04/2025



NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway
Point, TAS

ARCHITECT
 P L A Y
PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

CLIENT


PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS
DRAWING NUMBER	A1103	DRAWING TITLE	Roof Plan
SCALE	1 : 100	PAPER SIZE	A3
DRAWN BY	SH	REVIEWED BY	RN
REVISION	E	STATUS	Preliminary




Sorell Council

Development Application:5.2024.307.1 -
Response to Request For Information - 12
Oakmont Road, Midway Point P3.pdf
Plan Reference:P3
Date received:07/04/2025

1 North Elevation
Scale: 1 : 100



2 South Elevation
Scale: 1 : 100



NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road



12 Oakmont Road, Midway
Point, TAS

ARCHITECT

CLIENT

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS
DRAWING NUMBER	A2001	DRAWING TITLE	North and South Elevations
SCALE	1 : 100	PAPER SIZE	A3
DRAWN BY	SH	REVIEWED BY	RN
REVISION	E	STATUS	Preliminary



- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway
Point, TAS


ARCHITECT

 P L A Y


PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

CLIENT


PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS		
DRAWING NUMBER	A2002	DRAWING TITLE	East and West Elevation		
SCALE	1 : 100	PAPER SIZE	A3	REVISION	E
DRAWN BY	SH	REVIEWED BY	RN	STATUS	Preliminary



1 Fence Front Elevation (North - Gate)
Scale: 1 : 50



2 Fence Side Elevation 1 (North West)
Scale: 1 : 50



3 Fence Side Elevation 2 (West)
Scale: 1 : 50

Sorell Council
Development Application: 5.2024.307.1 -
Response to Request For Information - 12
Oakmont Road, Midway Point P3.pdf
Plan Reference: P3
Date received: 07/04/2025

NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2025.01.22	Issued for Design Permit Coordination
B	2025.02.27	Issued for RFI
C	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road


12 Oakmont Road, Midway
Point, TAS

ARCHITECT

CLIENT

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS
DRAWING NUMBER	A2003	DRAWING TITLE	Fence Elevations
SCALE	1 : 50	PAPER SIZE	A3
DRAWN BY	SH	REVIEWED BY	RN
REVISION	C	STATUS	Preliminary



 **Sorell Council**
Development Application:5.2024.307.1 -
Response to Request For Information - 12
Oakmont Road, Midway Point P3.pdf
Plan Reference:P3
Date received:07/04/2025

NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway
Point, TAS


ARCHITECT

 **P L A Y**

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

CLIENT

PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS
DRAWING NUMBER	A3001	DRAWING TITLE	Section A
SCALE	1 : 100	PAPER SIZE	A3
DRAWN BY	SH	REVIEWED BY	RN
REVISION	E	STATUS	Preliminary



 **Sorell Council**
Development Application:5.2024.307.1 -
Response to Request For Information - 12
Oakmont Road, Midway Point P3.pdf
Plan Reference:P3
Date received:07/04/2025

NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway
Point, TAS


ARCHITECT

CLIENT

 **P L A Y**

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS
DRAWING NUMBER	A3002	DRAWING TITLE	Section B
SCALE	1 : 100	PAPER SIZE	A3
DRAWN BY	SH	REVIEWED BY	RN
REVISION	E	STATUS	Preliminary



Door Schedule						
Type Mark	Mark	Height (H)	Width (W)	Description	Count	Comments
D01	01	2600	5000	Panel-lift Garage Gate	1	
D02	01	2700	1000	Single-Panel Swing Door (Main Entrance)	1	
D03	01	2700	950	Single-Panel Swing Door (Entrance)	1	
D03	02	2700	950	Single-Panel Swing Door (Entrance)	1	
D03	03	2700	950	Single-Panel Swing Door (Entrance)	1	
D03	04	2700	950	Single-Panel Swing Door (Entrance)	1	
D04	01	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	02	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	03	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	04	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	05	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	06	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	07	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	08	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	09	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	10	2400	900	Single-Panel Swing Door (Rooms)	1	
D04	11	2400	900	Single-Panel Swing Door (Rooms)	1	
D05	01	2400	900	Single-Panel Swing Door (Wet Area)	1	
D05	02	2400	900	Single-Panel Swing Door (Wet Area)	1	
D05	03	2400	900	Single-Panel Swing Door (Wet Area)	1	
D05	04	2400	900	Single-Panel Swing Door (Wet Area)	1	
D06	01	2400	800	Single-Panel Cavity Sliding Door	1	

NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway Point, TAS



ARCHITECT

CLIENT

 P L A Y

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS		
DRAWING NUMBER	A4001	DRAWING TITLE	Door Schedule		
SCALE	1 : 50	PAPER SIZE	A3	REVISION	E
DRAWN BY	SH	REVIEWED BY	RN	STATUS	Preliminary



Window Schedule							
Type Mark	Mark	Height (H)	Width (W)	Sill Height (S)	Description	Count	Type Comments
W01	01	2700	900	0	Single-Panel Fixed Window	1	
W01	02	600	2400	2100	Single-Panel Fixed Window	1	
W01	03	600	1800	2100	Single-Panel Fixed Window	1	
W01	04	600	1800	2100	Single-Panel Fixed Window	1	
W01	05	900	1800	1800	Single-Panel Fixed Window	1	
W01	06	900	1800	1800	Single-Panel Fixed Window	1	
W01	07	600	2400	2100	Single-Panel Fixed Window	1	
W01	08	600	2400	2100	Single-Panel Fixed Window	1	
W01	09	600	2400	2100	Single-Panel Fixed Window	1	
W02	01	2700	2400	0	2-Panel Sliding Glazing Door	1	
W02	02	2700	2400	0	2-Panel Sliding Glazing Door	1	
W03	01	2700	4500	0	3-Panel Sliding Glazing Door	1	
W03	02	2700	3600	0	3-Panel Sliding Glazing Door	1	
W03	03	2700	3600	0	3-Panel Sliding Glazing Door	1	
W04	01	1600	1800	1100	2-Panel Sliding Window	1	
W04	02	1600	2400	1100	2-Panel Sliding Window	1	
W04	03	900	1800	1800	2-Panel Sliding Window	1	
W04	04	2200	1800	500	2-Panel Sliding Window	1	
W04	05	900	1800	1800	2-Panel Sliding Window	1	
W04	06	2200	1800	500	2-Panel Sliding Window	1	
W04	07	900	1800	1800	2-Panel Sliding Window	1	
W04	08	1600	2400	1100	2-Panel Sliding Window	1	
W04	09	1600	1800	1100	2-Panel Sliding Window	1	
W04	10	1600	2400	1100	2-Panel Sliding Window	1	
W05	01	2700	1000	0	Awning Window w/ Glazing Parapet	1	
W05	02	2700	1000	0	Awning Window w/ Glazing Parapet	1	
W05	03	2700	1000	0	Awning Window w/ Glazing Parapet	1	
W05	04	2700	1000	0	Awning Window w/ Glazing Parapet	1	
W06	01	2500	3600	500	3-Panel Custom Awning Window w/ Glazing Parapet	1	

NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway
Point, TAS

ARCHITECT

 P L A Y

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

CLIENT

PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS
DRAWING NUMBER	A4002	DRAWING TITLE	Window Schedule
SCALE	1 : 50	PAPER SIZE	A3
DRAWN BY	SH	REVIEWED BY	RN
REVISION	E	STATUS	Preliminary



AL01
ALUMINIUM POWERCOATED MONUMENT
FINISH TO WINDOWS AND VERTICAL POST
FENCE



RF01
RENDER AND WHITE PAINT FINISH




CF01
EXPOSED AGGREGATE CONCRETE FLOOR
PAVEMENT



CF02
POLISHED CONCRETE FLOOR



TF01
TIMBER FINISH FLOORING



TF02
TIMBER-LOOK ALUMINIUM BATTERN FINISH



TL02
TILE FINISH TO OUTDOOR AREA



SF01
STACKING STONE FINISH TO GARAGE
EXTERIOR WALLS

MR01
METAL ROOF

TL01
TILE FINISH TO WET AREAS TBC

NOTES

- ALL WORKS TO BE IN ACCORDANCE WITH THE BUILDING CODE OF AUSTRALIA, AUSTRALIAN STANDARDS, STATUTORY REGULATIONS AND LOCAL AUTHORITY REQUIREMENTS.
- CONTRACTOR TO ENSURE CONSISTENCY BETWEEN SIMILAR MATERIAL IS MAINTAINED.
- PREPARE & MAKE GOOD ALL SURFACES & SUBSTRATE AS REQUIRED TO RECEIVE NEW FINISHES AS PER MANUFACTURER'S SPECIFICATION.
- ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE COMMENCEMENT OF WORK. ALL DIMENSIONS MUST BE CHECKED & VERIFIED ON SITE PRIOR TO CONSTRUCTION & MANUFACTURE OF ANY ITEM.
- THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF THE AUTHOR. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE EXPRESS AUTHORITY OF PLAY CO PTY LTD.

REV	DATE	DESCRIPTION
A	2024.11.20	Issued for Design Permit Coordination
B	2024.12.03	Issued for Design Permit Coordination
C	2025.01.22	Issued for Design Permit Coordination
D	2025.02.27	Issued for RFI
E	2025.04.02	Issued for RFI

PROJECT
12 Oakmont Road

12 Oakmont Road, Midway
Point, TAS

ARCHITECT
 P L A Y

PLAY CO PTY LTD
ABN 206 135 521 86
SUITE 4.02, 11 HELP STREET
CHATSWOOD NSW 2067
WWW.PLAY-CO.COM.AU

CLIENT

PROJECT NUMBER	P537	PROJECT ADDRESS	12 Oakmont Road, Midway Point, TAS		
DRAWING NUMBER	A4003	DRAWING TITLE	Material and Finish Schedule		
SCALE	1 : 10	PAPER SIZE	A3	REVISION	E
DRAWN BY	SH	REVIEWED BY	RN	STATUS	Preliminary