



Attachment to item number 5.1 -

Site Investigation Report (Site Classification & Wind Loads for Housing);

Site Investigation Report (On-Site Wastewater Management System Assessment Report);

SITE INVESTIGATION REPORT

**AS 2870 SITE CLASSIFICATION &
AS 4055 WIND LOADS FOR HOUSING**

**CLIENT:
JAMES & JESSICA FISHER**

**PROJECT ADDRESS:
12 EAST STREET
DODGES FERRY 7173**

**PROPOSED DEVELOPMENT:
NEW RESIDENTIAL DWELLING**

**FILE NUMBER:
H2750**

**DATE:
24 NOVEMBER 2023**



Sorell Council

Development Application: 5.2024.266.1 -
Response to Request for Information P2.pdf

Plans Reference: P2
Date received: 27.02.2025

**HED CONSULTING
UNIT 2, 1 LIVERPOOL ST, HOBART 7000
P 03 6146 0334 E info@hed-consulting.com.au**

**HED
CONSULTING**



Dear Sorell Council Planning Officer,

We confirm that the siting of the proposed dwelling complies with Section 10.4.3 Setback P2 of the planning scheme and does not cause an unreasonable loss of amenity to adjoining properties.

The site features a natural slope, narrowing at the top and opening out further downslope. The proposed dwelling is located at the higher portion of the site, which is essential to accommodate the wastewater system at the lower end. This positioning is both functional and respectful of the site constraints, ensuring the infrastructure is located away from neighbouring dwellings. The proposed location reflects the established development pattern in the area, where similar topographical challenges have influenced the placement of houses.

The setbacks of the proposed dwelling align with those of surrounding properties, maintaining consistency with the character of the area. The height, bulk, and form of the dwelling have been designed to integrate harmoniously into the sloping landscape. This solution lowers visual impact and ensures the dwelling does not obstruct direct views of neighbouring or adjoining properties. We have utilised the slope, so the design ensures the building blends with the natural terrain without appearing imposing or inconsistent with the area's character.

Shadow diagrams have been prepared and submitted to demonstrate that the proposed dwelling has minimal impact on sunlight to adjoining properties. The shadow diagrams confirm that private open spaces and habitable room windows on neighbouring properties will not be unreasonably affected. The dwelling's orientation and design prioritise sunlight access for adjoining properties while maximising usability for the site itself.

The dwelling's siting ensures adequate private open space is retained on the property and that the privacy and amenity of adjoining properties are preserved. Furthermore, the proposed development aligns with the established character of the neighbourhood, where dwellings typically make use of sloping sites to accommodate infrastructure such as wastewater systems.

In conclusion, the proposed dwelling is sited to balance the unique constraints of the site with the need to protect the amenity of adjoining properties. The design complies with Section 10.4.3 Setback P2 of the planning scheme by ensuring consistency with the setbacks, scale, and character of the area while minimising impacts on neighbouring properties.

1. Executive Summary

The subject land is located at 12 East Street, Dodges Ferry. The development proposal includes the construction of a residential dwelling. The site investigation has been conducted in accordance with AS2870:2011 *Residential slabs and footings* and AS4055-2021 *Wind Load for housing*. A summary of the report is detailed in the table below.

| Analysis | Observations / Results |
|-----------------------------------|--------------------------------------|
| Site classification | P (due to erodible soils) |
| Surface movement (y_s) range: | 0-20mm (S) |
| Geology: | Triassic dominantly quartz sandstone |
| Refusal depth: | No refusal (2.8m+) |
| Soil bearing capacity: | 100 kPa @ 0.6m depth |
| Modified Emerson Crumb test: | Non – dispersive |
| Wind classification: | N3 |

2. Client Information and Site Location

| | Information |
|------------------|-----------------------------|
| Client name: | James & Jessica Fisher |
| Site address: | 12 East Street Dodges Ferry |
| Property ID: | 5914901 |
| Title Reference: | 79621/6 |

3. Site information

| Site information | Results |
|----------------------|--|
| Size of development: | Single residential dwelling |
| Services available: | Power, telecommunications |
| Zoning: | Low Density Residential |
| Tenure: | Private Freehold |
| Permit Authority: | Sorell Council |
| Planning Overlays: | Southern Beaches On-site Waste Water and Stormwater Management Specific Area Plan, Airport obstacle limitation area & Low landslip hazard band |

4. Site visit

| Site investigation | Observations / Results |
|-----------------------------|---|
| Date of site investigation: | 23/11/2023 |
| Slope: | 20 - 30% |
| Aspect: | South - east |
| Rainfall: | 24.3mm (preceding two weeks) ¹ |
| Drainage: | Well - draining |
| Vegetation: | Grass and isolated shrubs |
| Erosion: | No significant erosion was observed |

¹ Bureau of Meteorology, <http://www.bom.gov.au>, Daily Rainfall Sorell (Abbatoirs)

5. Soil Profile

Two bore holes were conducted in the top half of the lot. Both bore holes revealed a deep sandy soil profile. The soil profile and location of the bore holes is shown in the appendix of this report.

6. Site Stability

The proposed dwelling will be located within the Low landslip hazard band. The land has a slope that exceeds the commonly accepted threshold slope angle of 10 degrees for soil derived from Triassic sedimentary bedrock. Bore holes revealed a loose sandy topsoil and would be exposed to wind erosion if disturbed.

The site exhibits no signs of significant erosion or land instability. It should be noted that this report does not include a Landslide Risk Assessment and should not be relied upon for land stability.

Earthworks shall comply with AS3798-2007 Guidelines on earthworks for commercial and residential developments.

The Australian Geomechanics Society Sub-committee on landslide risk management (2007) can be found in the appendix of this report. These guidelines provide information on good hillside practice for construction and should be followed for the construction of the proposed dwelling.

7. AS2870 Site Classification

The site is classified as: **P** (due to the presence of erodible soils).

The natural soil profile has 0-20 mm γ_s surface movement.

Footings shall be bedded / piered to competent natural material. Dense competent sand was identified at 2.1m depth in bore hole BH01 and 2.3m in bore hole BH02.

8. AS4055 Wind Classification

The site is classified as per AS4055 – 2021 Wind loads for housing.

| Site information | Results |
|-----------------------------|---------|
| Geographic region: | A |
| Terrain Category: | 1 |
| Topographic classification: | T1 |
| Shielding: | NS |
| Wind Classification: | N3 |
| Wind Speed ($V_{h,u}$): | 50m/s |

9. General notes and limitations

Site Investigation:

Site investigation conducted in accordance with the requirements of clause 2.4 of AS2870:2011. The aim of a site investigation is to obtain information about the soil at the location of the intended building(s). The location of bore holes are based on information supplied from the client and other any other location that is deemed necessary by HED Consulting to provide an accurate report. The investigation only applies to this part of the site and the results and recommendations of this report should not be used for any other part of the site.

HED Consulting aims to provide an accurate report at the time of the investigation however natural variations in soil characteristics and depth can occur over short distances. Soil conditions can also vary over time due to climatic events or earthworks. For example, the bearing capacity of clay soils can vary due to the seasonal climatic events. HED Consulting accepts no responsibility for soil conditions that are different to what was inspected at the time of the investigation. If the soil conditions encountered vary to the results of this report HED Consulting should be contacted for advice. As per clause 2.5.2 of AS2870:2011 the site

may require to be re-classified if a cut exceeds 500mm or depth of fill would result in a P classification (when the earthworks were not known at the time of investigation).

Soil testing:

Soil samples (when collected) are tested in accordance with AS1289.7.1.1 – 2003 *Soil reactivity tests-determination of the shrinkage index of a soil-shrink swell index*. Soil testing is not required for all sites due to previous testing of similar material and/or using professional opinion. Bearing capacity of soil is based on field testing with accordance to clause 6.1.7 of AS1726:2017 and / or pocket penetrometer and / or DCP method. Bearing capacity of clays can vary seasonally. Clay can lose strength with high moisture content and increase in strength when clay dries. Bearing capacity results are estimated and are valid for the time of the investigation only. Emersion testing is conducted in accordance with Dispersive Soils and their Management, Technical Reference Manual, Marcus Hardie – 2009. This test reveals whether a clay is dispersive or not.

Building maintenance notes:

The building foundations shall be designed by an engineer. The builder must ensure that good site drainage is provided during the construction phase. Soil drains shall be constructed before excavation of the footings. Roof water should be diverted away from the footing as soon as the roof is constructed by using temporary pipes if necessary.

The long-term performance of the building is dependent upon satisfactory ongoing maintenance by the owner. The builder and owner should obtain a copy of the notes contained within the CSIRO – Building Technology Services, Foundation Maintenance and Footing Performance. A copy of this manual can be purchased from CSIRO Publishing, <http://www.publish.csiro.au>. Earthworks shall comply with AS3798-2007 Guidelines on Earthworks for commercial and residential developments.

10. Appendix

10.1 Field photos



Photo 1: Field photo showing the soil profile of bore hole BH01.



Photo 2: Field photo showing the soil profile of bore hole BH02.

10.2 Bore hole logs

See attached.

10.3 Site plan & Goodhillside Construction Guidelines

See attached.

10.4 Form 55

See attached.

Engineering Log - Bore hole

Project Number : H2750

Client: James & Jessica Fisher Date: 23/11/2023
Project Address: 12 East Street Dodges Ferry Borehole Location: Lat -042.866152° / Long +147.620042° (±4.7m)
Logged By: J Hepper Drilling Method: 55mm Sitech Auger

| Drilling Information | | | | | Observation / Notes | | | | |
|----------------------|---------|-------|------------|--------------|---|--------------------|--------------------------------|----------------------------|---------------------------------------|
| Method | Support | Water | Depth (mm) | Group Symbol | Material Description: Colour, Structural, Fraction, Plasticity, Bedding, Additional | Moisture Condition | Consistency / Relative Density | In situ testing (Est. kPa) | Structure and Additional Observations |
| | | | 200 | SP | SAND, fine - very fine grained, rounded, trace rootlets, brown - grey | D | L | ≤ 50 | |
| | | | 1500 | SP | SAND, fine grained, rounded, brown - white | D | MD | ≥ 50 - ≤ 100 | D |
| | | | 2100 | SP | SAND, medium grained, rounded, brown - white | M | MD | ≥ 50 - ≤ 100 | D |
| | | | 2800 | SP | SAND, medium grained, rounded, trace clay, grey - brown mottled orange | M | D | ≥ 100 | |
| | | | | | Limit of bore | | | | |

Drilling Method

HA - Hand Auger
E - Excavator
WB - Wash Boring

Support

C - Casing

Sample and Tests

U - Undisturbed Sample
D - Disturbed Sample
PP - Pocket Penetrometer
DCP - Dynamic Cone Penetration Test
SPT - Standard Penetration Test
SV - Shear Vane Test

Classification Symbols and

Soil Description
Based on Unified Soil Classification System and in accordance with AS1726

Moisture Condition

W - Wet
M - Moist
D - Dry

Consistency / Relative Density

VS - Very Soft L - Loose
S - Soft MD - Medium Dense
F - Firm D - Dense
St - Stiff VD - Very Dense
Vst - Very Stiff
H - Hard
Fr - Friable

Water

▼ Level
▷ Inflow
◁ Partial Loss

Engineering Log - Bore hole

Project Number : H2750

Client: James & Jessica Fisher Date: 23/11/2023
 Project Address: 12 East Street Dodges Ferry Borehole Location: Lat -042.866183° / Long +147.620249° (±4.8m)
 Logged By: J Hepper Drilling Method: 55mm Sitech Auger

| Drilling Information | | | | | | Observation / Notes | | |
|----------------------|---------|-------|------------|--------------|---|---------------------|--------------------------------|----------------------------|
| Method | Support | Water | Depth (mm) | Group Symbol | Material Description: Colour, Structural, Fraction, Plasticity, Bedding, Additional | Moisture Condition | Consistency / Relative Density | In situ testing (Est. KPa) |
| | | | 200 | SP | SAND, fine grained, rounded, trace rootlets, grey - brown | D | L | ≤ 50 |
| | | | 2300 | SP | SAND, fine grained, rounded, brown - white | D - M | MD | ≥ 50 - ≤ 100 |
| | | | 2800 | SP | SAND, medium grained, rounded, brown - white | M | D | ≥ 100 |
| | | | | | Limit of bore | | | |

Drilling Method

HA - Hand Auger
 E - Excavator
 WB - Wash Boring

Support

C - Casing

Sample and Tests

U - Undisturbed Sample
 D - Disturbed Sample
 PP - Pocket Penetrometer
 DCP - Dynamic Cone Penetration Test
 SPT - Standard Penetration Test
 SV - Shear Vane Test

Classification Symbols and

Soil Description
 Based on Unified Soil Classification System and in accordance with AS1726

Moisture Condition

W - Wet
 M - Moist
 D - Dry

Consistency / Relative Density

VS - Very Soft L - Loose
 S - Soft MD - Medium Dense
 F - Firm D - Dense
 St - Stiff VD - Very Dense
 Vst - Very Stiff
 H - Hard
 Fr - Friable

Water

▼ Level
 ▷ Inflow
 ◁ Partial Loss

12 EAST STREET DODGES FERRY BORE HOLE LOCALITIES

EXISTING OUTBUILDING

BH01

BH02

BH01

- BORE HOLE ID



PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

APPENDIX G - SOME GUIDELINES FOR HILLSIDE CONSTRUCTION

GOOD ENGINEERING PRACTICE

POOR ENGINEERING PRACTICE

ADVICE

| | | |
|-------------------------|---|--|
| GEOTECHNICAL ASSESSMENT | Obtain advice from a qualified, experienced geotechnical practitioner at early stage of planning and before site works. | Prepare detailed plan and start site works before geotechnical advice. |
|-------------------------|---|--|

PLANNING

| | | |
|---------------|---|---|
| SITE PLANNING | Having obtained geotechnical advice, plan the development with the risk arising from the identified hazards and consequences in mind. | Plan development without regard for the Risk. |
|---------------|---|---|

DESIGN AND CONSTRUCTION

| | | |
|-------------------------------|--|---|
| HOUSE DESIGN | Use flexible structures which incorporate properly designed brickwork, timber or steel frames, timber or panel cladding. Consider use of split levels. Use decks for recreational areas where appropriate. | Floor plans which require extensive cutting and filling. Movement intolerant structures. |
| SITE CLEARING | Retain natural vegetation wherever practicable. | Indiscriminately clear the site. |
| ACCESS & DRIVEWAYS | Satisfy requirements below for cuts, fills, retaining walls and drainage. Council specifications for grades may need to be modified. Driveways and parking areas may need to be fully supported on piers. | Excavate and fill for site access before geotechnical advice. |
| EARTHWORKS | Retain natural contours wherever possible. | Indiscriminatory bulk earthworks. |
| CUTS | Minimise depth. Support with engineered retaining walls or batter to appropriate slope. Provide drainage measures and erosion control. | Large scale cuts and benching. Unsupported cuts. Ignore drainage requirements |
| FILLS | Minimise height. Strip vegetation and topsoil and key into natural slopes prior to filling. Use clean fill materials and compact to engineering standards. Batter to appropriate slope or support with engineered retaining wall. Provide surface drainage and appropriate subsurface drainage. | Loose or poorly compacted fill, which if it fails, may flow a considerable distance including onto property below. Block natural drainage lines. Fill over existing vegetation and topsoil. Include stumps, trees, vegetation, topsoil, boulders, building rubble etc in fill. |
| ROCK OUTCROPS & BOULDERS | Remove or stabilise boulders which may have unacceptable risk. Support rock faces where necessary. | Disturb or undercut detached blocks or boulders. |
| RETAINING WALLS | Engineer design to resist applied soil and water forces. Found on rock where practicable. Provide subsurface drainage within wall backfill and surface drainage on slope above. Construct wall as soon as possible after cut/fill operation. | Construct a structurally inadequate wall such as sandstone flagging, brick or unreinforced blockwork. Lack of subsurface drains and weepholes. |
| FOOTINGS | Found within rock where practicable. Use rows of piers or strip footings oriented up and down slope. Design for lateral creep pressures if necessary. Backfill footing excavations to exclude ingress of surface water. | Found on topsoil, loose fill, detached boulders or undercut cliffs. |
| SWIMMING POOLS | Engineer designed. Support on piers to rock where practicable. Provide with under-drainage and gravity drain outlet where practicable. Design for high soil pressures which may develop on uphill side whilst there may be little or no lateral support on downhill side. | |
| DRAINAGE | | |
| SURFACE | Provide at tops of cut and fill slopes. Discharge to street drainage or natural water courses. Provide general falls to prevent blockage by siltation and incorporate silt traps. Line to minimise infiltration and make flexible where possible. Special structures to dissipate energy at changes of slope and/or direction. | Discharge at top of fills and cuts. Allow water to pond on bench areas. |
| SUBSURFACE | Provide filter around subsurface drain. Provide drain behind retaining walls. Use flexible pipelines with access for maintenance. Prevent inflow of surface water. | Discharge roof runoff into absorption trenches. |
| SEPTIC & SULLAGE | Usually requires pump-out or mains sewer systems; absorption trenches may be possible in some areas if risk is acceptable. Storage tanks should be water-tight and adequately founded. | Discharge sullage directly onto and into slopes. Use absorption trenches without consideration of landslide risk. |
| EROSION CONTROL & LANDSCAPING | Control erosion as this may lead to instability. Revegetate cleared area. | Failure to observe earthworks and drainage recommendations when landscaping. |


DRAWINGS AND SITE VISITS DURING CONSTRUCTION

| | | |
|-------------|---|--|
| DRAWINGS | Building Application drawings should be viewed by geotechnical consultant | |
| SITE VISITS | Site Visits by consultant may be appropriate during construction/ | |


INSPECTION AND MAINTENANCE BY OWNER

| | | |
|------------------------|--|--|
| OWNER'S RESPONSIBILITY | Clean drainage systems; repair broken joints in drains and leaks in supply pipes. Where structural distress is evident see advice. If seepage observed, determine causes or seek advice on consequences. | |
|------------------------|--|--|

EXAMPLES OF **GOOD** HILLSIDE PRACTICE



EXAMPLES OF **POOR** HILLSIDE PRACTICE



CERTIFICATE OF QUALIFIED PERSON – ASSESSABLE ITEM

Section 321

Form **55**

To: Owner /Agent
 Address
 Suburb/postcode

Qualified person details:

Qualified person:
Address: Phone No:
 Fax No:
Licence No: Email address:

Qualifications and Insurance details: (description from Column 3 of the Director's Determination - Certificates by Qualified Persons for Assessable Items)

Speciality area of expertise: (description from Column 4 of the Director's Determination - Certificates by Qualified Persons for Assessable Items)

Details of work:

Address: Lot No:
 Certificate of title No:
The assessable item related to this certificate: (description of the assessable item being certified)
Assessable item includes –

- a material;
- a design
- a form of construction
- a document
- testing of a component, building system or plumbing system
- an inspection, or assessment, performed

Certificate details:

Certificate type: (description from Column 1 of Schedule 1 of the Director's Determination - Certificates by Qualified Persons for Assessable Items n)

This certificate is in relation to the above assessable item, at any stage, as part of - (tick one)

building work, plumbing work or plumbing installation or demolition work: ☒

or

a building, temporary structure or plumbing installation: ☐

In issuing this certificate the following matters are relevant –

| | |
|------------------------|--|
| Documents: | AS2870 Site Classification and AS4055 Wind Classification dated 24 November 2023 |
| Relevant calculations: | |
| References: | AS2870 – 2011, AS4055 – 2021 Appendix G, Landslide Risk Management, Journal and News of the Australian Geomechanics Society Volume 42 No 1 March 2007 |

Substance of Certificate: (what it is that is being certified)

Foundation and wind classification


Scope and/or Limitations

Footings to be bedded / piered into competent material as per report.

Footings to inspected by engineer prior to pour.

Limitations as per section 9.0 of site investigation report dated 24 November 2023

I certify the matters described in this certificate.

| | | | |
|-------------------|---|--------------------------|---------------------|
| Qualified person: | <div>Signed: JOE HEPPER </div> | Certificate No: H2750 | Date: 24/11/2023 |
|-------------------|---|--------------------------|---------------------|

SITE INVESTIGATION REPORT

ON-SITE WASTEWATER MANAGEMENT SYSTEM ASSESSMENT REPORT

CLIENT:
J & J FISHER



Sorell Council

Development Application: 5.2024.266.1 -
Response to Request for Information P2.pdf

Plans Reference: P2
Date received: 27.02.2025

PROJECT ADDRESS:
12 EAST STREET
DODGES FERRY 7173

PROPOSED DEVELOPMENT:
THREE – BEDROOM DWELLING

FILE NUMBER:
H2750

DATE:
20 SEPTEMBER 2024

HED CONSULTING
UNIT 2, 1 LIVERPOOL STREET, HOBART 7000
03 6146 0334 info@hed-consulting.com.au

HED
CONSULTING

1. Executive Summary

The subject land is located at 12 East Street, Dodges Ferry. The development proposal includes the construction of a three – bedroom residential dwelling and requires an onsite wastewater management system. The site investigation has been conducted in accordance with AS1547:2012 *On-site domestic-wastewater management*. A summary of the report is detailed in the table below.

| Analysis | Observations / Results |
|---------------------------------|---|
| Soil category: | 1 |
| Estimated permeability: | 3m/day |
| Long Term Acceptance Rate: | 20mm/day |
| Geology: | Triassic dominantly quartz sandstone |
| Refusal depth: | No refusal (min. 2.5m) |
| Modified Emerson Crumb test: | Non - dispersive |
| Type of OWMS: | Dual – purpose septic tank & absorption bed |
| Land application area required: | 30m ² (total wetted area) |

2. Client and Site Location

| | Information |
|------------------|-----------------------------|
| Client name: | J & J Fisher |
| Site address: | 12 East Street Dodges Ferry |
| Property ID: | 5914901 |
| Title Reference: | 79621/6 |

3. Site information

| Site information | Results |
|----------------------|--|
| Size of development: | Three – bedroom dwelling |
| Services available: | Power & telecommunications |
| Zoning: | Low Density Residential |
| Tenure: | Private freehold |
| Permit Authority: | Sorell Council |
| Planning Overlays: | Southern Beaches On-site Waste Water and Stormwater Management Specific Area Plan, Airport obstacle limitation area & Low landslip hazard band |

4. Site visit

| Site investigation | Observations / Results |
|-----------------------------|---|
| Date of site investigation: | 17/9/2024 |
| Slope: | 30-34% |
| Aspect: | South - east |
| Rainfall: | 14.1mm (preceding two weeks) ¹ |
| Drainage: | Well draining |
| Vegetation | Grass and minor trees |
| Erosion: | None |

¹ Bureau of Meteorology, <http://www.bom.gov.au>, Daily Rainfall Sorell (Abbatoirs)

5. Soil Profile

Bore holes were conducted to gather information on the soil characteristics and depth to limiting layer. The below soil profile is typical of the bore holes conducted at the land application area.

BH01 & BH02

| Soil depth (mm) | Soil Description | Soil Category |
|-----------------|---|-----------------------|
| 0-300 | Brown SAND, trace rootlets, moist, loose. | 1 – GRAVELS AND SANDS |
| 300-2500+ | Brown – white SAND, medium grained, rounded, moist, medium dense. | 1 – GRAVELS AND SANDS |

No ground water was observed in any bore hole.

The soil is classed as soil category 1 – Gravels and sands for purposes of AS1547:2012. A long - term acceptance rate (LTAR) of 20mm/day has been adopted. Borehole localities are provided in the appendix of this report.

6. Wastewater Load & Total Wetted Area Required

The wastewater load is calculated from AS1547:2012.

| | |
|-----------------------------|----------------------------|
| Number of bedroom(s): | 3 |
| Number of people: | 5 |
| Individual wastewater load: | 120 (tank water supply) |
| Total wastewater load: | 600L/day |
| Long term acceptance rate: | 20mm/day (primary treated) |
| Total wetted area required: | 300m ² |

7. Site limitations and risks

The attached 'Trench3.0' program site capability and environment sensitivity reports detail several factors and risks associated with onsite wastewater disposal. Alerts will be flagged when some factors are 'high risk.' These factors need to be addressed and decreased to a tolerable risk by implementing design risk reduction measures. These measures are detailed in the text box of both reports and may be expanded upon further in this report.

The limitations of the site include the steep slope angle. These limitations can be overcome by careful installation of the absorption trenches. A bench should be created for the excavator to operate in a safe manner.

8. Onsite wastewater management system

Primary treatment (Min. 3000L dual – purpose septic tank)

All wastewater from the dwelling shall be gravity – fed to a minimum of a 3000-litre dual – purpose septic tank. This is the ‘working capacity’ not total volume.

Land application area

The primary treated wastewater shall be gravity fed to the land application area. This area shall consist of 30m² of total wetted area. This can be achieved by installing a single absorption bed with a length of 15m and width of 2m.

Minimum setbacks of the land application area shown below:

| | |
|---|------|
| Upslope & cross gradient property boundary: | 1.5m |
| Down slope property boundary: | 10m |
| Down slope surface water: | 100m |

A further minimum area of 30m² shall be a ‘reserve’ area. Refer to attached construction notes, drawings, and site plan for further information.

The bed shall be installed when the weather is fine. Avoid excavation when the soil is wet to avoid smearing any clay. The excavator should be fitted with ‘raker teeth’ and excavated in small sections to avoid compaction.

If rain is forecast cover any open parts of the bed. Always excavate perpendicular to the line of fall (parallel to contours) and make sure inverts are level.

9. OMWS Designer Inspection

The OWMS must be inspected by the designer to issue an OWMS Installation Certificate. This inspection is a requirement of the plumbing permit issued by the permit authority.

Please email info@hed-consulting.com.au or phone 03 6146 0334 before works begin on the OWMS to arrange a date and time for the inspection.

10. Operation & Maintenance Guidelines

This OWMS has been assessed to perform in accordance with the attached loading certificate. Regular maintenance is essential for the long-term performance of any OWMS. Maintenance guidelines are shown below. This is not a complete list and other maintenance guidelines should be sought from the manufacturer and the permit authority.

Primary treatment (Septic tank)

- Septic tank must be protected from vehicle traffic to avoid damage.
- Kitchen waste such as grease and fats shall be removed and disposed of into a bin before washing.
- Install sink waste plugs to keep out possible solids entering the OWMS.
- Do not install a garbage grinder.
- Do not dispose of hygiene products into the OWMS.
- Use bio – degradable soaps and low – phosphorus cleaning products.
- Do not put powerful bleachers, chemicals, and paint into the OWMS.
- Try and space out water usage as much as possible to avoid peaks loading.
- Septic tank to be pumped out / de-sludged at a maximum of every 3-5 years.

Land application area (Secondary treatment)

- Land application area to be protected from all vehicle traffic (including ride – on mowers) and regular foot traffic (no paths).
- Access to the land application area shall be discouraged. The land application area is not to be used as a play area for children.
- The reserve area (if required) shall not be built upon and access to this area shall also be discouraged.

11. Report limitations

Site Investigation:

Site investigations are conducted in accordance with clause 2.4 of AS1547:2012. The aim of a site investigation is to obtain information about the soil at the location of the proposed land application area. The location of the bore holes is based on information supplied from the client and where is deemed necessary by HED Consulting. The investigation only applies to this part of the site and the results and recommendations of this report should not be used for any other part of the site.

Soil testing:

Soil samples are collected and tested in accordance with Appendix E of AS1547:2012. Emersion testing is conducted in accordance with Dispersive Soils and their Management, Technical Reference Manual, Marcus Hardie – 2009. This test reveals whether clay is dispersive or not. The test is not always accurate however it is recognized as a reliable and quick way to test for dispersion.

Wastewater load:

The report is based on wastewater load as per the attached loading certificate. HED Consulting accepts no responsibility for the performance of the OWMS if the wastewater load exceeds the amount shown on the loading certificate.

12. Appendix

12.1 OWMS Construction Notes

Primary treatment (Septic tank)

- The septic tank shall be buried with the opening accessible at the natural surface.
- The tank shall also be placed in a location where vehicular access is possible for desludging / pump out purposes.
- The septic tank opening shall be easily accessible for inspection and maintenance requirements.
- The septic tank shall be sealed to prevent stormwater intrusion.

-
- The septic tank shall have a minimum working volume of 3000 litres.

Land application area (LAA)

The absorption bed has been designed to comply with the performance requirements of AS/NZS147:2012.

- The LAA shall be kept clear of all traffic (including people).
- The LAA shall be prepared by removing tree vegetation and backfilling any holes with sandy topsoil.
- Construction of the absorption bed shall be done when the weather is fine, and the soil is relatively dry.
- The absorption bed shall be constructed parallel to the contours.
- The base of the bed shall be made flat.
- The bed shall be installed as per the attached diagram and at the location as per the attached site plan.
- SITE INSPECTION STAGE – The pipework of the modified bed shall be inspected by the designer before the bed is backfilled with sandy topsoil.
- Topsoil must be good quality with some organic matter to promote vegetation growth.
- Fast growing, shallow root vegetation with a high transpiration capacity shall be planted in the topsoil and the area down slope of the bed.
- A list of suitable vegetation is provided with this report. Your council and local nursery can also advise on suitable plants.

12.2 OWMS Trench Reports, Construction Diagrams, Site Plan, Compliance to OWMS Guidelines & Risk Assessment

See attached.

12.3 OWMS Loading Certificate

See attached.

12.4 Form 55 (Site and Soil Evaluation) & Form 35 (OWMS Design)

See attached.

Assessment Report
Onsite Wastewater Management Assessment

Assessment for J & J Fisher C/- Matt Kennedy
admin@matt-kennedy.com.au
Assessed site(s) 12 East Street Dodges Ferry
Local authority Sorell Council

Assess. Date 20-Sep-24
Ref. No. H2750
Site(s) inspected 17-Sep-24
Assessed by J Hepper

This report summarises wastewater volumes, climatic inputs for the site, soil characteristics and system sizing and design issues. Site Capability and Environmental sensitivity issues are reported separately, where 'Alert' columns flag factors with high (A) or very high (AA) limitations which probably require special consideration for system design(s). Blank spaces on this page indicate data have not been entered into TRENCH.

Wastewater Characteristics

Wastewater volume (L/day) used for this assessment = 600 (using a method independent of the no. of bedrooms)
Septic tank wastewater volume (L/day) = 200
Sullage volume (L/day) = 400
Total nitrogen (kg/year) generated by wastewater = 7.3
Total phosphorus (kg/year) generated by wastewater = 3.3

Climatic assumptions for site

(Evapotranspiration estimated using mean max. daily temperatures)

| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec |
|----------------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| Mean rainfall (mm) | 40 | 38 | 39 | 43 | 42 | 37 | 45 | 49 | 42 | 49 | 48 | 52 |
| Adopted rainfall (R, mm) | 44 | 41 | 42 | 47 | 46 | 40 | 49 | 53 | 46 | 53 | 52 | 57 |
| Retained rain (Rr, mm) | 31 | 29 | 29 | 33 | 32 | 28 | 34 | 37 | 32 | 37 | 36 | 40 |
| Max. daily temp. (deg. C) | 22 | 22 | 21 | 18 | 15 | 13 | 12 | 13 | 15 | 17 | 19 | 21 |
| Evapotrans (ET, mm) | 82 | 69 | 66 | 53 | 43 | 47 | 45 | 48 | 54 | 63 | 68 | 78 |
| Evapotrans. less rain (mm) | 51 | 40 | 36 | 20 | 11 | 19 | 10 | 11 | 22 | 26 | 32 | 38 |

Annual evapotranspiration less retained rain (mm) = 317

Soil characteristics

Texture = Sand Category = 1 Thick. (m) = 3
Adopted permeability (m/day) = 3 Adopted LTAR (L/sq m/day) = 20 Min depth (m) to water = 3

Proposed disposal and treatment methods

Proportion of wastewater to be retained on site: All wastewater will be disposed of on the site
The preferred method of on-site primary treatment: In dual purpose septic tank(s)
The preferred method of on-site secondary treatment: In-ground
The preferred type of in-ground secondary treatment: Trench(es)
The preferred type of above-ground secondary treatment: None
Site modifications or specific designs: Not needed

Suggested dimensions for on-site secondary treatment system

Total length (m) = 15
Width (m) = 2
Depth (m) = 0.25
Total disposal area (sq m) required = 60
comprising a Primary Area (sq m) of: 30
and a Secondary (backup) Area (sq m) of: 30

Sufficient area is available on site

Comments

The three bedroom / five people dwelling will require a minimum total wetted area of 30m².

HED Consulting
Land suitability and system sizing for on-site wastewater management
Trench 3.0 (Australian Institute of Environmental Health)

Site Capability Report
Onsite Wastewater Management Assessment

Assessment for J & J Fisher C/- Matt Kennedy
admin@matt-kennedy.com.au
Assessed site(s) 12 East Street Dodges Ferry
Local authority Sorell Council

Assess. Date 20-Sep-24
Ref. No. H2750
Site(s) inspected 17-Sep-24
Assessed by J Hepper

This report summarises data relating to the physical capability of the assessed site(s) to accept wastewater. Environmental sensitivity and system design issues are reported separately. The 'Alert' column flags factors with high (A) or very high (AA) site limitations which probably require special consideration in site acceptability or for system design(s). Blank spaces indicate data have not been entered into TRENCH.

| Alert | Factor | Units | Value | Confid level | Limitation | | Remarks |
|-------|-----------------------------|------------------------|-------|--------------|------------|----------|-----------------------------|
| | | | | | Trench | Amended | |
| | Expected design area | sq m | 1,185 | High | Low | | |
| | Density of disposal systems | /sq km | 200 | High | Very high | Moderate | Other factors lessen impact |
| | Slope angle | degrees | 18 | V. high | Very high | Moderate | Other factors lessen impact |
| | Slope form | Straight simple | | V. high | Low | | |
| | Surface drainage | Good | | Mod. | Very low | | |
| | Flood potential | Site floods <1:100 yrs | | High | Very low | | |
| | Heavy rain events | Infrequent | | Mod. | Moderate | | |
| | Aspect (Southern hemi.) | Faces SE or SW | | V. high | High | Moderate | Other factors lessen impact |
| | Frequency of strong winds | Common | | High | Low | | |
| | Wastewater volume | L/day | 600 | High | Moderate | | |
| | SAR of septic tank effluent | | 1.6 | Mod. | Low | | |
| | SAR of sullage | | 2.8 | High | Moderate | | |
| | Soil thickness | m | 3.0 | High | Very low | | |
| | Depth to bedrock | m | 3.0 | V. high | Very low | | |
| | Surface rock outcrop | % | 0 | High | Very low | | |
| | Cobbles in soil | % | 0 | High | Very low | | |
| | Soil pH | | 6.0 | Mod. | Low | | |
| | Soil bulk density | gm/cub. cm | 1.6 | Mod. | Moderate | | |
| | Soil dispersion | Emerson No. | 8 | Mod. | Very low | | |
| | Adopted permeability | m/day | 3 | Mod. | Very high | Moderate | Other factors lessen impact |
| | Long Term Accept. Rate | L/day/sq m | 20 | Mod. | Low | | |

Comments

Wastewater to be treated to acceptable level within the property boundaries. The land has a steep slope angle, care should be taken when installing the onsite wastewater management system. The site has a south - east aspect but does receive good wind and sun exposure. Elevated permeability due to deep sandy soil profile.

HED Consulting
Land suitability and system sizing for on-site wastewater management
Trench 3.0 (Australian Institute of Environmental Health)

Environmental Sensitivity Report
Onsite Wastewater Management Assessment

Assessment for J & J Fisher C/- Matt Kennedy
admin@matt-kennedy.com.au
Assessed site(s) 12 East Street Dodges Ferry
Local authority Sorell Council


Assess. Date 20-Sep-24
Ref. No. H2750
Site(s) inspected 17-Sep-24
Assessed by J Hepper

This report summarises data relating to the environmental sensitivity of the assessed site(s) in relation to applied wastewater. Physical capability and system design issues are reported separately. The 'Alert' column flags factors with high (A) or very high (AA) limitations which probably require special consideration in site acceptability or for system design(s). Blank spaces indicate data have not been entered into TRENCH.

| Alert | Factor | Units | Value | Confid level | Limitation | | Remarks |
|-------|--------------------------------|------------------------|-------|--------------|------------|----------|-----------------------------|
| | | | | | Trench | Amended | |
| | Cation exchange capacity | mmol/100g | 15 | Mod. | Very high | Moderate | Other factors lessen impact |
| | Phos. adsorp. capacity | kg/cub m | 0.2 | Mod. | High | Moderate | Other factors lessen impact |
| | Annual rainfall excess | mm | -317 | High | Very low | | |
| | Min. depth to water table | m | 3 | Mod. | Very low | | |
| | Annual nutrient load | kg | 10.6 | High | Moderate | | |
| | G'water environ. value | Agric sensit/dom irrig | | Mod. | Moderate | | |
| | Min. separation dist. required | m | 8 | High | Very low | | |
| | Risk to adjacent bores | Very low | | Mod. | Very low | | |
| | Surf. water env. value | Recreational | | Mod. | High | Moderate | Other factors lessen impact |
| | Dist. to nearest surface water | m | 350 | High | Low | | |
| | Dist. to nearest other feature | m | 8 | High | Very high | Moderate | Other factors lessen impact |
| | Risk of slope instability | Moderate | | High | Moderate | | |
| | Distance to landslip | m | 200 | Mod. | Low | | |

Comments

The soil has a low cation exchange and phosphorus adsorption capacity. The planting of vegetation will enhance nutrient uptake. No groundwater was intercepted within 2.5m of the ground surface. 'Trench 3.0' indicates a viral die-off distance of 8m thus distance to nearest surface water and nearest other feature (down slope property boundary) is deemed acceptable.



PLAN LAYOUT

SCALE 1:50 @ A3


DISTRIBUTION PIPEWORK: MIN80MM DIA UPVC PIPE (LATERALS). 6MM DIA PERFORATIONS TO BE DRILLED INTO EACH LATERAL @ 75MM INTERNALS. ALTERNATE EACH SIDE OF PIPE AT OR JUST BELOW MID-HEIGHT.

SINGLE 6MM PERFORATION TO BE DRILLED INTO BASE OF EACH LATERAL (LOCATED AT CENTRE OF EACH LATERAL)

ALL PIPEWORK TO BE LEVEL USING A LASER LEVEL


700MM LATERAL SPACINGS FROM SIDE WALL AND 600MM BETWEEN LATERALS

SEE DRAIN DETAIL



SECTION LAYOUT

SCALE 1:25 @ A3



DRAIN DETAIL (NTS)



250MM DEPTH DISTRIBUTION AGGREGATE (20-40MM GRAVEL)



SANDY LOAM TOPSOIL



VEGETATION WITH A HIGH TRANSPIRATION CAPACITY AND ABILITY TO TOLERATE WET SOIL CONDITIONS



SEE ATTACHED PLANT LIST



www.hed-consulting.com.au
info@hed-consulting.com.au

CLIENT
J & J FISHER

SITE ADDRESS
12 EAST STREET DODGES FERRY 7173

FILENAME
H2750

DATE
20/9/2024

DRAWN
J H

SCALE
AS
SHOWN

COMMENTS

CERTIFIED

ENGINEER

List of plants suitable for Aerobic Waste Water Treatment Systems

| Common plant name | Soil type | | | | | | | Botanical name |
|---|-----------|-----|--------|------|------|------|---------------|---------------------------------|
| | Wet | Dry | Margin | Clay | Sand | Loam | Salt tolerant | Genus and species |
| Grasses & sedges | | | | | | | | |
| southern cordrush | ✓ | | ✓ | ✓ | ✓ | | | <i>Baloskian australe</i> |
| tassel cordrush | ✓ | | ✓ | ✓ | ✓ | ✓ | | <i>Baloskian tetaphyllum</i> |
| tall sedge | ✓ | | ✓ | ✓ | | ✓ | | <i>Carex appressa</i> |
| tassell sedge | ✓ | | ✓ | ✓ | | ✓ | | <i>Carex fascicularis</i> |
| curly sedge | | ✓ | ✓ | ✓ | | ✓ | | <i>Carex tasmanica</i> |
| spreading flaxlily | | ✓ | ✓ | ✓ | ✓ | ✓ | | <i>Dianella revoluta</i> |
| forest flaxlily | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | | <i>Dianella tasmanica</i> |
| western flag-iris | ✓ | | ✓ | ✓ | ✓ | ✓ | | <i>Diplarrena latifolia</i> |
| white flag-iris | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | | <i>Diplarrena moraea</i> |
| knobby clubsedge | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | <i>Ficini nodosa</i> |
| cutting grass | ✓ | | ✓ | ✓ | ✓ | ✓ | | <i>Gahnia grandis</i> |
| sea rush | ✓ | | ✓ | ✓ | ✓ | ✓ | ✓ | <i>Juncus kraussii</i> |
| pale rush | ✓ | | ✓ | ✓ | ✓ | ✓ | | <i>Juncus pallidus</i> |
| sagg | | ✓ | ✓ | ✓ | ✓ | ✓ | | <i>Lomandra longifolia</i> |
| silver tussockgrass | ✓ | ✓ | ✓ | ✓ | | ✓ | | <i>Poa labillardierei</i> |
| velvet tussockgrass | | ✓ | ✓ | ✓ | | ✓ | | <i>Poa rodwayi</i> |
| Low shrubs (up to 1.5m) | | | | | | | | |
| wiry bauera | | | ✓ | | | ✓ | | <i>Bauera rubiodes</i> |
| hop native-primrose | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | | <i>Goodenia ovata</i> |
| slender honeymyrtle | ✓ | | ✓ | ✓ | | ✓ | | <i>Melaleuca gibbosa</i> |
| Tall shrubs/trees (2-5m) | | | | | | | | |
| silver wattle | | ✓ | ✓ | ✓ | ✓ | ✓ | | <i>Acacia dealbata</i> |
| blackwood | ✓ | | ✓ | ✓ | | ✓ | | <i>Acacia melanoxylon</i> |
| arching wattle | ✓ | | ✓ | ✓ | | ✓ | | <i>Acacia riceana</i> |
| prickly moses | | | ✓ | ✓ | ✓ | ✓ | | <i>Acacia verticillata</i> |
| yellow bottlebrush | | ✓ | ✓ | ✓ | | ✓ | | <i>Callistemon pallidus</i> |
| prickly bottlebrush | ✓ | | ✓ | ✓ | | ✓ | | <i>Callistemon viridiflorus</i> |
| native hop | | ✓ | ✓ | ✓ | ✓ | ✓ | | <i>Dodonaea viscosa</i> |
| smoky teatree | | ✓ | ✓ | | ✓ | ✓ | | <i>Leptospermum glaucescens</i> |
| woolly teatree | ✓ | ✓ | ✓ | ✓ | | ✓ | | <i>Leptospermum lanigerum</i> |
| shiny teatree | ✓ | | ✓ | ✓ | | ✓ | | <i>Leptospermum nitidum</i> |
| river teatree | ✓ | | ✓ | ✓ | | ✓ | | <i>Leptospermum riparium</i> |
| common teatree | | ✓ | ✓ | ✓ | ✓ | ✓ | | <i>Leptospermum scoparium</i> |
| warty paperbark | ✓ | | ✓ | ✓ | | ✓ | | <i>Melaleuca pustulata</i> |
| swamp honeymyrtle | ✓ | | ✓ | ✓ | | ✓ | | <i>Melaleuca squamea</i> |
| scented paperbark | ✓ | | ✓ | ✓ | | ✓ | | <i>Melaleuca squarrosa</i> |
| common dogwood | ✓ | | ✓ | ✓ | | ✓ | | <i>Pomaderris apetala</i> |
| Trees (>10m) | | | | | | | | |
| black gum | ✓ | | ✓ | ✓ | | ✓ | | <i>Eucalyptus ovata</i> |
| Exotics | | | | | | | | |
| Pittosporum bicolor | | | | | | | | |
| Pittosporum Tenuifolium | | | | | | | | |
| coleonema | | | | | | | | |
| acemena (lilypilly) | | | | | | | | |
| ceanothus | | | | | | | | |
| hebe all varieties are very good with the exception of hebe emerald green | | | | | | | | |
| penstemon | | | | | | | | |
| abelia | | | | | | | | |
| buxus sempervirens | | | | | | | | |

* Fruit trees are not recommended in an irrigation area.


Note: For information only. Please consult your local nursery before finalising the plant choices to suit your locality and site conditions.

Source: Clarence City Council Infosheet, Plants suitable for Aerobic Waste water Treatment Systems

ONSITE WASTEWATER SITE PLAN

CLIENT: J & J FISHER
ADDRESS: 12 EAST STREET DODGES FERRY
PROP ID: 5914901 CT: 79621/6
DATE: 20/9/2024
VERSION: 1.0
DRAWN BY: JH

HED CONSULTING
UNIT 2, 1 LIVERPOOL STREET, HOBART 7000
P 03 6146 0334 / E info@hed-consulting.com.au



SOR – S2.0 Southern Beaches On-site Waste Water and Stormwater Management Specific Area Plan

...SOR – S2.7 Development Standards for Buildings and Works

SOR-S2.7.1 On-site waste water

| Objective: | That the site has a sufficient and suitable area of land available for on-site waste water management. | | |
|---|--|---|--|
| Acceptable Solutions | | Performance Criteria | Development Response to Achieve Compliance |
| A1 Development must: <ul style="list-style-type: none"> (a) not cover less than 20% of the site; (b) not located on land shown on an overlay map in the relevant Local Provisions Schedule, as within; <ul style="list-style-type: none"> (i) a flood-prone hazard area; (ii) a landslip hazard area; (iii) a coastal erosion hazard area; (iv) a waterway and coastal protection area; or (v) a coastal inundation hazard area; (c) be located on a site with a soil depth of at least 1.5m; (d) be located on a site where the average gradient of the land does not exceed 10%; and (e) in the case of a dwelling, provide 65m² of land for wastewater land application area per bedroom | | P1 The site must provide sufficient area for management of on-site waste water, having regard to: <ul style="list-style-type: none"> (a) the topography of the site; (b) the capacity of the site to absorb wastewater; (c) the size and shape of the site; (d) the existing buildings and any constraints imposed by existing development; (e) the area of the site to be covered by the proposed development; (f) the provision for landscaping, vehicle parking, driveways and private open space; | Proposed LAA complies with P1. The Onsite Wastewater Management System Report satisfies the performance criteria. |

| | | |
|--|---|------------------------|
| <p>which is located at least 1.5m from an upslope or side slope boundary and 5m from a downslope boundary.</p> | <p>(g) any adverse impacts on the quality of ground surface and coastal waters;</p> <p>(h) any adverse environmental impact on surrounding properties and the locality; and</p> <p>(i) any written advice from a suitably qualified person (onsite waste water management) about the adequacy of the on-site waste water management system.</p> | |
| <p>A2</p> <p>An outbuilding, driveway or parking area or addition or alteration to a building must not encroach onto an existing land application area.</p> | <p>P2</p> <p>An outbuilding, driveway or parking area or addition or alteration to a building must demonstrate that there is sufficient suitable area of land available for a new on-site waste water management system.</p> | <p>Not applicable.</p> |

WASTEWATER DESIGN COMPLIANCE TO DIRECTOR'S GUIDELINES FOR ON-SITE WASTEWATER MANAGEMENT SYSTEMS

3. Standards for Wastewater Land Application Areas

3.1 Objective – PCA FP1.5 (a)-(c)

| Acceptable Solutions | Performance Criteria | Development Response to Achieve Compliance |
|--|---|---|
| A1 Horizontal separation distance for a building to a land application area must comply with one of the following: <ul style="list-style-type: none"> (a) be no less than 6m; (b) be no less than: <ul style="list-style-type: none"> (i) 3m from an upslope or level building; (ii) if primary treated effluent to be no less than 4m plus 1m for every degree of average gradient from a down slope building; (iii) if secondary treated effluent and subsurface application, no less than 2m plus 0.25m for every degree of average gradient from a down slope building | P1 The land application area (LAA) is located so that the risk of wastewater reducing the bearing capacity of a building's foundations is acceptably low. | Proposed LAA complies with A1. The LAA is a minimum 6m from any building. |
| A2 Horizontal separation distance from down slope surface water to a land application area must comply with (a) or (b) <ul style="list-style-type: none"> (a) be no less than 100m; or (b) be no less than the following: | P2 Horizontal separation distance from down slope surface water to a land application area must comply with all of the following: <ul style="list-style-type: none"> (a) setbacks must be consistent with AS/NZS1547 Appendix R; | Proposed LAA complies with A2(a). The LAA is a minimum 100m from the down slope surface water. |

| | | |
|---|---|--|
| <ul style="list-style-type: none"> (i) if primary treated effluent 15m plus 7m for every degree of average gradient to down slope surface water; or (ii) if secondary treated effluent and subsurface application, 15m plus 2m for every degree of average gradient to down slope surface water. | <ul style="list-style-type: none"> (b) a risk assessment in accordance with Appendix A of AS/NZS 1547 has been completed that demonstrates that the risk is acceptable. | |
| <p>A3</p> <p>Horizontal separation distance from a property boundary to a land application area must comply with either of the following:</p> <ul style="list-style-type: none"> (a) be no less than 40m from a property boundary; <p>or</p> <ul style="list-style-type: none"> (b) be no less than: <ul style="list-style-type: none"> (i) 1.5m from an upslope or level property boundary; and (ii) if primary treated effluent 2m for every degree of average gradient from a downslope property boundary; or (iii) if secondary treated effluent and subsurface application, 1.5m plus 1m for every degree of average gradient from a downslope property boundary. | <p>P3</p> <p>Horizontal separation distance from a property boundary to a land application area must comply with all of the following:</p> <ul style="list-style-type: none"> (a) setback must be consistent with AS/NZS 1547 Appendix R; and (b) a risk assessment in accordance with Appendix A of AS/NZS1547 has been completed that demonstrates that the risk is acceptable | <p>Proposed LAA complies with P3.</p> <p>The setback is consistent with AS/NZS 1547 Appendix R.</p> <p>A risk assessment in accordance with Appendix A of AS/NZS1547 has been completed that demonstrates that the risk is acceptable (see appendix of this report).</p> |

| | | |
|--|--|---|
| <p>A4</p> <p>Horizontal separation distance from a downslope bore, well or similar water supply to a land application area must be no less than 50m and not be within the zone of influence of the bore whether up or down gradient.</p> | <p>P4</p> <p>Horizontal separation distance from a downslope bore, well or similar water supply to a land application area must comply with all of the following:</p> <ul style="list-style-type: none"> (a) setback must be consistent with AS/NZS 1547 Appendix R; and (b) a risk assessment completed in accordance with Appendix A of AS/NZS 1547 demonstrates that the risk is acceptable. | <p>Proposed LAA complies with A4.</p> <p>The LAA is a minimum 50m from a downslope bore, well or similar water supply and not within the zone of influence of any bore.</p> |
| <p>A5</p> <p>Vertical separation distance between the groundwater and a land application area must be no less than:</p> <ul style="list-style-type: none"> (a) 1.5m if primary treated effluent; or (b) 0.6m if secondary treated effluent | <p>P5</p> <p>Vertical separation distance between groundwater and a land application area must comply with the following:</p> <ul style="list-style-type: none"> (a) setback must be consistent with AS/NZS 1547 Appendix R; and (b) a risk assessment completed in accordance with Appendix A of AS/NZS 1547 that demonstrates that the risk is acceptable. | <p>Proposed LAA complies with A5.</p> <p>The LAA has a minimum 1.5m vertical separation distance between the groundwater and LAA.</p> |
| <p>A6</p> <p>Vertical separation distance between a limiting layer and a land application area must be no less than:</p> <ul style="list-style-type: none"> (a) 1.5m if primary treated effluent; or (b) 0.6m if secondary treated effluent | <p>P6</p> <p>Vertical setback must be consistent with AS/NZS 1547 Appendix R.</p> | <p>Proposed LAA complies with A6.</p> <p>The LAA has a minimum 1.5m vertical separation distance between the limiting layer and LAA.</p> |

| | | |
|-------------------------------|--|---|
| <p>A7</p> <p>None.</p> | <p>P7</p> <p>A wastewater treatment unit must be located a sufficient distance from buildings or neighbouring properties so that emissions (odour, noise or aerosols) from the unit do not create an environmental nuisance to the residents of those properties.</p> <p>Note: Part 6 of the Building Act 2016 specifies requirements for protection work which apply to plumbing work including a wastewater treatment unit.</p> | <p>Proposed wastewater design complies with P7.</p> |
|-------------------------------|--|---|


HORIZONTAL AND VERTICAL SETBACK DISTANCES ASSESSMENT

ADAPTED FROM TABLE R1 OF AS1547:2012 - THIS TABLE TO BE USED IN CONJUNCTION WITH TABLE R2

| Site feature | Setback distance range (m) | Site constraint items of specific concern (See table R2) | Site specific assessment | Minimum setback distance required |
|--|---|---|--------------------------|-----------------------------------|
| | Horizontal setback distance (m) | | | |
| Property boundary | 1.5 - 50 | A, D, J | 8m | 8m |
| Buildings / houses | 2 - 6 | A, D, J | >6m | 6m |
| Surface water | 15 - 100 | A, B, D, E, F, G, J | >100m | 100m |
| Bore, well | 15 - 50 | A, C, H, J | >50m | 50m |
| Recreational areas (Children's play areas, swimming pools etc.) | 3 - 15 | A, E, J | >15m | 10m |
| In-ground water tank | 4 - 15 | A, E, J | >15m | 10m |
| Retaining wall and Embankments, escarpments, cuttings | 3.0m or 45° angle from toe of wall (whichever is greatest) | D, G, H | >3m | 3m |
| | Vertical setback distance (m) | | | |
| Groundwater | 0.6 – 1.5 | A, C, F, H, I, J | >1.5m | 1.5m |
| Hardpan or bedrock | 0.5 – 1.5 | A, C, J | >1.5m | 1.5m |

SITE CONSTRAINT SCALE FOR DEVELOPMENT OF SETBACK DISTANCES

ADAPTED FROM TABLE R2 OF AS1547:2012 - THIS TABLE TO BE USED IN CONJUNCTION WITH TABLE R1

| Item | Site/system feature | Constraint scale Lower ←  Higher Examples of constraint factors | | Sensitive features | Site specific assessment | Constraint assessment |
|------|-------------------------------|---|--|---|---|-----------------------|
| | | | | | | |
| A | Microbial quality of effluent | Effluent quality consistently producing ≤ 10 cfu/100 mL <i>E. Coli</i> (secondary treated effluent with disinfection) | Effluent quality consistently producing $\geq 10^6$ cfu/100 mL <i>E. Coli</i> (for example, primary treated effluent) | Groundwater and surface pollution hazard, public health hazard | Primary treated effluent | Medium |
| B | Surface water | Category 1 to 3 soils, no surface water down gradient within >100m, low rainfall area | Category 4 to 6 soils, permanent surface water <50m down gradient, high rainfall area, high resource/environmental value | Surface water pollution hazard for low permeable soils, low lying and poorly draining areas | Category 1 soils, down slope surface water >100m down gradient. | Low |
| C | Groundwater | Category 5 and 6 soils, low resource /environmental value | Category 1 and 2 soils, gravel aquifers, high resource/environmental value | Groundwater pollution hazard | Category 1 soils, no groundwater within 2.5m of surface | Low |
| D | Slope | 0 – 6% (surface effluent application) 0 – 10% (subsurface effluent application) | >10% (surface effluent application) >30% (subsurface effluent application) | Off – site export of effluent, erosion | 30% slope and subsurface application | Medium |

| Item | Site/system feature | Constraint scale Lower ←————→ Higher Examples of constraint factors | | Sensitive features | Site specific assessment | Constraint assessment |
|------|--|---|--|--|--|-----------------------|
| | | | | | | |
| E | Position of land application area in landscape | Downgradient of surface water, property boundary, recreational area | Upgradient of surface water, property boundary, recreational area | Surface water pollution hazard, off – site export of effluent | Property boundary min 9m. | Medium |
| F | Drainage | Category 1 and 2 soils, gentle sloping area | Category 6 soils, sites with visible seepage, moisture tolerant vegetation, low lying area | Groundwater pollution hazard | Category 1 soils, moderate - steep sloping land | Low |
| G | Flood potential | Above 1 in 20 year flood contour | Below 1 in 20 year flood contour | Off – site export of effluent, system failure, mechanical faults | Above 1 in 20 year flood contour | Low |
| H | Geology and soils | Category 3 and 4 soils, low porous regolith, deep, uniform soils | Category 1 and 6 soils, fractured rock, gravel aquifers, highly porous regolith | Groundwater pollution hazard for porous regolith and permeable soils | Category 1 soils, permeable soils | Medium |
| I | Landform | Hill crests, convex side slopes and plains | Drainage plains and incise channels | Groundwater pollution hazard, resurfacing hazard | Moderate - steep slope, straight simple drainage pattern | Low |
| J | Application method | Drip irrigation or subsurface application of effluent | Surface/above ground application of effluent | Off – site export of effluent, surface water pollution | Subsurface application of effluent | Low |

Note: Constraint assessment of Medium and High are discussed in the attached risk assessment.

RISK ASSESSMENT (IN ACCORDANCE TO APPENDIX A OF AS1547 : 2012)

CLIENT: J & J FISHER

SITE ADDRESS: 12 EAST STREET DODGES FERRY

PROPOSED TYPE OF WASTEWATER SYSTEM: DUAL PURPOSE SEPTIC TANK AND ABSORPTION BED

| Cause | Likelihood | Consequence | Risk | Factors that increase likelihood | Design risk reduction measures |
|--|------------|-------------|----------|---|--|
| Wastewater system hydraulic failure | Possible | Medium | Moderate | <ul style="list-style-type: none"> Excess solids discharged Inadequate hydraulic design of treatment plant of land application system | <p>The installation of water saving fixtures in the dwelling is recommended. Food waste disposal units should not be installed.</p> <p>The land application area has been designed for a wastewater load of 600L/day (5 people).</p> |
| Biological failure from power outage causing cessation of pumps and aerators | NA | NA | NA | <ul style="list-style-type: none"> Remote or poorly serviced power areas Faulty wiring | Gravity – fed system. |
| Wastewater biological failure from washout of bacteria | Unlikely | Minor | Low | <ul style="list-style-type: none"> Inadequate septic tank capacity Hydraulic overload | The septic tank shall have sufficient capacity for daily wastewater loads and potential shock loads. |
| Soil system failure in dispersive soils | Unlikely | Minor | Low | <ul style="list-style-type: none"> Clay | Non – dispersive soils. |
| Marginal soil conditions (Constraint assessment A, D, E & H) | Possible | Major | High | <ul style="list-style-type: none"> Poor draining medium to heavy clays Inadequate topsoil Inadequate vegetation South facing, poor exposure to sunlight Non – conservative design loading rate for soil type | <p>Vegetation shall be planted in the raised bed and surrounding area to enhance evapo – transpiration</p> <p>Topsoil has adequate depth and quality.</p> <p>Good exposure to sunlight and wind.</p> <p>Conservative DLR has been adopted.</p> |
| Limited available area (Constraint assessment E) | Possible | Minor | Low | <ul style="list-style-type: none"> Small lot size Steep slopes | Permeable soils. |

| | | | | | |
|--|----------|--------|----------|--|--|
| High rainfall or torrential downpours | Possible | Medium | Moderate | <ul style="list-style-type: none"> • Inappropriate type of land application system • Stormwater ingress / ponding • Poor draining soils • Inadequate topsoil and assimilation capacity | <p>Design based on rainfall data.</p> <p>Subsurface method of disposal maximise evapo – transpiration and limits absorption into the subsoil.</p> <p>Cut – off drain to be installed upslope of the LAA.</p> |
| Salinisation | Unlikely | Medium | Low | <ul style="list-style-type: none"> • High groundwater table | No groundwater intercepted. |
| Highly permeable soils or soils with preferential pathways | Possible | Medium | Moderate | <ul style="list-style-type: none"> • High groundwater table • Permeable gravel soils • Fissures in clay soils • Inadequate design of land application system | No groundwater intercepted. |



Sorell Council

Development Application: 5.2024.266.1 -
Response to Request for Information P2.pdf

Plans Reference: P2
Date received: 27.02.2025



AHEAD OF THE BUILD

PRE-CONSTRUCTION SERVICES FOR TASMANIAN HOMES

ONSITE WASTEWATER MANAGEMENT SYSTEM

LOADING CERTIFICATE as per clause 7.4.2 (d) of AS1547:2012

| | |
|--|--|
| Client: | J & J Fisher. |
| Site Address: | 12 East Street Dodges Ferry. |
| Permit Authority: | Sorell Council. |
| (i) System Capacity: | Individual person daily flow: 120 litres (tank water supply). Three bedroom / 5 people: 5 x 120 = 600 litres per day. |
| (ii) Summary of design criteria: | Effluent quality: Primary treated (dual – purpose septic tank). Land application system: Absorption bed. |
| (iii) The location and use of the 'reserve area' | There is room on the existing lot to provide a reserve land application area. See site plan for location. |
| (iv) Use of water efficient fittings, fixtures or appliances | It is recommended that water efficient fittings, fixtures and appliances are utilised. These includes maximum 4.5/3L toilets, 9L/min shower heads, aerator faucets and water conserving dishwashes and washing machines. |
| (v) Allowable variation from design flows (peak loading events) | The septic tank can accommodate variation in flows (peak and under loading) from normal domestic use. |
| (vi) Consequences of changes in loading | The Onsite Wastewater Management System (OWMS) can cope with a wastewater load from domestic use only. Additional organic loading from sink garbage grinders should be avoided. Use 'septic – safe' detergents and disinfectants and dilute to recommended levels. Bio - degradable soaps and low – phosphorus products are preferred. |
| (vii) Consequences of overloading the system | The OWMS is designed for a domestic wastewater loading of 600L / per day. Excessive loading (>600L/day) may result in failure of the system. This can include blockage of pipework, mechanical and / or pump failure, flooding of system, runoff from land application area and pooling of effluent. These failures may cause public health and / or environmental nuisance. |

HED CONSULTING
www.hed-consulting.com.au

info@hed-consulting.com.au
03 6146 0334

GROUND FLOOR, THE SANDSTONE BUILDING
1 LIVERPOOL STREET, HOBART

ABN:16 650 393 409



AHEAD OF THE BUILD

PRE-CONSTRUCTION SERVICES FOR TASMANIAN HOMES

| | |
|--|--|
| (viii) Consequences of underloading the system | Nil. |
| (ix) Consequences of lack of operation, maintenance, and monitoring attention | <p>All OWMS require maintenance and monitoring to ensure the system is working effectively. The septic tank should be de-sludged / pumped out every three to five years.</p> <p>The lack of maintenance and monitoring of the OWMS may cause public health and environmental nuisances such as foul odour, increase in likelihood of spreading infectious diseases, polluting surface and ground waters.</p> |
| (x) Any other relevant considerations related to the use of the system | <p>The OWMS shall be fenced if livestock has access to the site.</p> <p>Vehicle access over the OWMS is prohibited.</p> <p>Pedestrian access of the land application area shall be discouraged (no path over the area).</p> <p>The OWMS is not a play area for children.</p> <p>The land application area should be kept weed free.</p> |

CERTIFICATE OF QUALIFIED PERSON – ASSESSABLE ITEM

Section 321

Form **55**

To: J & J FISHER

Owner /Agent

C/- admin@matt-kennedy.com.au

Address

Suburb/postcode

Qualified person details:

Qualified person: JOE HEPPER

Address: UNIT 2, 1 LIVERPOOL STREET

Phone No: 03 6146 0334

HOBART

7000

Fax No:

Licence No: NA

Email address: info@hed-consulting.com.au

Qualifications and Insurance details:

BSc. major in geology and experience in environmental geology
PI Insurance - ABOUT UNDERWRITING
PN: ENG 20 000459

(description from Column 3 of the Director's Determination - Certificates by Qualified Persons for Assessable Items)

Speciality area of expertise:

Site and soil evaluation (and land application system design)

(description from Column 4 of the Director's Determination - Certificates by Qualified Persons for Assessable Items)

Details of work:

Address: 12 EAST STREET

Lot No: 6

DODGES FERRY

7173

Certificate of title No: 79621

The assessable item related to this certificate:

Site and soil evaluation

(description of the assessable item being certified)

Assessable item includes –

- a material;
- a design
- a form of construction
- a document
- testing of a component, building system or plumbing system
- an inspection, or assessment, performed

Certificate details:

Certificate type: On-site wastewater management – Site and soil evaluation (and land application system design)

(description from Column 1 of Schedule 1 of the Director's Determination - Certificates by Qualified Persons for Assessable Items n)

This certificate is in relation to the above assessable item, at any stage, as part of - (tick one)

building work, plumbing work or plumbing installation or demolition work: ☒

or

a building, temporary structure or plumbing installation: ☐

In issuing this certificate the following matters are relevant –

Documents:

Site Investigation Report, Site and Soil Evaluation dated 20 September 2024.

Relevant
calculations:

References:

AS1547: 2012

Substance of Certificate: (what it is that is being certified)

Site and soil evaluation for proposed onsite wastewater management system.


Scope and/or Limitations

I certify the matters described in this certificate.

Qualified person:

Signed:

JOE HEPPER



Certificate No:

H2750

Date:

20/9/2024

CERTIFICATE OF THE RESPONSIBLE DESIGNER

Section 94
Section 106
Section 129
Section 155

Form **35**

To: Owner name
 Address
 Suburb/postcode

Designer details:

Name: Category:
 Business name: Phone No:
 Business address:
 Fax No:
 Licence No: Email address:

Details of the proposed work:

Owner/Applicant Designer's project reference No.
 Address: Lot No:

 Type of work: Building work ☐ Plumbing work ☒ (X all applicable)

Description of work:

On-site wastewater management system

(new building / alteration /
addition / repair / removal /
re-erection
water / sewerage /
stormwater /
on-site wastewater
management system /
backflow prevention / other)

Description of the Design Work (Scope, limitations or exclusions): (X all applicable certificates)

| Certificate Type: | Certificate | Responsible Practitioner |
|-------------------|---|---|
| | <input type="checkbox"/> Building design | Architect or Building Designer |
| | <input type="checkbox"/> Structural design | Engineer or Civil Designer |
| | <input type="checkbox"/> Fire Safety design | Fire Engineer |
| | <input type="checkbox"/> Civil design | Civil Engineer or Civil Designer |
| | <input type="checkbox"/> Hydraulic design | Building Services Designer |
| | <input type="checkbox"/> Fire service design | Building Services Designer |
| | <input type="checkbox"/> Electrical design | Building Services Designer |
| | <input type="checkbox"/> Mechanical design | Building Service Designer |
| | <input checked="" type="checkbox"/> Plumbing design | Plumber-Certifier; Architect, Building Designer or Engineer |
| | <input type="checkbox"/> Other (specify) | |

Deemed-to-Satisfy: ☒ Performance Solution: ☐ (X the appropriate box)

Other details:

Design documents provided:

The following documents are provided with this Certificate –

Document description:

| | | |
|---------------------------------|-----------------------------|-----------------|
| Drawing numbers: V1.0 | Prepared by: HED Consulting | Date: 20/9/2024 |
| Schedules: V1.0 | Prepared by: HED Consulting | Date: 20/9/2024 |
| Specifications: V1.0 | Prepared by: HED Consulting | Date: 20/9/2024 |
| Computations: | Prepared by: | Date: |
| Performance solution proposals: | Prepared by: | Date: |
| Test reports: V1.0 | Prepared by: HED Consulting | Date: 20/9/2024 |

Standards, codes or guidelines relied on in design process:

AS1547: 2012

Director's Guidelines for On-site Wastewater Management Systems, Building Act 2016, 20 November 2017, version 2.0

Any other relevant documentation:**Attribution as designer:**

I, Manikandan Muthiah, am responsible for the design of that part of the work as described in this certificate;

The documentation relating to the design includes sufficient information for the assessment of the work in accordance with the *Building Act 2016* and sufficient detail for the builder or plumber to carry out the work in accordance with the documents and the Act;

This certificate confirms compliance and is evidence of suitability of this design with the requirements of the National Construction Code.

*Name: (print)**Signed**Date*

Designer:

MANIKANDAN MUTHIAH



20/9/2024

Licence No:

064518368

Assessment of Certifiable Works: (TasWater)

Note: single residential dwellings and outbuildings on a lot with an existing sewer connection are not considered to increase demand and are not certifiable.

If you cannot check ALL of these boxes, LEAVE THIS SECTION BLANK.

TasWater must then be contacted to determine if the proposed works are Certifiable Works.

I confirm that the proposed works are not Certifiable Works, in accordance with the Guidelines for TasWater CCW Assessments, by virtue that all of the following are satisfied:

- ☒ The works will not increase the demand for water supplied by TasWater
- ☒ The works will not increase or decrease the amount of sewage or toxins that is to be removed by, or discharged into, TasWater's sewerage infrastructure
- ☒ The works will not require a new connection, or a modification to an existing connection, to be made to TasWater's infrastructure
- ☒ The works will not damage or interfere with TasWater's works
- ☒ The works will not adversely affect TasWater's operations
- ☒ The work are not within 2m of TasWater's infrastructure and are outside any TasWater easement
- ☒ I have checked the LISTMap to confirm the location of TasWater infrastructure
- ☒ If the property is connected to TasWater's water system, a water meter is in place, or has been applied for to TasWater.

Certification:

I, Manikandan Muthiah being responsible for the proposed work, am satisfied that the works described above are not Certifiable Works, as defined within the *Water and Sewerage Industry Act 2008*, that I have answered the above questions with all due diligence and have read and understood the Guidelines for TasWater CCW Assessments.

Note: the Guidelines for TasWater Certification of Certifiable Works Assessments are available at: www.taswater.com.au

| | | | |
|-----------|--------------------|---|-----------|
| | Name: (print) | Signed | Date |
| Designer: | MANIKANDAN MUTHIAH |  | 20/9/2024 |

CERTIFICATE OF THE RESPONSIBLE DESIGNER

Section 94
Section 106
Section 129
Section 155

To: Owner name
 Address
 Suburb/postcode

Form **35**

Designer details:

Name: Category:
Business name: Phone No:
Business address:
 Fax No:
Licence No: Email address:

Details of the proposed work:

Owner/Applicant Designer's project reference No.
Address: Lot No:

Type of work: Building work ☒ Plumbing work ☐ (X all applicable)

Description of work:

Proposed dwelling

(new building / alteration /
addition / repair / removal /
re-erection
water / sewerage /
stormwater /
on-site wastewater
management system /
backflow prevention / other)

Description of the Design Work (Scope, limitations or exclusions): (X all applicable certificates)

| Certificate Type: | Certificate | Responsible Practitioner |
|-------------------|--|---|
| | <input type="checkbox"/> Building design | Architect or Building Designer |
| | <input type="checkbox"/> Structural design | Engineer or Civil Designer |
| | <input type="checkbox"/> Fire Safety design | Fire Engineer |
| | <input type="checkbox"/> Civil design | Civil Engineer or Civil Designer |
| | <input checked="" type="checkbox"/> Hydraulic design | Building Services Designer |
| | <input type="checkbox"/> Fire service design | Building Services Designer |
| | <input type="checkbox"/> Electrical design | Building Services Designer |
| | <input type="checkbox"/> Mechanical design | Building Service Designer |
| | <input type="checkbox"/> Plumbing design | Plumber-Certifier; Architect, Building Designer or Engineer |
| | <input type="checkbox"/> Other (specify) | |

Deemed-to-Satisfy: ☒ Performance Solution: ☐ (X the appropriate box)

Other details: This certificate covers the hydraulic design, onsite stormwater management of proposed development.

Design documents provided:

The following documents are provided with this Certificate –

Document description:

| | | |
|---------------------------------|--------------|------------|
| Drawing numbers: | Prepared by: | Date: |
| H2750 | D.C | 30/01/2025 |
| Sheets 50-A-101, 50-A-102 | | |
| Schedules: | Prepared by: | Date: |
| Specifications: | Prepared by: | Date: |
| Computations: | Prepared by: | Date: |
| Performance solution proposals: | Prepared by: | Date: |
| Test reports: | Prepared by: | Date: |

Standards, codes or guidelines relied on in design process:

AS3500..3; Australian Rainfall and Runoff
HED Consulting Site Investigation report dated 24 November 2023.

Any other relevant documentation:**Attribution as designer:**

I, Manikandan Muthiah, am responsible for the design of that part of the work as described in this certificate;

The documentation relating to the design includes sufficient information for the assessment of the work in accordance with the *Building Act 2016* and sufficient detail for the builder or plumber to carry out the work in accordance with the documents and the Act;

This certificate confirms compliance and is evidence of suitability of this design with the requirements of the National Construction Code.

| | | | |
|-------------|----------------------|---------------|-------------|
| | <i>Name: (print)</i> | <i>Signed</i> | <i>Date</i> |
| Designer: | Manikandan Muthiah | | 19/02/2025 |
| Licence No: | 06451868 | | |